

## **PART D - DETAIL SPECIFICATIONS**

### **D-1 SCOPE OF WORK**

#### **CUY-West Sixth Street Streetscape, Part 1, PID 89722**

Limits of work: West Lakeside Avenue to West St. Clair Avenue

Work includes:

- Pavement planing and asphalt overlay
- Curb bump-outs and relocation of existing granite curb.
- Renovation and expansion of planting beds around existing trees
- Installation of streetscaping items such as benches and bicycle racks
- Pavement markings
- All other associated work to complete the project.

#### **CUY-Professor Street Intersections, Part 2, PID 90218**

Limits of work: Intersections of Professor Street with West 10<sup>th</sup> Street, Literary Avenue, College Avenue and Jefferson Avenue

Work includes:

- Pavement planing and asphalt overlay within the intersections
- Curb bump-outs
- Decorative crosswalks
- Installation of streetscaping items such as decorative sidewalks
- Realignment of the West 10<sup>th</sup> Street-Professor Street-Fairfield Avenue intersection.
- All other associated work to complete the project

**All quantities listed in contract are approximate.** They were derived from measurements in the field, computer generated areas or are based on engineering judgments. Payments shall be computed from field measurements of the work complete and accepted in place. Any work item not listed in the bid schedule of items shall be considered incidental to the work item it is associated with to complete the project. Omitted items, if any, shall be brought to City's attention before bidding. Contractors are strongly urged to visit the site and verify the work required. Any discrepancies between field conditions and the contract work shall be brought to the City's attention during the pre-bid meeting.

**Contractor shall coordinate** his work with all public and private utilities, including City Traffic Engineering and/or sign shop to coordinate signal operations, pavement markings, and detector loops.