



3-D FINITE ELEMENT MODELING OF CUY-480-18.42 DECK REPLACEMENT
VOLUME I
SFN # 1812521 & 1812548
PID 90591



ODOT District 12
5500 Transportation Blvd.
Garfield Heights, Ohio 44125



August 6, 2012



July 31, 2012

Myron Pakush, P.E.
Deputy Director
ODOT - District 12
5500 Transportation Blvd.
Garfield Heights, OH 44125

RE: CUY-480-18.42
PID 90591
Deck Replacement Study

Attention Mr. Pakush:

The enclosed report addresses the out-of-plane distortions that occur as a result of replacing the decks for the CUY-480-18.42 L\R twin structures when utilizing part-width construction methods. P.E. Stamps have been affixed below for this report. The engineering analyses efforts that are specifically represented by the P.E. stamps are listed as follows:



- 3-D Finite Element Modeling (FEM) of the CUY-480-18.42 R Bridge for Deck Replacement analyses.
- Superstructure analysis and code checking during deck removal and existing conditions per AASHTO Standard Specifications, 17th Edition 2002.
- Using 3-D FEM to determine superstructure deflections, out-of-plane movements, and possible impacts to fatigue prone bridge components.
- Deck replacement analyses and construction recommendations.
- Retrofit design to control out-of-plane movements and related stresses.

If additional information is desired regarding the discussions provided in this report, please contact E.L. Robinson Engineering.

Respectfully,



Richard Engel, P.E.
Vice President



Volume I – Contents

	PART I	
	Development of a 3-D Finite Element Model for the CUY-480-1842 Superstructure	
I.	INTRODUCTION	1
	<i>Physical Condition of Existing Superstructure</i>	3
	<i>History of Out-of-Plane Distortion Induced Cracking</i>	4
	<i>Maintenance of Traffic Schemes</i>	5
	Alternative 1 (5+2)	5
	Alternative 2 (5+1)	6
II.	3-D FINITE ELEMENT MODELING	7
	<i>Development of the Coarse Model</i>	8
	Modeling of Girders and Cross Frames	8
	Moment Release of Diagonal and Lateral Bracing	11
	Modeling of Non-composite and Unintended Composite Action	11
	Geometry Grouping	12
	Loads	12
	<i>Methodology for the Sub-Model Development</i>	15
	Modeling of Girders/Stringers and Floorbeams	16
	Boundary Conditions	18
III.	SUPERSTRUCTURE ANALYSIS AND CODE CHECKING	19
	<i>Shear Capacity Check</i>	19
	<i>Girder Section Capacity</i>	19
	<i>Intermediate Cross Frames & Floor Beams</i>	20
	<i>Constructability</i>	20
	<i>Selected Results from 3-D Analysis</i>	23
	<i>Summary of Code Checking</i>	26
IV.	OUT OF PLANE DISTORTION	27
	Results in the Positive Moment Region – Existing Conditions (Composite)	29
	<i>Fisher’s $s-\Delta$ Expression</i>	35
V.	RETROFIT OPTIONS TO CONTROL OUT OF PLANE DISTORTION	36
	<i>Partial Removal of Connection Plate</i>	36
	<i>Rigid Connection Retrofit</i>	37
VI.	EFFECTIVENESS OF FINITE ELEMENT MODELING IN PREDICTING OUT-OF-PLANE DISTORTION INDUCED STRESSES IN BRIDGES	38
VII.	SUMMARY	39

	PART II	
	Half-Width Deck Removal Study	
	INTRODUCTION	42
	RECONNAISSANCE INFORMATION OBTAINED FOR VERIFICATION OF AS-BUILT CONDITIONS ..	42
	SUPERSTRUCTURE RETROFITS PERFORMED IN 1989	43
	MAINTENANCE OF TRAFFIC	44
	DECK REMOVAL SEGMENTS	48
	OUT OF PLANE DISTORTION INDUCED STRESSES FOR THE HALF-DECK REMOVAL SEGMENTS	49
	<i>Evaluation of the Removal of the 300 feet long Half-Width Deck Segment</i>	50
	<i>Dead load & Live Load Deflections</i>	52
	<i>Discussions with Contractors</i>	54
	CONCLUSIONS	55
	REFERENCES	62

Appendix A

- Estimated Construction Cost & Schedule

Appendix B


- Existing Plans Including Retrofit Plans

Appendix C

- Project Background Documents

PART I
Development of a 3-D Finite Element Model
for the CUY-480-1842 Superstructure

3-D FINITE ELEMENT MODELING OF CUY-480-18.42 DECK REPLACEMENT



I. Introduction

This study investigated the part-width replacement of the reinforced concrete decks for the twin CUY-480-1842 L/R structures. Each structure currently carries four lanes of traffic. The existing structures each have four main girders spaced at 22'-4". There are two intermediate stringers located between the main girders.

The scope of work for this study requires that during replacement of the decks, a minimum of three 12 foot lanes of traffic be maintained in both directions (eastbound and westbound). The existing width of one of the bridges cannot accommodate six lanes of traffic; therefore, a full closure of one bridge at a time is not acceptable. Part-width deck replacement procedures will cause differential deflection between adjacent main girders and stringers when the existing deck is removed in part-width segments. ELR was directed to determine if the components of the existing steel superstructure would perform satisfactorily when part-width deck replacement procedures are utilized. A component of the evaluation includes establishing if and where retrofit details must be designed and constructed to control out-of-plane distortions during phase construction procedures. Some of the major scope items included:

- Development of a 3-D Finite Element Model for the CUY-480-1842 Superstructure(s).
- Study the CUY-480-1842 R structure, noting that both of the structures are somewhat similar.
- Study part-width deck replacement using the MOT Alternative Scheme termed (5+1).
- Develop Sub-Model(s) for Out-of-Plane Distortion only for areas of high stress identified in the full model.

The existing 4150 feet long I-480 EB and WB structures utilize fifteen spans to carry a relatively high volume of South Freeway traffic over the Cuyahoga River Valley. These structures are an important



component of the interstate network traversing the City of Cleveland, which makes maintenance of traffic a paramount issue during the rehabilitation work. Within the limits of the river valley are the Cuyahoga River, Erie Canal, CSX and RTA railroad tracks, Cleveland Metro Park bike path and Canal Road.

3-D FINITE ELEMENT MODELING OF CUY-480-18.42 DECK REPLACEMENT

The existing structures were designed using the AASHTO Allowable Stress Design Method in accordance with the 1965 AASHTO Standard Specifications, interim specifications and the Ohio "Supplement". The applied Design Loading was the HS 20-44 loading and the Interstate Alternate Loading. The construction of the twin bridges was completed in 1975. The superstructure is divided into five units with four hinges having intermediate steel finger deck joints at each hinge to accommodate thermal movement. Elastomeric compression seal joints are provided at the abutments. The lengths of the five (5) superstructure units are as follows: Unit 1 is 795'; Units 2-4 are 900' and Unit 5 is 655'. The sub-stringers are supported on a steel floorbeam system. The original superstructure design philosophy assumed that the reinforced concrete deck and stringers would perform as non-composite members. The steel material used for the main girders is ASTM A588 and the remaining steel members consist of A36 steel. The existing reinforced concrete substructure units are T-type piers varying in height from 75 feet to 185 feet and stub abutments which are located at the top of the spill thru slopes. The substructures are supported on either steel H-piles or spread footings on shale. The current BARS (LFD) load rating for the bridge is HS19.4, which is governed by the moment capacity at one of the piers.

The existing structural steel experienced fatigue cracks dating back to the shipment of the girders to the construction site. In 1973, after cracks were discovered in the main steel girders during erection, ODOT commissioned Prof. John Fisher of Lehigh University to perform a fatigue evaluation of the bridge to determine the cause of the cracks. Prof. Fisher's findings concluded that the cause of the cracks was fatigue related to and caused by the relative out-of-plane distortion caused by cyclical loading of the girders which occurred during shipping on railroad flatbed cars.

The existing reinforced concrete decks are approximately 35 years old. An overlay was placed on the decks in 1989. Due to the configuration of the superstructure's transverse floorbeam/crossframe members, it is necessary to avoid eccentric loads to the main girders from the concrete deck dead load and traffic live load. The original contract plans did not allow part-width deck construction procedures to be used. The plans stated that *"Deck concrete shall be placed symmetrically about longitudinal centerline of the deck. No longitudinal construction joints shall be permitted"*.

The 2010 Bridge Inspection Report performed by HDR Engineering, Inc. and Northwest Consultants, Inc. states that the overall condition for both bridges is "satisfactory" (General Appraisal is 6). The deck for both bridges is rated as being in "fair" condition (condition rating is 5). As indicated in the inspection reports, the girders are in good condition. The stringers, which are welded to the top flange of the top chord of the floorbeam, have experienced some cracking at the connections. The structural steel was last painted in 2001.

Additional project background information can be found in Appendix C. The cost estimates for the deck replacement work, provided in Appendix A, were prepared using planning level information. The cost estimates were prepared to aid in making preliminary design decisions.

Part I of Volume I of this study provides a summary of the procedures utilized to develop and perform a 3D finite element evaluation of the existing structures. The existing structures have experienced and are prone

to high localized out-of-plane stresses at the crossframe to web connections. The feasibility of developing an acceptable deck replacement design and sequence of work has been evaluated and the results are presented in this report.

Part I contains multilevel 3-D modeling evaluations developed for the right bridge. ELR calculated the deflections and out-of-plane deformations caused by part-width construction alternatives and determined possible impacts to the fatigue prone details. Selected computational results are presented in Volume II of this report. The out-of-plane distortion causes higher stresses in the positive moment regions than in the negative moment regions near the pier support. Part I includes the evaluation of retrofit details with the objective of controlling the distortion-induced stresses.

As a result of the work accomplished during the Part I study phase, ODOT District 12 personnel were in a position to provide direction for the work to be performed during the Part II study phase. Part II of Volume I contains results of the study which focused on establishing a preferred deck replacement removal sequence along with recommended deck removal and replacement dimensions. The Part II analyses were performed to determine the specific construction procedures to be used to replace the existing decks when utilizing part-width construction methods, while satisfying maintenance of traffic obligations. ODOT has a strong desire to replace each deck in one construction season. This part-width construction work must be accomplished without jeopardizing the structural integrity of the superstructure. The recommended design procedures must include construction constraints necessary to ensure that out-of-plane stresses caused by the deck removal distortions are not any higher than the highest operating stress level presently occurring in the existing girders.

Volume II contains the calculations performed for the analyses portion of this study.

Physical Condition of Existing Superstructure

The Bridge Inspection Reports performed by HDR Engineering, Inc. and Northwest Consultants, Inc. (inspections dated 9/20-10/1/2010, 2009 and 10/13-10/16/2008) were reviewed.

The 2010 Inspection Report, for both bridges indicates that the overall condition is described as “satisfactory” (General Appraisal rating of 6).

The girders were found to be in “Fair” condition. The inspection report indicated the presence of two 2” diameter holes drilled in the web on each side of the lower lateral bracing gusset plate. These holes were used to arrest crack growth that is common at these locations throughout the superstructure. The inspection report recommended monitoring some of the high stress areas where the holes were overcut.



Holes measuring ½”, 1”, 1 ½”, or 2” have been drilled in the web to relieve stresses at various locations.

The stringers sit on top of the floorbeams and are welded to the top flange of the top chord of the floorbeams. The stringers were reported to be in good condition. Several of these stringer/floorbeam connections have developed cracks (see photo showing crack in weld of stringer 11 to the floor beam in span 3 of the right bridge). These cracks have not propagated into the stringer flanges.



The floorbeams and its connections were found to be in good condition.

The superstructure was painted in 2001. The paint coating has numerous areas where the primer is visible; however, there is no evidence of corrosion. Overall the protective coating system is in good condition (between 1 and 5% of the painted area needs to be repainted).



The bridge decks are in fair condition (5 rating). There are several areas where the concrete has spalled and exposed the reinforcing steel. The underside of the deck contains numerous hairline cracks, narrow transverse cracks, and map cracking.





The “Bearings” section of the Supplemental Report of the 2009 Inspection Results, which accompanied the 2009 Annual Inspection of the “Valley View” Bridges, indicates that the bearings show no sign of movement. This conclusion is verified by observing that the paint is not cracked over the junctions between the gears of the rollers and the racks above and below the rollers.




History of Out-of-Plane Distortion Induced Cracking

As a result of the steel girder cracks which occurred during erection, Professor John Fisher was contacted in 1973 to perform a fatigue evaluation of the superstructure.

As a part of the 1973 investigations, cores/coupons were obtained at several crack locations and fractographic examinations of the crack surfaces were performed.

All the cracks were found to be fatigue related and were determined to be caused by the relative out-of-plane distortion and bending of the short web length between the end of the stiffeners and the web-to-flange fillet weld. The cracks were primarily parallel to the longitudinal direction of the girder and to the bending stresses. The relative movement was caused by the cyclic swaying motion of the girders while in transit to the construction site and/or wind-induced motion during storage on the ground. The following exhibits summarize the types of cracks found and the repairs that were performed as summarized from Fisher (1984).

Crack Location	Crack Characteristics	Repairs
<p>Between the stiffener weld and web.</p> 	<p>This type of crack was parallel to the primary bending of the girders and constituted 80% to 90% of cracks noted in the girders. These cracks were not through cracks and noted on the near side of the web. These cracks were caused by cyclical applied loads.</p>	<p>No repairs were performed for this type of crack. It was determined that these cracks would not propagate any further.</p>
<p>Across the welds</p> 	<p>This type of cracks were noted at the end of several stiffeners and in some instances extended completely across the weld and penetrated into the web.</p>	<p>The cracks that propagated into the weld near the stiffener end were removed by grinding out the crack. The ground-out area was examined with dye-penetrant to confirm the removal of the crack tip.</p>

Crack Location	Crack Characteristics	Repairs
<p>At fillet weld toes</p> 	<p>These types of cracks were noted at the weld toes at the end of stiffeners adjacent to the tension flange. The sample cores indicated that the crack had propagated into the web at the end of the fillet weld and turned and moved up the web after a short distance into the web.</p>	<p>Repairs were done by drilling 7/16" diameter holes at the end of each crack.</p> 
<p>Web surface opposite side of the stiffeners</p>	<p>These types of cracks were noted in the web surface opposite the stiffener. The cracks originated on the web surface and did not join the crack propagating into the web from the other surface at the end of the transverse stiffener.</p>	<p>Repairs were done by drilling 7/16" diameter holes at the end of each crack.</p> 

3-D FINITE ELEMENT MODELING OF CUY-480-18.42 DECK REPLACEMENT




Maintenance of Traffic Schemes

Following the creation of the 3-D model, two maintenance of traffic schemes were evaluated for the part-width replacement of the existing deck. Alternative 1 was designated as (5+2) and Alternative 2 as (5+1).

Alternative 1 (5+2)

For this alternative, five lanes of traffic are placed on the left bridge while 2 lanes of traffic are placed on the right bridge. The right bridge deck removal and replacement is carried out in two phases as shown. In phase 1, two lanes of traffic are placed on the right bridge while constructing a composite deck in the middle bay. In phase 2, traffic lane is placed in the middle of the deck while constructing both outer bay composite decks.

Phase 2 has a composite deck in the middle which is constructed in phase 1 of this alternative as shown below.






3-D FINITE ELEMENT MODELING OF CUY-480-18.42 DECK REPLACEMENT

Alternative 2 (5+1)

For this alternative, five lanes of traffic are placed on the left bridge while the deck is replaced on the right bridge. This alternative is also carried out in two phases as shown. In phase 1, one lane of traffic is placed in the middle bay of the right bridge while the outside bays are removed and replaced with a composite deck. In phase 2, one lane of traffic is placed in each on the newly constructed portions of the deck while the middle bay is replaced.

Alternative 2 (5+1) is the scheme that is studied in more detail in Part 1 based on direction provided by ODOT at the Nov. 4, 2011 meeting.



II. 3-D Finite Element Modeling

ELR reviewed the original design plans, the rehabilitation plans, and the latest inspection report prior to beginning development of the 3-D FE Model. The CAD model was generated through the use of the framing plan, horizontal curves, vertical curves, deck dimensions, girder locations, pier positions, and abutment geometry from the existing plans.

The 3-D FE modeling was accomplished as follows:

1. Build and analyze the entire right bridge for the existing conditions and MOT phases using LARSA 4D. The resulting model was defined as a coarse-model.
2. Create sub-models of regions: near the pier and mid-span using the LUSAS program.
3. Obtain the forces and moments at the boundary nodal locations from the coarse-model.
4. Apply boundary conditions to the sub-models. Analyze sub-models and ensure compatibility of the deformed shape of the girders/stringer and stringers between the sub-models and the coarse-models.

Because the CUY-480-18.42 bridges are relatively large structures, out-of-plane analyses could not be performed utilizing only a coarse-model, thereby, requiring a coarse-model and sub-model evaluation procedure.


The LARSA 4D computer program (version 7.05.35) was used for the 3-D Finite Element Modeling of the eastbound structure (Right Bridge). In the 3-D coarse model, flanges of girders, floorbeams and stringers were modeled using line/beam elements while the webs were modeled using plate/shell elements. The cross frames and lateral bracing were modeled using line/beam elements.

Typically, the effects of the configuration and the stiffness of substructures on the behavior of the superstructure are insignificant and can be safely neglected in the superstructure analysis. As noted in the 2009 inspection report, the bearings show no sign of movement (the paint over the junctions between the gears of the rollers and the racks above and below the rollers is not cracked). The same inspection report also indicated that noticeable sway (back and forth) of the tall piers is observable when a person is standing or sitting on the piers while a truck passes overhead.

Due to the complex size of the bridge, the modeling of the live loads presented several computational challenges.

Model	Influence Surface/Line	DOF	Lanes	Number of Moving Load cases	Computation Time (Run Time)	Disk Space
Coarse Model - Existing Conditions	Surface	289350	5	14800	16 days	500 (GB)
Coarse Model - Existing Conditions	Surface	289350	2	3552	5 days	201 (GB)
Coarse Model - Existing Conditions	Line	289350	5	5914	5 days	200 (GB)
Coarse Model - Existing Conditions	Line	289350	2	2372	2 days	100 (GB)
Coarse Model of Unit 2 ONLY - Existing Conditions	Surface	44622	5	3225	5 Hours	24 (GB)
Coarse Model of Unit 2 ONLY - Alt 2 - Phase 1	Surface	34352	1	1280	2 Hours	9 (GB)
Coarse Model of Alt 2 - Phase 1	Surface (Short)	226602	1	860	14 Hours	20 (GB)
Coarse Model of Alt 2 - Phase 2	Surface (Short)	283140	2	1720	24 Hours	45 (GB)

The above summary documents the unusually long computational time periods needed to evaluate each loading condition. These relatively long computational time periods, which result from the large size of the 3-D model, limited the study of the presence of live loads in only spans 10, 11 and 12. The detailed evaluation of out-of-plane distortion was focused in span 11.



No. of Nodes = 48,226
No. of Shells = 36,563
No. of Beam Elements = 41,602

Development of the Coarse Model

This section provides the background for the development of the coarse model. The 3-D FE model consists of five units matching the units shown in the construction plans. Units 2, 3, and 4 are identical to each other. Each of the five units were built in separate files which were then combined as a single LARSA model file.




Table 1 Units, Spans, and Spans Lengths

Unit	Spans	Length (feet)
Unit 1	1,2,3	220, 300,300
Unit 2	4,5,6	300,300,300
Unit 3	7,8,9	300,300,300
Unit 4	10,11,12	300,300,300
Unit 5	13,14,15	225,225,180




Figure 1 Unit 1




Figure 2 Units 2, 3 and 4




Figure 3 Unit 5

Modeling of Girders and Cross Frames

The webs of the girders and the stringers were modeled using 4-node shell elements while the flanges were modeled using beam elements. The cross frame chords were modeled using beam elements. Bearing stiffeners, intermediate stiffeners, and longitudinal stiffeners were modeled using beam elements.

Figures 4 and 5 show detailed views of one cross frame as modeled in LARSA. The 3-D viewing option was used in Figure 5 to show the graphical representation of the flanges and stiffeners.

The deck slab and barriers were modeled using 4-node shell elements. The pier columns, pier cap, and pier bearing were modeled using beam elements as shown in Figure 6.




Figure 4 Modeling of Girders, Stringers and Cross frames




Figure 5 3-D view of Girders and Cross Frames




Figure 6 Modeling of Pier Column and Cap

A fixed end boundary condition was specified at the bottom of the relatively tall pier columns. The actual fixity is located below the pier footing. Soil-structure interaction modeling was not performed because the actual location of the fixed end boundary condition does not change the performance of the model for these tall piers.

The master-slave connection option available in the LARSA program was used to model the hinges as shown in Figure 7. Forces (F_x , F_y and F_z) are allowed to transfer but Moments (M_x , M_y and M_z) are not transferred.




Figure 7 Modeling of the Hinges

The height of the bearings was also modeled. The moments were released and forces are transferred to the pier cap as shown in Figure 8.




Figure 8 Modeling of the Bearings



Moment Release of Diagonal and Lateral Bracing

The moments at both ends of the diagonal and lateral bracing were released. Figure 9 shows the locations of the released moments at the connections between the diagonal members. The diagonals for this design, which consist of a non-skewed and tangent condition, are treated as truss ended or truss members, not as flexural members. This is typical when developing models of this nature (see P 58 - NSBA/AASHTO's Guidelines for the Analysis of Steel Girder Bridges). This cross frame modeling approach was decided at an ODOT Central Office- Office of Structures meeting requested by ELR.




Figure 9 Crossframe Detail (Released Moments)

Modeling of Non-composite and Unintended Composite Action

The existing superstructure was originally designed assuming that the reinforced concrete deck would perform as a non-composite superstructure component. The most accurate finite element approach for modeling the assumed non-composite behavior is to perform a contact analyses. This procedure takes into account the friction developed between the reinforced concrete deck and the steel girder. However, this modeling approach is very complex and requires significant computer resources.

Non-composite bridges generally exhibit composite action under service loads due to the chemical bond and the friction between the two different materials. This composite action can range from fully composite to completely non-composite, depending on the actual deck to stringer details, the years of service, and the loading conditions.

In our sub-models, both composite and non-composite behaviors were evaluated. Linear coupled degrees of freedom (master/slave options) were used for modeling this behavior.

For non-composite behavior, it is assumed that the corresponding deck and girder contact surface nodes will displace the same in the vertical, longitudinal and transverse directions, but independently in the three rotational directions (rotation around vertical, longitudinal and transverse directions). The deck bottom surface and the girder top flanges are meshed with a series of coincident nodes. Each pair of coincident nodes are linked together for the transverse (Y), longitudinal (X) and vertical (Z) degrees of freedom (DOF), but are "untied" for the rotation around X, Y and Z DOF so that the model can behave non-compositely.

For composite behavior (top flange is restrained by the deck), it was assumed that the corresponding deck and girder contact surface nodes would displace and rotate the same in the vertical, longitudinal and

transverse directions. The deck bottom surface and the girder top flanges are meshed with a series of coincident nodes. Each pair of coincident nodes are linked together for the transverse (Y), longitudinal (X) and vertical (Z) DOF for rotation and translation.




Figure 10 Modeling of Non-composite Action




Figure 11 Modeling of Composite Action

Geometry Grouping

LARSA 4D allows breaking the model into groups based on geometry thereby making the development of the model more manageable and easier to review. In LARSA 4D, groups can be any selected geometric objects in the structure such as points, beams, or plates.

The structure groups allow for ease of assigning material properties and help with managing the entire model for results.

In the FE model, there are five main groups for each of the units. Under each unit, groups of parameters were defined. The chart in Figure 12 shows an exploded view of the Unit 1 folder.





Figure 12 Groups

Loads

Dead Loads


The temporary barrier dead load used for the MOT was applied to the model. The barrier was modeled as shown in the image of the superstructure provided below.



The self-weight of the structure is computed internally by the SELFWEIGHT load case available in the computer program.

Live Loads

The HS20- Truck, the HS20- Lane, and a Train of HS20 Trucks were used to apply live load to the computer model.



The HS20-44 truck and lane loads are defined in the LARSA program.

In accordance with Section 6B.7.2 of the AASHTO Manual for Bridge Evaluation (2nd Edition), for spans over 200 feet in length, a train of HS20 trucks should be considered. Trucks are spaced with 30 feet clear distance between vehicles to simulate a train of vehicles in one lane. A number of analyses were made to establish the truck spacing that will generate the maximum live load stresses.

Influence Surface Analyses

The common approach for influence line analysis is to lump each axle or wheel of the vehicle on the centerlines of the members in the lane path, unless: 1) the lane is specified with offsets that take it away from the member centerline, 2) a transverse offset is specified in the influence result case options, or 3) the load pattern has transverse offsets specified on the wheels. In cases 2 and 3, a second set of influence coefficients, based on a one-unit torque, is used to compute the moment induced by the eccentricity as described in LARSA-4D documentation. Load distributions across multiple girders are accomplished either through rigid cross-beams connecting girders, or by loading multiple lanes simultaneously (see Figure 13).

With the influence surface method, load distribution is accomplished automatically. Plate decks by their nature will spread load from the point of contact with the wheel throughout the deck, and to any connected elements.

The first step in defining the live load analysis is to define the traffic lanes. Lanes can be defined by selecting a series of lines/plates along the traffic path. The traffic lanes are adjusted to fit the actual traffic paths, as shown in Figure 13.

When using the standard solution method, LARSA 4D places as many lanes as will fit on the surface, according to the width of the surface specified in the input geometry, simultaneously maximizing the live load effect according to any multiple presence factors.




Figure 13 Lane Definition (1)





Figure 14 Depiction of Lanes

The second step in the analyses is to define the influence loads. For each lane, a moving load case is defined in the LARSA program

The resulting load cases are created based on the moving load analyses by utilizing the influence line/surface data. The following input screen shows the LARSA 4D analysis options for influence analyses.



3-D FINITE ELEMENT MODELING OF CUY-480-18.42 DECK REPLACEMENT

Methodology for the Sub-Model Development

The LARSA 4-D model of the entire bridge is defined in this report as a coarse model. A finer mesh (sub-model) was used for evaluating out-of-plane displacement in the superstructure components. Sub-models were prepared using LUSAS, because this program has advanced mesh generation features.

The maximum Dead Load (DL) moment was found to be at Pier 2, followed by the moment at the Pier 10 location. For analyses of out-of-plane displacement or distortion, regions in Span 11 were selected because this span does not have any hinges.

Sub-models capturing the relevant three-dimensional out-of-plane displacements are prepared for the following:

- Phase 1 of MOT Scheme Alt 2 (5+1). By initial evaluation, Phase 2 was found to be susceptible to lesser out-of-plane distortions
- Existing conditions (existing deck slab – considered both behaviors: non-composite and composite)

The sub-models prepared were for interior and exterior girders in both negative and positive moment regions of Span 11 as shown in Figure 15.





Figure 15 Mid-span and Near Pier Sub-Models

3-D FINITE ELEMENT MODELING OF CUY-480-18.42 DECK REPLACEMENT

Modeling of Girders/Stringers and Floorbeams



The cut length for sub-models was 20 feet with half of the length (10 ft.) on each side of the connection plate.

All the plates (flanges, webs, stiffeners) of interior and exterior girders are modeled by 4-node thick shell elements as shown on this page.

Each of the sub-models has approximately 27000 4-node shell elements (361422 structural degrees of freedom for each of the sub-models)

Figures 16 & 17 identify plate names for plate thickness assignments of the various members.

- Geometric Key
- Top Chord Web
 - Top Chord Flange
 - Diagonal Chord Thickness
 - Gusset Plate 2
 - Stringer Web
 - Stringer Flange
 - Girder Flange (34x2.75)
 - Girder Web (9/16)
 - Stiffeners
 - Long. Stiffeners
 - Lateral Chord Thickness
 - Gusset Plate 1
 - Bottom Chord
 - LGeo23 (Pipe XX2 major z)

No. of Shell Elements: 27000
 361422 structural degrees of freedom




Figure 16 Properties Assignment of the Interior Sub-Model

- Geometric Key

- Girder Flange (24x1.50)
- Girder Web (7/16)
- Long. Stiffeners
- Stiffeners
- Top Chord Flange
- Top Chord Web
- Gusset Plate 1
- Lateral Chord Thickness
- Diagonal Chord Thickness
- Bottom Chord
- Stringer Web
- Stringer Flange
- Gusset Plate 2




Figure 17 Properties Assignment of the Exterior Girder Sub-Model




Figure 18 FE model of Interior Girder Sub-Model





Figure 19 FE model of Exterior Girder Sub-Model

Boundary Conditions

Figures 20 and 21 depict the boundary conditions used in the sub-models. $T_x = 0$ indicates that translation is prevented in the X-direction. $R_x = 0$ refers to prevention of rotation in the x-direction. At the boundary, all conditions of statics were satisfied. The boundary conditions (Moments and Forces) for the sub-models were obtained from the full model of the structure (LARSA 4-D Model – Entire Structure – Alternative 2).



A-A is a line of Symmetry

Figure 20 Boundary Conditions of the Interior Girder Sub-Model




Figure 21 Boundary Conditions of the Interior Girder Sub-Model




Figure 22 Deformed Shape of the Interior Girder Model

III. Superstructure Analysis and Code Checking

The existing girders and stringers were checked with existing loading conditions and Alternate 2 MOT. The following checks were performed according to AASHTO Standard Specifications for Highway Bridges, 17th Edition, 2002. The results indicate all moment and shear stresses due to phase construction to be acceptable. The complete results are presented in Volume II of this report.

Shear Capacity Check

According to AASHTO Standard Specifications, shear is assumed to be carried by the steel web. The strength of web is determined by elastic methods.

The maximum shear in the web cannot exceed the plastic shear force, V_p , given in 10.48.8.1 of AASHTO Standard Specifications as follows

$$V_p = 0.58F_y D t_w \quad (10-115)$$

The spacing of intermediate transverse stiffeners is based on the shear capacity, V_u , defined in Article 10.48.8.1 of AASHTO Standard Specifications as follows:

$$V_u = V_p \left[C + \frac{0.87(1-C)}{\sqrt{1+(d_o/D)^2}} \right] \quad (10-114)$$

V_u in the above equation is equal to the shear buckling capacity. The constant, C , is equal to the ratio of the shear buckling stress to the shear yield stress and is specified in Article 10.48.8.1 of the Standard Specifications. For transversely stiffened webs, C is calculated using a shear-buckling coefficient k equal to $5+5/(d_o/D)^2$, where d_o is equal to the transverse stiffener spacing. The maximum spacing of intermediate transverse stiffeners is limited to the web depth D . The maximum spacing of the first stiffener in an end panel is limited to $0.5D$.

' V_u ' is the absolute value of the shear capacity of the web (kips) based on the transverse stiffener spacing as shown on the plans.

Girder Section Capacity

The composite section capacity is calculated according to AASHTO's Standard Specifications Section 10.50.

- Positive Moment Sections
 - Noncompact sections

The bending stresses due to appropriate loadings shall not exceed:

- the yielding stress of the tension flange (F_y)
- $F_y R_b$ of in the compression flange, where

$$R_b = 1 - 0.002 \left(\frac{D_c t_w}{A_{fc}} \right) \left[\frac{D_c}{t_w} - \lambda / \sqrt{\frac{M_r}{S_{xc}}} \right] \leq 1.0 \quad (10-103b)$$

Here, A_{fc} shall be taken as the effective combined transformed area of the top flange and concrete deck that yields, D_c is calculated with accordance to article 10.50b, f_b is equal to factored bending stress in the compression flange not exceeding F_y . λ is defined as follows:

$$\begin{aligned} \lambda &= 15,400 \text{ for sections where } D_c \leq D/2 \\ &= 12,500 \text{ for sections where } D_c > D/2, D_c \text{ is the depth of the web of the steel girder} \\ &\text{in compression} \end{aligned}$$

According to Section 10.50.1.2.2, when girders are not provided with temporary supports during the placing of the dead load, the sum of the stresses produced by $1.3D_s$ acting on the steel girder alone with $1.3(D_c + 5(L+I)/3)$ acting on the composite girder shall not exceed yield stress at any point, where D_c and D_s are the moments caused by the dead load acting on the steel girder and composite girder, respectively.

- Negative Moment Sections
 - Noncompact sections

The girder maximum strength, M_u is defined as follows:

The bending stresses due to appropriate loadings shall not exceed:

- the yielding stress of the tension flange (F_y)
- $F_{cr} R_b$ of in the compression flange, where

$$F_{cr} = \left(4,400 \frac{t}{b} \right)^2 \leq F_y$$

Where b and t are the compression flange width and thickness, respectively.

$$R_b = 1 - 0.002 \left(\frac{D_c t_w}{A_{fc}} \right) \left[\frac{D_c}{t_w} - \lambda / \sqrt{\frac{M_r}{S_{xc}}} \right] \leq 1.0$$

Here, f_b is equal to factored bending stress in the compression flange not exceeding F_y . λ is defined as above.

Intermediate Cross Frames & Floor Beams

AASHTO Standard Specifications for Highway Bridges, 17th Edition-2002 was used to check the adequacy of the cross frame sections. Each member was checked for the axial capacity and the combined axial load and bending effect, Sections 10.54.1 and 10.54.2 respectively. Equation 10-150 is used to calculate the maximum axial strength, while equations 10-155 and 10-156 set limits for the combined axial loads and bending moments.

$$P_u = 0.85 A_s F_{cr} \quad \text{AASHTO 10-150}$$

$$\frac{P}{0.85 A_s F_{cr}} + \frac{M C}{M_u \left(1 - \frac{P}{A_s F_e}\right)} \leq 1.0 \quad \text{AASHTO 10-155}$$

$$\frac{P}{0.85 A_s F_y} + \frac{M}{M_p} \leq 1.0 \quad \text{AASHTO 10-156}$$

$$F_{cr} = F_y \left[1 - \frac{F_y}{4\pi^2 E} \left(\frac{KL_c}{r}\right)^2\right] \quad \text{for } \frac{KL_c}{r} \leq \sqrt{\frac{2\pi^2 E}{F_y}} \quad (10-151)$$

$$F_{cr} = \frac{\pi^2 E}{\left(\frac{KL_c}{r}\right)^2} \quad \text{for } \frac{KL_c}{r} \geq \sqrt{\frac{2\pi^2 E}{F_y}} \quad (10-154)$$

Constructability

AASHTO's Standard Specifications Constructability Section 10.61 states that the moment and shear capacities of a girder shall meet the requirements to control local buckling of the web and compression flange, and to prevent lateral torsional buckling of the cross section under the non-composite dead load prior to hardening of the deck slab. A load factor of $\gamma = 1.3$ shall be used in calculating the applied moments and shears.

The requirements are as follows:

- **Web Bend Buckling**

According to AASHTO Standard Specifications Section 10.61.1, the maximum factored non-composite dead load compressive bending stress in the web shall not exceed the value given below:

$$f_b \leq \frac{26,200,000 \alpha k}{\left(\frac{D}{t_w}\right)^2} \leq F_{yw} \quad (10-173)$$

Where

F_{yw} : minimum yield strength of the web

D_c : depth of the web of the steel girder in compression

D : web depth

t_w : thickness of the web

Here the buckling coefficient k is taken to be 9 (D/D_c) for members without longitudinal stiffeners. When longitudinal stiffeners are present the buckling coefficient k is calculated as:

$$\begin{aligned} \text{for } \frac{d_s}{D_c} \geq 0.4 \quad k &= 5.17 \left(\frac{D}{d_s}\right)^2 \geq 9 \left(\frac{D}{D_c}\right)^2 \\ \text{for } \frac{d_s}{D_c} < 0.4 \quad k &= 11.64 \left(\frac{D}{D_c - d_s}\right)^2 \end{aligned}$$

In the case when both edges of the web are in compression, k should be taken as 7.2 for members with or without longitudinal stiffeners. $\alpha = 1.3$ for members without a longitudinal stiffener and 1 for members with longitudinal stiffer (Equation 10-173).

- **Web shear buckling**

According to AASHTO Standard Specifications Section 10.61.2, the sum of the factored noncomposite and composite dead-load shears shall not exceed the shear buckling capacity of the web:

$$V_u = C V_p \quad (10-113)$$

The maximum shear in the web cannot exceed the plastic shear force, V_p , given in 10.48.8.1 of AASHTO Standard Specifications as follows

$$V_p = 0.58 F_y D t_w \quad (10-115)$$

The spacing of intermediate transverse stiffeners is based on the shear capacity, V_u , defined in Article 10.48.8.1 of AASHTO Standard Specifications as follows:

$$V_u = V_p \left[C + \frac{0.87(1-C)}{\sqrt{1+\left(\frac{d_0}{D}\right)^2}} \right] \quad (10-114)$$

V_u in the above equation is equal to the shear buckling capacity. The constant, C , is equal to the ratio of the shear buckling stress to the shear yield stress and is specified in Article 10.48.8.1 of the Standard Specifications. For transversely stiffened webs, C is calculated using a shear-buckling coefficient k as follows:

$$\begin{aligned} \text{for } \frac{D}{t_w} < \frac{6,000\sqrt{k}}{\sqrt{F_y}} & \quad C = 1.0 \\ \text{for } \frac{6,000\sqrt{k}}{\sqrt{F_y}} \leq \frac{D}{t_w} < \frac{7,500\sqrt{k}}{\sqrt{F_y}} & \quad C = \frac{6,000\sqrt{k}}{\left(\frac{D}{t_w}\right)F_y} \quad (10-116) \\ \text{for } \frac{D}{t_w} > \frac{7,500\sqrt{k}}{\sqrt{F_y}} & \quad C = \frac{4.5 \times 10^7 k}{\left(\frac{D}{t_w}\right)^2 F_y} \quad (10-117) \end{aligned}$$

where $k = 5 + 5/(d_0/D)^2$; d_0 is equal to the transverse stiffener spacing. The maximum spacing of intermediate transverse stiffeners is limited to the web depth D . The maximum spacing of the first stiffener in an end panel is limited to $0.5D$. d_0 = distance between transverse stiffeners

V_u is the absolute value of the shear capacity of the web (kips) based on the transverse stiffener spacing as shown on the plans.

• Lateral-Torsional Buckling of the Cross Section

According to AASHTO Standard Specifications Section 10.61.3 the maximum factored non-composite dead-load moment shall not exceed the values of M_u calculated as partially braced member according to the following equation:

$$\begin{aligned} M_u &= M_r R_b \quad (10-103a) \\ R_b &= 1 \text{ for longitudinally stiffened girders} \end{aligned}$$

$$\text{if } \frac{D}{t_w} \leq 5,460 \sqrt{\frac{k}{f_b}}$$

$$\text{for } \frac{d_s}{D_c} \geq 0.4 k = 5.17 \left(\frac{D}{d_s}\right)^2 \geq 9 \left(\frac{D}{D_c}\right)^2$$

$$\text{for } \frac{d_s}{D_c} \geq 0.4 k = 11.64 \left(\frac{D}{D_c - d_s}\right)^2$$

Where

d_s = the distance from centerline of a plate longitudinal stiffener
 f_b = factored bending stress in the compression flange

In the case when both edges of the web are in compression k should be taken as 7.2
Otherwise

$$R_b = 1 - 0.002 \left(\frac{D_c t_w}{A_{fc}}\right) \left[\frac{D_c}{t_w} - \frac{\lambda}{\sqrt{S_{xc}}}\right] \leq 1.0 \quad (10-103b) \quad \text{for girders with or without longitudinal stiffeners}$$

Where:

D_c = depth of the web in compression (in)

t_w = thickness of the web (in)

A_{fc} = area of compression flange (in²)

M_r = lateral torsional buckling moment (lb.-in)

S_{xc} = section modulus with respect to compression flange (in³)

$\lambda = 15,400$ for sections where $D_c \leq D/2$

$= 12,500$ for sections where $D_c > D/2$

The moment capacity, M_r should be less than yielding moment M_y at all times, and should be less than the lateral torsional buckling moment as follows:

For

$$\frac{D_c}{t_w} \leq \frac{\lambda}{\sqrt{F_y}}$$

$$M_r = 91 \times 10^6 C_b \left(\frac{I_{yc}}{L_b} \right) \sqrt{0.772 \frac{J}{I_{yc}} + 9.87 \left(\frac{d}{L_b} \right)^2} \leq M_y \quad (10-103c)$$

$$\frac{D_c}{t_w} > \frac{\lambda}{\sqrt{F_y}} \quad (10-103d)$$

for $L_b \leq L_p$
 $M_r = M_y$
 for $L_r \geq L_b > L_p$

$$M_r = C_b F_y S_{xc} \left[1 - 0.5 \left(\frac{L_b - L_p}{L_r - L_p} \right) \right]; \quad L_r = \left(\frac{572 \times 10^6 I_{yc} d}{F_y S_{xc}} \right)^{1/2} \quad (10-103e,f)$$

for $L_b > L_p$

$$M_r = C_b \frac{F_y S_{xc}}{2} \left(\frac{L_r}{L_b} \right)^2 \quad (10-103g)$$

Where

L_b = unbraced length of the compression flange (in)

$L_p = 9,500 r' / (F_y)^{1/2}$

r' = radius of gyration of compression flange about vertical axis in the plane of the web, (in⁴).

d = depth of girder (in)

$J = [(bt^3)_c + (bt^3)_t + Dt_w^3] / 3$ where b and t represent the flange width and thickness of the compression and tension flange, respectively, (in⁴).

$C_b = 1.75 + 1.05(M1/M2) + 0.3(M1/M2)^2 \leq 2.3$ where $M1$ is the smaller and $M2$ is the larger end moment in the unbraced segment of the beam.

$C_b = 1.0$ for unbraced cantilevers and for members where the moment within a significant portion of the unbraced segment is greater than or equal to the largest of the segment end moments

- **Compression Flange Local Buckling**

According to Article 10.61.4, in positive moment regions, the ratio of the top compression flange width to thickness shall not exceed the following formula:

$$\frac{b}{t} = \frac{4,400}{\sqrt{f_{dl}}} \leq 24 \quad (10-174)$$




Where f_{dl} is the top flange compressive stress due to the factored non-composite dead load divided over R_b , but not exceeding F_y . R_b is defined in the lateral torsional buckling section.

Selected Results from 3-D Analysis

Preliminary findings indicated large out-of-planes stresses due to both MOT alternates. Alternate 1 MOT yielded significantly higher stresses, so it was determined after consultation with ODOT that further analyses efforts be limited to Alternate 2 MOT.

The Alternative 2 (5+1) has two phases. Phase 2 has a composite deck on the outsides as shown here. Results from the analyses are presented:

- Unfactored Shear and Moments
- Bending (Flexure) Stresses for Girders F and Stringer No. 3 for various AASHTO Load Combinations



Zoom 105.6%
 Deformed Model - DL
 Scale Factor: 45.2




Figure 23 Alt 2- Phase 1 - Deformed Shape - Mid Span 11

Zoom 83.47%
 Deformed Model - DL
 Scale Factor: 32




Figure 24 Alt 2- Phase 2 - Deformed Shape - Mid Span 11

Table 2 summarizes load combinations considered in the analyses.

Table 2 Factors for load combinations (LFD) used in the LARSA Model

Load Combination	AASHTO GROUP	DL	Live Load	W
1	I	1.3	1.30 [5/3 HS20 Truck Plus impact (30 %)]	0
2	I	1.3	1.30 [5/3 HS20 Moment Plus impact (30 %)]	0
3	I	1.3	1.30 [5/3 HS20 Shear Plus impact (30 %)]	0
4	I	1.3	1.30 [5/3 HS20 Train Plus impact (30 %)]	0
5	II	1.3	0	1
6	III	1.3	1.30 [1.0 HS20 Truck Plus impact (30 %)]	0.3
7	III	1.3	1.30 [1.0 HS20 Moment Plus impact (30 %)]	0.3
8	III	1.3	1.30 [1.0 HS20 Shear Plus impact (30 %)]	0.3
9	III	1.3	1.30 [1.0 HS20 Train Plus impact (30 %)]	0.3
10			Fatigue Truck Plus impact (10 %)	

Table 3 Unfactored Shear and Moments (Mid Span 11)

	DL Moment (Kips.ft)		DL Shear (Kips)		Dead Load Deflection (in)		Live Load Max Deflection (in)		(DL+LL) Max Deflection (in)	
	Interior	Exterior	Interior	Exterior	Interior	Exterior	Interior	Exterior	Interior	Exterior
Current (mid span 11)	4291	2996	-21.7	-19.4	1.93	1.85	3.3	3.0	5.23	4.85
MOT Phase 1 (mid span 11)	2309	1695	-9.44	-4.11	0.79	0.57	1.8	1.7	2.59	2.27

Table 3 shows that no appreciable moments or shears occur during MOT phasing. The deflections of the interior and exterior girders in relationship to each other are consistent.

Table 4 summarizes stresses for various AASHTO load combinations. The maximum stresses computed are about 23 ksi in Girder F and about 11 ksi in Stringer 3. This is well below the allowable stress of 27 ksi for the main girder steel and 20 ksi for the stringers.

Table 4 Max and Min Bending Factored stresses on Girder F (interior) and Stringer 3 (MOT Alternative 2 – Phase 1)

Combination No.	AASHTO Group	Girder F		Stringer 3	
		Sxx (min) (ksi)	Sxx(max) (ksi)	Sxx (min) (ksi)	Sxx(max) (ksi)
1	I	-13.1	6.7	-8.5	7.5
2	I	-14.5	7.3	-8.1	7.4
3	I	-14.6	7.3	-8.4	8.0
5	II	-22.7	10.1	-10.6	9.1
6	III	-10.2	5.9	-5.9	4.6
7	III	-13.5	6.7	-7.2	6.3
8	III	-13.7	6.8	-7.5	6.7
9	III	-12.8	6.3	-7.5	6.4
10		-14.8	7.8	-8.8	7.3

Table 5 Factored Live Load Bending Stresses – Girder E (Exterior)

		Bending Stress (ksi) Near Pier		Bending Stress (ksi) MidSpan	
		Max -ve	Max +ve	Max -ve	Max +ve
Existing	At Top Flange	-0.55	0.03	-0.11	0.13
	At Bottom Flange	-0.26	0.81	-4.09	1.61
MOT Ph1	MOT 1 - At Top Flange	-0.1	2.12	-3.26	2.12
	MOT 1 - At Bottom Flange	-4.31	0.78	-3.78	6.81
MOT Ph2	At Top Flange	-0.33	0.83	-0.96	0.74
	At Bottom Flange	-2.22	1.98	-1.59	6.31

Table 6 Factored Live Load Bending Stresses – Girder F (Interior)

		Bending Stress (ksi) Near Pier		Bending Stress (ksi) MidSpan	
		Max -ve	Max +ve	Max -ve	Max +ve
Existing	At Top Flange	-0.11	1.12	-0.99	1.61
	At Bottom Flange	-2.34	0.81	-4.56	8.13
MOT Ph1	MOT 1 - At Top Flange	-0.07	3.33	-2.82	2.36
	MOT 1 - At Bottom Flange	-4.65	1.74	-3.28	8.27
MOT Ph2	At Top Flange	-0.33	0.76	-0.96	0.13
	At Bottom Flange	-3.49	0.74	-1.56	5.69

Notes

In Tables 5 and 6, the term “Near Pier” refers to girder area near the location of Pier 10 and the term “Midspan” refers to middle of span 11. MOT Ph1 & 2 refers to MOT Alternative 2 Phase 1 & 2 respectively. Max -ve and +ve in the Tables 5 and 6 refer to maximum and minimum live load envelopes. For stringer and girder locations – refer to page 16 of this report.

Summary of Code Checking

The existing girders and stringers were checked with both the existing loading condition and Alternate 2 MOT. The following checks were performed according to AASHTO Standard Specifications. The results indicate all moment and shear stresses due to phase construction to be acceptable. The results are presented in Part I of Volume II in tabular format for Girders E, F and Stringers 1, 2 & 3 (see page 16 for the girder and stringer location). The results include girder capacity (moment and shear) and constructability checks for following:


- Existing Deck (Maximum and Minimum LL Envelopes)
- Alternative 2 – Phase 1 MOT (Maximum and Minimum LL Envelopes)
- Alternative 2 – Phase 2 MOT (Maximum and Minimum LL Envelopes)

The detailed computations worksheets are also included in the Appendix of Volume II.

IV. Out of Plane Distortion

Out-of-plane distortion will cause stresses in the localized web gap region. In this section, results from out-of-plane distortion modeling at the following locations are presented: Near pier 10 (Negative Moment Region) and middle of span 11 (Positive Moment). A comparison between composite (top flange restrained by the deck) and non-composite structural performance was evaluated only for the existing design conditions.

The figures below show the cracks that may develop due to the various components of out-of-plane distortion induced axial stresses. The high stresses in the X direction cause the initiation of vertical cracks as shown in Figure (a). The high stresses in the Y direction may cause failure of the stiffeners web welds ending in stiffener detachment. Similarly, high stresses in the Z direction may cause horizontal cracks. The maximum tension component of the principal stress (S1) is a critical force for initiating cracks.



S_x = Stress in X-direction i.e. along the length of the girder (Refer to Figure a)
 S_y = Stress in the Y-Direction i.e. perpendicular to the length of the girder (Refer to Figure b)
 S_z = Stress in the vertical direction i.e. along the depth of the girder (Refer to Figure c)
 S₁ = Maximum principal stress (See Figure d)

The table shown below contains a summary of out-of-plane distortion induced stresses and maximum deflections for interior and exterior girders at near pier 10 (Negative Moment Region) and middle of span 11 (Positive Moment). The following cases are presented: Composite and non-composite structural performance and Phase I of MOT Scheme (5+1).

	Stress (ksi) Interior				Stress (ksi) Exterior				Max Deflection (in)	
	S _x	S _y	S _z	S ₁	S _x	S _y	S _z	S ₁	Interior	Exterior
MOT (5+1) - Phase I										
Mid Span	80	26	25	100	25	17	25	38	0.054	0.03
Near Pier	50	23	20	51	30	17	20	35	0.02	0.04
EXISTING DECK - NON COMPOSITE DECK										
Mid Span	54	20	21	55	#	#	#	#	0.0216	#
Near Pier	20	12	14	22	49	18	34	66	0.01	0.024
EXISTING DECK MODELED AS COMPOSITE (BENCHMARK)										
Mid Span	45	7	11	46	26	4	11	27	0.024	0.0132

Note: # Based upon preliminary analysis, the interior girder controlled the design. Therefore only the interior girder was analyzed



As stated in Fisher (1985), these out-of-plane stresses are caused by bridge members moving in three dimensions. The lateral movement, y-axis, is termed as out-of-plane displacement and is caused by lateral bracing or transverse beams.

Volume II of this report includes the following information for interior and exterior girders in both the negative and positive moment regions of span 11:

- o Out-of-plane distortion contours at the top and bottom
- o Out-of-plane stresses (S_x, S_y, S_z and S₁)

3-D FINITE ELEMENT MODELING OF CUY-480-18.42 DECK REPLACEMENT

The figures on this page show the typical stress distribution due to out-of-plane distortions caused by the forces in the floorbeams and crossframe members. Out-of-plane distortion behavior is depicted as follows: Distortion or deformed shape is shown in figure (a), the stress concentrations at the connection plates are provided in figures (b) and (c). The out-of-plane stresses are plotted and shown in figure (d), four components (S_x , S_y , S_z , S_1) are shown.



(c) (d)
Figure 25 Typical Stress Distribution due to out-of-plane Distortion

The modeling of existing conditions provided a benchmark for comparison with the phase construction stress levels. The non-composite assumption yielded overstresses that the current bridge does not reveal. The existing, condition were also modeled considering composite action which yielded stresses below the yield strength of the material, thereby reflecting more accurately the anticipated performance of the existing structure. Therefore, the existing structure modeled as composite serves as the final benchmark for comparison with the phase construction model.

Figures 26 through 30 show the FE mesh and boundary conditions for the aforementioned benchmark (Positive Moment Region – Existing Conditions). Figures 31 through 46 show out-of-plane stress contours (S_{xx} , S_{yy} , S_{zz} and S_1) for top and bottom flanges of Girders E & F.

Results in the Positive Moment Region – Existing Conditions (Composite)




Figure 26 Composite FE model for Girder E and F




Figure 28 BC – Plane of Symmetry




Figure 27 Composite FE Model for Girder E and F




Figure 29 BC – Plane of Symmetry in the Composite FE model




Figure 30 Results – Deformed Mesh for the Composite Model

Loadcase: 17:Group 4
Results file: I480 - LOC 6 (18).mys
Entity: Stress (top) - Thick Shell
Component: SX





Figure 31 Positive Moment – Girder E – Top Flange Sxx

3-D FINITE ELEMENT MODELING OF CUY-480-18.42 DECK REPLACEMENT




Figure 32 Positive Moment – Girder E – Top Flange Syy




Figure 33 Positive Moment – Girder E – Top Flange Szz




Figure 34 Positive Moment – Girder E – Top Flange S1




Figure 35 Positive Moment – Girder E – Bottom Flange Sxx

3-D FINITE ELEMENT MODELING OF CUY-480-18.42 DECK REPLACEMENT




Figure 36 Positive Moment – Girder E – Bottom Flange Syy




Figure 38 Positive Moment – Girder E – Bottom Flange S1




Figure 37 Positive Moment – Girder E – Bottom Flange Szz




Figure 39 Positive Moment – Girder F – Top Flange Sxx

3-D FINITE ELEMENT MODELING OF CUY-480-18.42 DECK REPLACEMENT




Figure 40 Positive Moment – Girder F – Top Flange Syy




Figure 42 Positive Moment – Girder F – Top Flange S1




Figure 41 Positive Moment – Girder F – Top Flange Szz




Figure 43 Positive Moment – Girder F – Bottom Flange Sxx

3-D FINITE ELEMENT MODELING OF CUY-480-18.42 DECK REPLACEMENT




Figure 44 Positive Moment – Girder F – Bottom Flange Syy




Figure 46 Positive Moment – Girder F – Bottom Flange S1





Figure 45 Positive Moment – Girder E – Bottom Flange Szz

Fisher's s - Δ Expression

The web gap stress calculation due to the out-of-plane distortion, which is shown in the figure below, was established by Fisher (1998). The expression indicates that the bending effect due to out-of-plane distortion causes a stress that increases proportionally with Young's modulus (E), out-of-plane distortion (Δ), and the web thickness. The stress(s) is inversely proportional to the square of web gap length. In the expression, a fixed end moment is computed based on the distortion for the stress computation.

The Table 7 shows a summary of the calculated stress(s) using Fisher's formula. The out-of-plane distortion (Δ) was calculated using the sub-models. The computation is a means to perform hand calculations which indicate even small displacement will yield large stresses, which is the case for the existing structure.



$$\sigma = \frac{My_c}{I} = \frac{6EI\Delta}{L^2} \left(\frac{t_w}{2}\right) \left(\frac{1}{I}\right) = \frac{3E\Delta t_w}{L^2}$$

σ = web gap bending stress (ksi)

M = web gap bending Moment (Kips-in) = $\frac{6EI\Delta}{L^2}$ (fixed end beam moment)

y_c = distance from neutral axis to extreme fiber (in.)

I = Moment of Inertia (in.⁴)

E = Young's Modulus (ksi)

L = Web gap Length (in.)

Δ = out-of-plane displacement (in.)

t_w = web thickness (in.)

Table 7 Summary of out-of-plane distortion (Δ) and the Out-of-Plane bending stress (calculated using Fisher's Formula)

Girder/Location	Web Gap Length (L)	Out of Plane Displacement (Δ) - inches	Thickness of Web (t_w)	E (ksi)	Stresses Using Fisher's Formula
Existing Deck (Considering Composite Action)					
Ext Girder E or H - Midspan 11	1	0.0132	0.4375	29000	>> Yield Strength
Int Girder F or G - Midspan 11	1	0.024	0.4375	29000	>> Yield Strength
Existing Deck (Non Composite)					
Ext Girder E or H - Pier 10	1	0.024	0.5625	29000	>> Yield Strength
Int Girder F or G - Midspan 11	1	0.0216	0.4375	29000	>> Yield Strength
Int Girder F or G - Pier 10	1	0.01	0.5625	29000	>> Yield Strength
MOT ALT 2 - Phase I (without retrofit)					
Ext Girder E or H - Midspan 11	1	0.03	0.4375	29000	>> Yield Strength
Ext Girder E or H - Pier 10	1	0.04	0.5625	29000	>> Yield Strength
Int Girder F or G - Midspan 11	1	0.054	0.4375	29000	>> Yield Strength
Int Girder F or G - Pier 10	1	0.025	0.5625	29000	>> Yield Strength

As indicated above, the out-of-plane bending stresses well exceed the material yield strength for all conditions. It should be noted that if the out-of-plane displacement doubles or triples as shown in the above table. It is safe to assume based on the simplified expression that the stresses will also double or triple for phase construction. Therefore, retrofit details are required to prevent displacement.

V. Retrofit Options to Control Out of Plane Distortion

As stated in Fisher (1985), three techniques can be used to control out-of-plane distortions:

- (1) Drill holes at each end of the high stress areas.
- (2) Remove a segment of the connection plate near the stress area to lengthen the web gap.
- (3) Bolt the connection plate to the tension flange in the bridge's negative moment areas.

Partial Removal of Connection Plate

Option 2 was studied by removing approximately 6 inches of connection plate (top and bottom) as shown below. As presented in Section VI of this report, Option 2 caused an increase in out-of-plane distortion induced stresses.






Figure 47 Positive Moment - Interior – FE model after shorten the CF stiffeners



If a piece of the stiffener nearest the location of potential cracks is removed, the web gap length is thereby increased and bending stresses in the web are reduced. In some cases this step plus holes drilled at each crack's ends will prevent further crack growth.

Rigid Connection Retrofit

A bolted connection of the stiffener to the flange is assumed to limit out-of-plane rotation (stresses). Stresses were calculated to assess the effectiveness of this type of connection. Various retrofit options are available to make this connection. Figures 48 – 50 show views of FE mesh used for the modeling of a rigid connection retrofit.





Figure 48 FE Model - Stiffeners Connected to Girder Top Flange




Figure 49 FE Model - Stiffeners Connected to Girder Bottom Flange




Figure 50 FE Model - Stiffeners Connected to Girder Top Flange

VI. Effectiveness of Finite Element Modeling in Predicting Out-of-Plane Distortion Induced Stresses in Bridges

When the adjacent girders deflect unequally under traffic loading, the end of the transverse structural member is forced to rotate, pulling the unstiffened portion of the girder web out-of-plane, creating high secondary stresses at the connection plate end and leading to possible conditions for fatigue cracking. Unlike load-induced fatigue, procedures for prediction of distortion-induced stresses are not in bridge design specifications. Procedures for determination of secondary stresses are not specified in the design or rating process.

The LARSA 4D computer program (version 7.05.35) was used for the 3-D Finite Element Modeling of the eastbound structure (Right Bridge). In the 3-D Model, flanges of girders, floorbeams and stringers were modeled using line/beam elements while the webs were modeled using plate/shell elements. The elements of cross frames and lateral bracing were modeled using line/beam elements. The 3-D FE model was developed using LARSA 4D to create a model that is referred to as a coarse-model. In order to compute out-of-plane distortions, sub-models were prepared using the LUSAS program. This process involved obtaining the forces and moments at the boundary nodal locations from the coarse-model and then applying boundary conditions to the sub-models. The next step was to analyze sub-models and ensure compatibility of the deformed shape of the girders/stringer and stringers between the sub-models and coarse-models. This course-model/sub-model process is required because a single model would result in an unusually large computer model to compute the out-of-plane stresses.

A literature search indicates that the applied procedure as described above is logical, rational and appropriate for this structural performance evaluation. We acknowledge that generally it is preferred to utilize field instrumentation to make measurements so that a calibration process can be used for understanding this relatively large finite element model. However, it is not practical to expect to be able to measure the out-of plane strains. Our literature search indicates that statistically we can estimate that the computed strains can be expected to be within approximately 10% of actual field strain values.

3-D FINITE ELEMENT MODELING OF CUY-480-18.42 FOR HALF WIDTH DECK REPLACEMENT

VII. Summary

Multilevel 3-D Finite Element modeling designs were developed for the right bridge. The models were used to evaluate:

- The deflections and out of plane movements caused by part-width construction scenarios and
- Possible impacts to fatigue prone bridge components. (Since retrofits were found to be required as a result of this portion of the study, fatigue life of the existing details was not addressed).


Field observations indicate that the existing deck and steel beams are in full contact and that composite action typically occurs even without a positive connection. Therefore, the stresses determined from modeling the deck and girders as a composite structure were used as the baseline stresses. To ensure a safe deck replacement protocol, it is recommended that the baseline stresses, assuming composite action (only for lateral restraint), should not be exceeded for any deck replacement scheme or MOT sequence.

The overall characteristics of out-of-plane distortion and induced stresses are higher in the positive moment regions, because relatively large differential girder deflections are present. In the negative moment regions near the pier support, the stresses were determined to become smaller.

Retrofit details were evaluated with the objective of controlling distortion-induced stresses. The results from those analyses are presented below.

For the partial removal of the connection plate in the positive region, the available length is less than required 12 inches. According to NCHRP 336, to efficiently release the restrained web, a minimum cut-short dimension of 12 inches or 20 times of the web thickness, whichever is larger, is recommended. Based upon the analysis, available dimensions were found to be inadequate for web gap stress release.

Of the two retrofit options to control out-of-plane distortion, only the rigid plate connection alternative was able to reduce the out-of-plane stresses. This option uses a bolted angle to provide rigid load paths for transmitting forces from the transverse members into the longitudinal girders.



	Stress (ksi) Interior				Stress (ksi) Exterior				Max Deflection (in)	
	Sx	Sy	Sz	S1	Sx	Sy	Sz	S1	Interior	Exterior
MOT (5+1) - Phase I										
Mid Span	80	26	25	100	25	17	25	38	0.054	0.03
Near Pier	50	23	20	51	30	17	20	35	0.02	0.04
EXISTING DECK - NON COMPOSITE DECK										
Mid Span	54	20	21	55	#	#	#	#	0.0216	#
Near Pier	20	12	14	22	49	18	34	66	0.01	0.024
EXISTING DECK MODELED AS COMPOSITE (BENCHMARK)										
Mid Span	45	7	11	46	26	4	11	27	0.024	0.0132
MOT (5+1) - PHASE I -- RETROFIT - PARTIAL REMOVAL OF CONNECTION PLATE										
Mid Span	80	8	288	298	#	#	#	#	0.72	#
Near Pier	20	7	14	22	#	#	#	#	0.12	#
MOT (5+1) - PHASE I - RETROFIT - RIGID CONNECTION PLATE										
Mid Span	44	10	9.7	45	24	8	5	25	0.036	0.012
Near Pier	4	6	4	13	8	6	6	11	0.002	0.036

Note: # Based upon preliminary analysis, the interior girder controlled the design. Therefore only the interior girder was analyzed.

Out-of-plane distortion causes very high stresses in the localized region around the web gap. The Figure below shows the cracks due to the various components of out-of-plane distortion induced axial stresses. The high stresses in the X direction cause the initiation of vertical cracks as shown in Figure 51(a). The high stresses in the Y direction may cause failure of the stiffeners web welds leading to stiffener detachment. Relatively high stresses in the Z direction may also cause horizontal cracks. The maximum tension component of the principal stress (S1) is also a critical measure for potential crack initiation.




Figure 51 Cracks due to different axial stresses.

Comparison of Pre-Retrofit and Post-Retrofit Factored **Out-of-plane Stresses** at Mid-span (Alt 2.Phase 1).

		Positive Moment				Negative Moment				Stress Range			
		Sx (ksi)	Sy (ksi)	Sz (ksi)	S1 (ksi)	Sx (ksi)	Sy (ksi)	Sz (ksi)	S1 (ksi)	Sx (ksi)	Sy (ksi)	Sz (ksi)	S1 (ksi)
Before Adding Rigid Connection	Top Flange	80	26	25	100	33	7	70	71	47	19	45	31
	Bottom Flange	63	10	45	100	17	4	47	48	46	6	2	54
Rigid	Top Flange	0	0	0	0	3	8	4	4	3	8	4	4
	Bottom Flange	44	10	9.7	45	0	0	0	0	44	10	9.7	45


CONSIDERATION OF INSTRUMENTATION FOR VERIFICATION OF THE 3-D MODEL

Retrofit options to control out-of-plane distortions were evaluated using 3-D Finite Element Computer Models. Consideration was given to instrumenting the girders for the purpose of validating the 3-D models. The instrumentation on the girders can be used to provide data for refinement of the computer model.


The use of instrumentation was discussed with Professor Dennis R. Mertz, Ph.D.,P.E.. He indicated that the comparison of FE-calculated distortion-induced stresses with field-measured stresses is not so simple or even informative. He reflected from his past experience where he had difficulty trying to measure the out-of-plane stresses in in-service bridges. He stated that, “It is very difficult to place gages and measure these stresses since the web gaps are so small, the strain gages are relatively large and the stress gradients in the gap are large also. The stresses are a maximum at the weld toe yet the center of the gage will be relatively far from the toe. In the end, the measured stresses are really extrapolated stresses not capturing the stress-concentration effect.”

He also stated “as our analytical techniques have matured, I think that it is no longer necessary to try to compare or calibrate FE results with field-measured results. In both cases, I believe that trends can be observed but the actual magnitude of the stresses is not readily obtainable. In my opinion, field measuring out-of-plane distortion-induced stresses is a waste of resources and a distraction.”

3-D FINITE ELEMENT MODELING OF CUY-480-18.42 FOR HALF WIDTH DECK REPLACEMENT



TYPICAL RETROFIT DETAIL



TYPICAL RETROFIT ELEVATION

**PART II
HALF-WIDTH DECK REMOVAL STUDY**

Introduction

Part I of this study consisted of the development of multilevel 3-D finite element (FE) models used to evaluate deck replacement options. The existing superstructure was modeled and analyzed to establish the present operating condition (maximum stresses) as a benchmark for the performance of the existing structure during the replacement of the deck. The existing girders, stringers and crossframes were evaluated by applying the existing live load and dead load condition. Code checks were performed according to the AASHTO Standard Specifications. The results of the analyses indicated that all primary (in-plane) stresses due to moments and shears were acceptable.

The 3-D FE models provided predictions for superstructure deflections, out-of-plane movements, and possible impacts to fatigue prone bridge components, caused by removing dead load and live load during part-width construction operations. The overall characteristics of out-of-plane distortion and induced stresses were the highest in the positive moment regions because relatively large differential girder deflections are present at the mid-span. At the negative moment regions near the pier supports, the differential deflections were much lower in magnitude.

The 3-D FE models were used to evaluate proposed retrofit details, with the objective of controlling distortion-induced stresses. Of the two retrofit options used to control out-of-plane distortion, only the rigid plate connection alternative was able to reduce the out-of-plane stresses. The rigid plate connection option uses a bolted angle that provides rigid load paths for transmitting forces from the transverse members into the longitudinal girders.

The Part I study results indicate that using part-width deck replacement construction methods with retrofit details was most likely feasible. Therefore, considering maintenance of traffic preferences, ODOT decided to evaluate various lengths of half-width deck removal segments as the main task to be performed and documented in Part II of Volume I. Using the FE models, the deflections and out-of-plane movements caused by the half-width construction loading conditions were computed and evaluated. The stress related impacts to fatigue prone bridge components were studied.

In 1989, retrofits were applied to the stiffener-floorbeam connections in conjunction with the placement of a concrete overlay on the original decks. The retrofits included additional welding at the top flange in the positive moment regions and the removal of 12 inches of the stiffeners in the negative moment regions. The crossframe locations at the piers were not retrofitted. Analyses of the negative moment retrofit locations, using the 3-D model, indicated that the retrofits applied to the superstructure did not help to improve or modify the performance of crossframes, as shown by the results provided in Table 8 (page 44). Note that the presence of the deck provides restraint to the top flange of the stringers which is an important contribution to the resistance against out-of-plane movements.

Several half-width deck removal segment lengths were evaluated for the purpose of establishing a preferred design. The preferred design should permit the replacement of the deck for one of the twin structures in one

construction season. Multilevel 3-D finite element models were used to evaluate the girder and beam live load and dead load deflections and out-of-plane movements caused by the part-width construction removal of the deck. After evaluating numerous deck removal alternatives, removing a 300 foot long half-width segment centered over a pier was found to be the best construction procedure. Maximum out-of-plane stresses and out-of-plane deflections for a 300 foot long half-width deck removal at various locations along the length of the bridge are presented in Table 9 (page 49).

A project cost estimate and construction schedule are provided in Appendix A. The planning level construction schedule has been provided for the purpose of predicting if it is reasonable to expect a contractor to be able to construct the bridge decks in half-width 300 foot segments in one construction season.

Reconnaissance Information Obtained for Verification of As-Built Conditions

The 3-D FE model prepared to evaluate the originally designed bridge was modified to include the 1989 retrofit details. The 1989 negative moment rehabilitation plans were obtained from the District 12 plan archive files. After reviewing the plans, ELR personnel performed a limited field review of the superstructure during a site visit on May 30, 2012. The purpose of the site visit was to confirm that the retrofits shown in the 1989 plans were performed as detailed and that the retrofits were performing as intended. The two 2" diameter holes drilled at each end of the cracks at the bottom of the transverse stiffeners, where the gusset plate is welded to provide wind bracing, were performing satisfactorily. All fatigue retrofits on the girders that were inspected appear to be functioning as intended, as was confirmed in the latest bridge inspection reports.

The retrofit removal details for the top 12" of the transverse stiffeners in the negative moment region were visually identified, but were not measured to verify the exact dimensions. The web removal details matched the proportions and details shown in the 1989 retrofit plans. The latest bridge inspection report states that there are some overcuts/nicks in the web where the crack arrest holes are drilled; overcuts were not located in the areas of the girders that were inspected.

ELR personnel had discussions with current and past ODOT personnel (Jim Barnhart, George Maki, David Leake, Bonnie Teeuwen, Mike Malloy, and Scott Slack) for the purpose of gaining knowledge of the work that has previously been performed on these superstructures. District 12 has had a history of dealing with several problems related to full depth girder cracks on multi-girder bridges as a result of the details similar to those used for the CUY-480 superstructure. Rather than reacting to cracks after the fact, ODOT promoted the policy of retrofitting known problem details before they could result in undesirable full depth cracks.

District 12 was proactive in trying to minimize future cracking problems in their bridges by retrofitting structural members that were known to cause problems due to out-of-plane fatigue cracking. This decision was driven primarily by the problems with the I-77 Kingsbury Run Bridge as well as other bridges where fatigue cracking had led to full depth girder cracking. The floorbeam attachment retrofit details used on the




3-D FINITE ELEMENT MODELING OF CUY-480-18.42 FOR HALF WIDTH DECK REPLACEMENT

CUY-480 superstructure were developed sometime before the details were developed for the lower lateral retrofits. The primary focus was on the twin girder/floorbeam connections because of non-redundancy issues with twin girder bridges. The initial goal was to minimize the occurrence of cracks due to out-of-plane bending at connections. When a significant crack occurred, emergency contracts were used to provide the repair details. By being proactive, District 12 was able to minimize the necessary number of emergency repair contracts. Even though the CUY-480 Bridge was not a non-redundant twin girder bridge, the structural steel had a history of undesirable fatigue cracking, therefore, since these twin bridges are very significant structures, proactive retrofits were utilized to help minimize the development of future cracking issues.



Superstructure Retrofits Performed in 1989

When the concrete overlay was placed in 1989, ODOT performed two types of retrofits to the stiffener-floorbeam connections:

- At the positive moment regions, where the top flange is in compression, additional welding was provided.
- At the negative moment regions, but not at the pier locations, the stiffeners were retrofitted by cutting out 12 inches of the stiffeners.



STIFFENER RETROFIT - COMPRESSIVE FLANGE



STIFFENER RETROFIT - NEGATIVE TENSION FLANGE

The 1989 retrofits consisted of the removal of 12 inches of the stiffener. This retrofit detail was evaluated for its ability to modify the out-of-plane distortion induced stresses. The interior girder was analyzed near Pier 10 in Span 11. The LARSA 4-D model of the entire bridge (coarse model) was utilized to obtain the forces and moments at the boundary nodal locations. As documented in Part I of this Volume, a finer mesh was used for evaluating out-of-plane displacements in the superstructure components.

Table 8 Comparison of Pre and Post 1989 Retrofits; Factored Out-of-plane Stresses in Span 11 near Pier 10

	Stress (ksi) Interior		
	Sx	Sz	S1
COMPARISON OF PRE & POST 1989 RETROFITS - NEAR PIER LOCATION			
Pre 1989	6.7	2.9	6.9
Post 1989	5.2	3	6.8

As shown in the table above, the 1989 retrofits were only moderately successful in reducing the out-of-plane distortion induced stresses.

Maintenance of Traffic

Maintenance of traffic is a key component of the CUY-480-18.42 project. The urban-interstate features of this project location along with the constraints associated with removing the existing deck make the design of a desirable maintenance of traffic plan a challenging engineering exercise. The design of a maintenance of traffic scheme that is safe, efficient, and cost effective is a paramount feature of this deck replacement project.

The ODOT Permitted Lane Closure Map/Schedule stipulates that four lanes of traffic in each direction shall be maintained on I-480. There are periods where traffic can be reduced to three lanes in each direction, but those times are for a short durations during nighttime and weekend periods. A reduction to two lanes is permitted, but only during nighttime periods. Due to the nature of the project's construction, these lane reductions are not feasible to perform long-term construction activities, but may be beneficial for delivering materials to the construction site. The scope of services for the project states that for maintenance of traffic, it is desired to maintain three lanes of traffic for both directions. This was used as the minimum number of lanes for each maintenance of traffic scheme analyzed.

Currently, there are four eastbound lanes on I-480 that taper to three lanes just west of I-77. I-480 continues as three eastbound lanes under I-77 and becomes four lanes on the CUY-480-18.42 bridge when I-77 merges into I-480. I-77 traffic to I-480 eastbound consists of two lanes that were formed by two southbound lanes merging with 1 northbound lane. The right lane of I-480 eastbound merges with the left lane of the I-77 ramp traffic. I-480 eastbound continues as four lanes east of the bridge and has a diverge lane to the E 98th Street/Transportation Boulevard interchange.

I-480 westbound is four lanes east of the CUY-480-18.42 bridge with a merge lane from the E 98th Street/Transportation Boulevard interchange. I-480 continues as four lanes across the bridge and has a 3-2 split where three lanes go to I-480 westbound and two lanes to I-77. The I-77 ramp has a 2-1 split with two lanes going to I-77 northbound and one lane to I-77 southbound.

It is anticipated that standard construction drawings can be used for lane reductions on I-480 from four lanes to three. Additional signing can be utilized to provide motorists guidance on the lane reductions, shifts, and/or closures. A contra flow MOT scheme is a potential solution. This will require significant advance signing to notify the motorists of the contraflow configuration and the loss of access to ramps from the crossover contraflow lanes. It may be necessary to utilize diagrammatic signing for the contraflow maintenance of traffic scheme.

The existing structures are typically 69.5' wide toe to toe of existing parapets. It was assumed that 12' lanes, one foot minimum barrier offsets, two foot portable concrete barrier (PCB), and a one foot minimum offset behind the PCB would be utilized during maintenance of traffic. Different maintenance of traffic schemes have been investigated to determine the scheme that maintains the required number of lanes in a safe and cost efficient manner. The proposed deck will remain at 69.5' toe to toe of proposed parapets,

3-D FINITE ELEMENT MODELING OF CUY-480-18.42 FOR HALF WIDTH DECK REPLACEMENT

except for the western end of the eastbound deck which widens to 85'. To facilitate construction, the use of stay in place forms is anticipated. For this project, there is a preference to locate the deck construction joint over a girder.

Part-Width Construction- No Crossover:

If traffic was not crossed over the median and part-width construction with three lanes of traffic in each direction was utilized, then 41' of width in each phase, and 82' total width would be needed. The project does not involve widening the structures, so it was determined that part-width construction with three lanes in each direction is not feasible.

Total Traffic Crossover Option:

The total traffic crossover option with three lanes in each direction would require 78 feet of width. The project does not involve widening the structures, so it has been determined that crossover construction with three lanes in each direction is not desirable. A total traffic crossover using the 69.5' width would limit the lanes to 10.5' each with one foot barrier offsets. The other obstacles to providing a total traffic crossover are as follows: A total traffic crossover option would allow for uninterrupted access for the bridge construction, but provide difficulties with maintaining ramp access and crossover geometrics. On the western end of the bridge, if traffic is crossed over to the westbound structure, then access from I-77 SB and NB to I-480 eastbound would be difficult. This is due to having to cross over from the eastbound side of I-480 to the westbound side of I-480 in the short distance between the Brecksville Road overpass bridge and the CUY-480-18.42 abutment, which is only about 600' +/- . Speed reductions may be necessary to facilitate these geometrics. It could be determined that this ramp movement would need to be detoured if the geometrics could not be worked out. When traffic is crossed over on the westbound structure, access to the eastbound I-480 to E. 98th Street/Transportation Boulevard ramp would be difficult. The existing off-ramp is in close proximity to the CUY-480-18.42 abutment so a temporary ramp and/or pavement may be required to provide access for this movement or this movement may need to be detoured if geometrics cannot be worked out. When traffic is crossed over to the eastbound structure, the E. 98th/Transportation Boulevard to I-480 westbound and the I-480 westbound to I-77 NB and SB ramp movements would be difficult due to their proximity to the CUY-480-18.42 abutments and the Brecksville Road overpass.

Since the part-width and total crossover options do not safely maintain three lanes in each direction on the existing structures, it was determined that a contra flow style maintenance of traffic scheme should be utilized. The contra scheme will be able to maintain more lanes of traffic while providing access to the ramps in a safe and efficient manner. Ramp traffic will most likely be shifted, but will utilize the existing ramp pavement and shoulders. A contraflow maintenance of traffic scheme is the recommended option for redecking the structure while providing the minimum number of three lanes in each direction.

Contraflow Crossover to Westbound Bridge:

This option could be phased so that there are three westbound and two eastbound lanes on the existing westbound bridge. The existing eastbound bridge would provide for two eastbound lanes (one lane from I-480 eastbound merging with two lanes from I-77). The eastbound bridge will be constructed part-width (in halves) in two phases by utilizing the existing deck and then the newly constructed deck. This option will allow three lanes of I-480 westbound traffic and provide four lanes for I-480 eastbound traffic (two lanes crossed over and two lanes on the eastbound bridge).

Contraflow Crossover to Eastbound Bridge:

Once the eastbound bridge is completed, 2 lanes of I-480 westbound traffic will now be crossed over to the eastbound structure and the westbound structure will be completed part width in two phases similar to the eastbound structure. There can be 3 eastbound lanes and two westbound lanes on the eastbound bridge, with 2 westbound lanes on westbound bridge. In both phases, westbound I-480 traffic will be able to access the I-77 ramps.


Contraflow Summary:

The contraflow maintenance of traffic option reduces capacity by one lane in each direction during different construction seasons. There will be four lanes in one direction and three lanes in the opposite direction per phase. All crossovers and maintenance of traffic zones provide a minimum of two lanes. This is extremely advantageous if a breakdown were to occur. For these reasons, the contraflow crossover scheme as described above is the recommended configuration.

If the CUY-77.9.50 project was under construction at the same time as the CUY-480-18.42 project, there may be potential for conflicts with the physical MOT zones. Coordination between the projects would be required, mainly, for Ramp E-N, I-480 westbound to I-77 northbound and Ramp N-E, I-77 southbound to I-480 eastbound, both 2 lane ramps. In certain phases of the CUY-77-9.50 MOT, these ramps are restricted to one lane. If these projects were constructed at the same time, it may be desirable to keep these ramps as one lane ramps where it would benefit both projects.

The next two pages in the report provide the deck replacement phase construction work dimensioned in section views of the superstructure.

3-D FINITE ELEMENT MODELING OF CUY-480-18.42 FOR HALF WIDTH DECK REPLACEMENT




P:\90591\structures\480_1842\PC001.dgn B/2/2012 10:01:13 AM fbawani

* - PORTABLE CONCRETE BARRIER
*** - THE CONTRACTOR WILL BE GIVEN TEMPORARY ACCESS DURING NON PEAK TRAFFIC HOURS, BY MEANS OF THE LANE LOCATED ADJACENT TO THE WORK

E.L. ROBINSON <small>INCORPORATED</small>											
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 50%;">DESIGNED</td> <td style="width: 50%;">CHECKED</td> </tr> <tr> <td>DRAWN</td> <td>REVIEWED</td> </tr> <tr> <td>FIB</td> <td>REVISION</td> </tr> </table>	DESIGNED	CHECKED	DRAWN	REVIEWED	FIB	REVISION	<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 50%;">DATE</td> <td style="width: 50%;">FILE NUMBER</td> </tr> <tr> <td>1812521 & 1812548</td> <td>1812521 & 1812548</td> </tr> </table>	DATE	FILE NUMBER	1812521 & 1812548	1812521 & 1812548
DESIGNED	CHECKED										
DRAWN	REVIEWED										
FIB	REVISION										
DATE	FILE NUMBER										
1812521 & 1812548	1812521 & 1812548										
PHASE CONSTRUCTION DETAILS CUY-480-18.42 L&R I-480 OVER CUYAHOGA RIVER VALLEY											
CUY-480-18.42 PID No. 90591											
1 / 2											

3-D FINITE ELEMENT MODELING OF CUY-480-18.42 FOR HALF WIDTH DECK REPLACEMENT



E.L. ROBINSON
INC.
100 Water Street, Suite 300 - Columbus, Ohio 43215

DESIGNED	DFT	CHECKED
DRAWN	FIB	REVISION
REVIEWED	DATE	STRUCTURE FILE NUMBER
		1812521 & 1812548

PHASE CONSTRUCTION DETAILS
CUY-480-18.42 L&R
I-480 OVER CUYAHOGA RIVER VALLEY

CUY-480-18.42
PID No. 90891

2 / 2




P:\90591\structures\480-1842\PC001.dgn 8/2/2012 9:59:37 AM fbawani


Deck Removal Segments

The goal of this study is to develop a plan to replace the deck for one of the twin structures in one construction season, and then replace the adjacent superstructure deck in the following construction season. The following half-width deck removal segments were evaluated for out-of-plane distortion induced stresses. The results of these out-of-plane distortion evaluations were used to formulate a one construction season deck replacement plan. The following options were evaluated:


1. 150 feet deck removal centered over a pier, 75 feet removed on each side of the pier
2. 150 feet deck removal centered at mid-span.
3. 300 feet deck removal from centerline of pier to centerline of pier
4. 300 feet deck removal centered over a pier, 150 feet removed on each side of the pier.
5. 600 feet deck removal centered over a pier, 300 feet removed on each side of the pier




1) 150 feet Deck Removal – 75 feet on each side of pier




2) 150 feet Deck Removal at mid-span



3) 300 feet Deck Removal – Pier to pier



4) 300 feet Deck Removal – 150 feet on each side of pier




5) 600 feet Deck Removal

3-D FINITE ELEMENT MODELING OF CUY-480-18.42 FOR HALF WIDTH DECK REPLACEMENT

Out of Plane Distortion Induced Stresses for the Half-Deck Removal Segments

Multilevel 3-D finite element models were developed for the right bridge. The models were used to evaluate the girder and beam deflections and out-of-plane movements caused by the part-width construction removal of live load and dead loads. The impacts to fatigue prone details were also evaluated.

As stated in Part I of this report, the LARSA 4-D model of the entire bridge is considered to be a coarse model. Sub-models were prepared using the LUSAS program because the LUSAS program has the ability to provide advanced mesh generation features which use a finer mesh for evaluating the out-of-plane displacement in the superstructure components. These sub-models are necessary to compute the out-of-plane distortions and related stresses to a reasonable desired accuracy.



Properties Assignment in the Sub-Model

Sub-models capturing the relevant three-dimensional out of plane displacements were prepared. Relative stress level results were computed for the following span removal segments:

1. 150 feet deck removal, 75 feet on each side of the pier
2. 150 feet deck removal centered at mid-span.
3. 300 feet deck removal, centerline of pier to centerline of pier
4. 300 feet deck removal, 150 feet on each side of the pier
5. 600 feet deck removal, centered over a pier

Table 9 (page 49) provides a comparison of the out of plane distortion induced stresses for the half-deck removal segments listed above.


When the 300 feet long deck segment is removed, centerline of pier to pier, there is a significant increase in the out of plane stresses, especially for the exterior girder. When a 300 feet long segment **centered** at a pier

is removed, the resulting distortion induced stresses are acceptable because the stresses are less than the 46 ksi benchmark stress; therefore retrofits are not necessary when this removal option is used. Based on the results of these analyses, additional evaluation work was performed for the purpose of understanding the deck removal option where 300 feet of deck is removed in segments centered over a pier.

Table 9 Comparison of out-of-plane distortion induced stresses (factored) for half-deck removal segments

	Stress (ksi) Interior				Stress (ksi) Exterior			
	Sx	Sy	Sz	S1	Sx	Sy	Sz	S1
(1)	At Near Pier - Deck Removal (150 ft) - 75 ft on each side of the Pier							
After Deck Removal	2	10	15	17	2	5	2	7
Existing w/ 1989 Retrofit	5.2	1	3	6.8	#	#	#	#
(2)	At Mid Span - Deck Removal (150 ft - mid span)							
After Deck Removal	43	4	16	44	40	2	8	41
Existing	45	7	11	46	26	3	11	27
(3)	At Mid Span (300 ft Deck Removal) - CL Pier to CL Pier							
After Deck Removal	43	1	14	44	46	4	18	47
Existing	45	7	11	46	26	3	11	27
(4)	At Mid Span (300 ft Deck Removal - 150 ft on each side of the pier)							
After Deck Removal	30	2	6	31	24	1	6	25
Existing w/ 1989 Retrofit	45	7	11	46	26	3	11	27
(5)	600 ft Deck Removal - MIDSPAN of SPAN 11							
After Deck Removal	48	3	10	49	49	4	15	49
600 ft Deck Removal - MIDSPAN of SPAN 12								
After Deck Removal	50	11	7	51	46	12	9	47
Existing	45	7	11	46	26	3	11	27

Based on preliminary analyses, the interior girder controlled. Therefore, only the interior girder was analyzed.




- Sx = Stress in x-direction i.e. along the length of the girder (Refer to Figure a)
- Sy = Stress in the y-direction i.e. perpendicular to the length of the girder (Refer to Figure b)
- Sz = Stress in the vertical direction i.e. along the depth of the girder (Refer to Figure c)
- S1 = Maximum principal stress (Refer to Figure d)


3-D FINITE ELEMENT MODELING OF CUY-480-18.42 FOR HALF WIDTH DECK REPLACEMENT

Evaluation of the Removal of the 300 feet long Half-Width Deck Segment

Since the out-of-plane stresses are at acceptable levels when the removal of a 300 feet long half-deck segment is centered at a pier, retrofits are not required for this option. Multilevel 3-D finite element modes were developed for the sequence of the deck removal segments in UNIT 4 as shown below.



The figure below provides a location key for the results of the analyses. The change in color of the segments represents the limits of the each deck removal segment.



LOCATION NUMBERING FOR SUB-MODELS


3-D FINITE ELEMENT MODELING OF CUY-480-18.42 FOR HALF WIDTH DECK REPLACEMENT

Table 10 Summary of the out-of-plane distortion induced stresses (factored loads) and for the unfactored deflections for a 300 feet half-deck removal segment centered at a pier:

	Location	Stress (ksi) Interior				Stress (ksi) Exterior				Out-of-Plane Distorsion	
		Sx (ksi)	Sy (ksi)	Sz (ksi)	S1 (ksi)	Sx (ksi)	Sy (ksi)	Sz (ksi)	S1 (ksi)	Interior (in)	Exterior (in)
SPAN 10	03	1	3	3.4	3.6	6.1	5.0	3.7	6.4	0.00756	0.00402
	06	8.2	5	22	24	10.5	4.0	19	20	0.01800	0.02400
	08	30	6	9.5	31	22	4.2	3	23	0.04200	0.04200
	10	30	6	29	31	22	4.9	18.5	22	0.04800	0.03000
	13	2.8	1	1.5	3.1	0.25	3.0	5.3	5.6	0.00520	0.00630
SPAN 11	15	3.3	3	4.7	4.7	15.1	2.0	2	15.3	0.00468	0.00180
	18	19	1	19	20	13.9	1.0	13.5	16.8	0.01920	0.00300
	20	30	2	6	31	24	1.0	6	24	0.04800	0.01800
	22	29	2	20	29	22	1.0	11	23	0.00960	0.01680
	25	4.3	5	8.2	8.5	7.8	7.0	3.8	8.9	0.00348	0.00144
SPAN 12	27	9.6	2	5.3	9.8	6.0	5.0	4.8	6.5	0.00370	0.00200
	30	41	6	31.5	42	35.5	3.0	26	37	0.06600	0.01440
	32	41	5	17.5	42	20.5	3.0	17	31	0.02400	0.03600

As shown in Table 10 (page 51), the computed maximum out-of-plane stresses are below the 46 ksi existing condition threshold value that was established in the Part I evaluation of the superstructure. Therefore, the half-width deck replacement option can be accomplished using the removal of 300 feet segments centered at a pier without the use of any additional retrofits.

The analyses for this evaluation are provided in detail in Volume II.




S_x = Stress in x-direction i.e. along the length of the girder (Refer to Figure a)
 S_y = Stress in the y-direction i.e. perpendicular to the length of the girder (Refer to Figure b)
 S_z = Stress in the vertical direction i.e. along the depth of the girder (Refer to Figure c)
 S_1 = Maximum principal stress (Refer to Figure d)


3-D FINITE ELEMENT MODELING OF CUY-480-18.42 FOR HALF WIDTH DECK REPLACEMENT

Dead load & Live Load Deflections

Dead load and live load deflections for Girders E, F, G, & H are presented for Spans 10 & 11 when a 300 feet long half-width deck segment is removed with 150 feet removed on each side of Pier 10. The deflections of the pier and pier cap are shown in Figures (a) & (b). Deflections were calculated for the purpose of verifying that the 3-D FE model provides results that are consistent with common sense engineering expectations. As shown below, the differential deflection between adjacent girders F & G is approximately one (1) inch when the half-width deck is removed. The live load differential deflection is approximately 1 inch between girders F & G. The live load differential deflections, which may include vibrations, should be mitigated by lowering the traffic speed during deck pours and also closing the adjacent lane until sufficient concrete set has been achieved.




(a) Girder deflected shapes for spans 10, 11 & 12 including piers during half-deck removal of 300 feet centered at pier 10



(b) Pier 10 & 11 including pier cap deflections during deck

Table 11 LL Deflections at Mid Span 10

Span 10	
Girder	Live Load Deflection at Mid Span (inches)
E	1.32
F	2.5
G	3.46
H	3.98



SPAN 11 - Girder Top Flange Deflection - DL




Table 12 LL Deflections at Mid Span 11

Span 11	
Girder	Live Load Deflection at Mid Span (inches)
E	0.92
F	1.75
G	2.44
H	3.51


3-D FINITE ELEMENT MODELING OF CUY-480-18.42 FOR HALF WIDTH DECK REPLACEMENT

Discussions with Contractors

Information regarding the replacement of the decks for the CUY-480 twin structures was solicited from three contractors The Ruhlin Company, The Great Lakes Construction Company and The Kokosing Construction Company. Below is a list of generalized statements received from these contractors:

1. In order to replace the deck for one of the twin superstructures within in a 9 month construction season time frame, consensus is that at least 300 feet long deck removal segments must be permitted (see figure on this page). It is a very aggressive schedule to complete two 300 feet long removal/replacements in 8 days while working two 10 hour shifts.
2. Allowing the closure of an additional lane to place concrete at night would be very beneficial (10 hour time frame).
3. The cost of providing retrofits may offset the advantage gained with the larger 600 feet deck section removal and replacement option. It is a very aggressive schedule to complete two 300 feet long removal/replacements every 2 weeks
4. The 300 feet option seems possible but would require 2 operations, double shifts and would be expensive.
5. A large crane or cranes may be needed below to furnish rebar. Possibly in prefabbed mats.
6. Could slip forming be used for the barriers?
7. Precast barriers should be considered.
8. Note: time is needed in the schedule to construct the barrier.
9. All access efforts to the site will be a challenge.
10. Are the expansion joints being replaced? If so that will impact schedule as well.
11. Consensus was that the Contractor would platform the entire bridge for access for the steel repairs, for safety and for containment of debris removal. Since the repairs need to be completed prior to removal and replacement of the deck, it may be necessary to platform both bridges. This would be very expensive.
12. Our steel retrofit expert studied the retrofit detail provided by ELR and he estimates each retrofit detail will cost in the \$2500-\$3000 range (per each for labor and materials, included is a foreman's pickup, welder, and compressor). This cost doesn't include any major access money since we don't know exactly what the conditions would be (i.e. would we be using a snooper truck, man lift from underneath, installing a full under deck system, etc...)
13. For a retrofit detail in the negative moment region the ELR detail shows 7/8 inch welded threaded studs on the underside of the top flange. If they want them "shot" on like a shear stud that is not going to happen, as you may have the same problem we always run into on the horizontal studs, but much worse. We would have to stick weld them or use a smaller diameter threaded stud. The maximum diameter would be 5/8 inch.

Deck pours based on 300 feet long segments for Unit 1R thru 5R.



Conclusions

The objective of this study was to determine a plan that would best permit the construction of new decks for the CUY-480-1842 twin structures while avoiding undesirable out-of plane induced stresses. ODOT has placed the following desired constraints on the design and construction of the new decks:

1. Do not generate any out-of-plane stresses in the superstructure that are higher than 46 ksi, which has been established as the baseline upper stress limits value (as computed by the 3-D model).
2. Maintenance of traffic barriers should not be present during snow removal operations. Any work that disrupts the flow of traffic should be avoided during the winter months.
3. The deck for one of the twin superstructures must be removed and replaced in one construction season.
4. Attempt to avoid the use of mechanical splices when constructing the new deck.
5. Address the use of retrofit details.

After evaluating numerous deck removal alternatives, removing a 300 feet long half-width segment centered over a pier was found to be the most conservative construction procedure. By centering the 300 feet deck removal and replacement work over a pier, the out-of-plane stresses in the web were found to be at an acceptable level, therefore, retrofits are not necessary for controlling stresses caused by deck replacement work when using this design alternative. The restraint provided by the reinforced concrete deck to the top flange of the stringers is considered to be a key component of the satisfactory stress levels found to be present during the 300 feet removal alternative. For removal and replacement of one 300 feet long half-width segment, the prediction from contractors that were interviewed, is that this work can be accomplished in approximately a two week time interval. Work will begin at the center pier (Pier 8) and simultaneously progress both up-station and back-station.

If there is a desire to remove the deck in 600 feet long half-width sections, connection plate to bottom flange retrofits will be necessary. The minimum number of locations that should be retrofitted are based on stresses computed by the 3-D FE modeling and are shown on pages 56 through 60. There are 6 retrofit locations per unit in Units 1 through 4, and 5 retrofit locations in Unit 5. These retrofit locations represent the minimum locations that need to be retrofitted for removal of 600 feet segments. According to the contractors interviewed, there does not appear to be a clear indication that utilizing 600 feet removal limits will shorten the duration of time necessary to complete one of the twin superstructure decks.

In the preparation of the cost estimate, we have assumed that retrofits will be provided at an average of 3 crossframe stations per span. For each crossframe station, 6 retrofits are required (one retrofit for each exterior girder and 2 retrofits for each of the two interior girders). Therefore, the number of individual retrofits is computed as $(6 \text{ per station}) * (3 \text{ stations per span}) * (15 \text{ spans}) * (2 \text{ structures}) = 540$ total retrofits. This retrofit work is estimated to cost approximately \$3,000,000. A complete project construction cost estimate and construction schedule are provided in Appendix A.

The following items should be considered when preparing the construction contract plans for this project:

1. Perform an in-depth inspection.
2. Develop deck replacement plans based on limiting the deck removal and replacement to 300 feet segments for a half-width phase construction.
3. Replace a portion of the abutment backwalls.
4. Provide new deck joints at the abutments.
5. Rehabilitate the existing finger joints.
6. Provide details to repair structural steel and reinforced concrete components deemed necessary based on inspection. This could include partial painting, structural steel repairs, and patching and sealing of existing concrete substructures.
7. The final design for these superstructures should be load rated. The ODOT Office of Structural Engineering provided existing BARS analysis files which analyzed one interior girder and one stringer for the left and right structures. The bridges were analyzed as non-composite structures and all the loads were distributed uniformly to a girder or stringer. In the existing analysis files, the dead load consisted of a 7.5" concrete deck and a 2.75" super plasticized dense concrete wearing surface. ELR performed a rating of the superstructures with the modifications as proposed in this report. The files were modified to include a composite deck. All the loads were distributed uniformly to a girder or stringer. The dead load used consisted of an 8.5" concrete deck, 20 psf for SIP forms and 42" single slope barriers. The modified files were run using the BARS-PC Release 5.5 using the Load Factor Method. The computed rating was found to be greater than the HS20 loading at the Inventory Level.

Recommendations


The final recommendation gleaned from the information in this report is to remove 300 feet of deck in half-width segments centered over a pier, at each construction interval during the construction of the reinforced concrete deck. Our recommendation is based on a desire to limit the out-of-plane stresses at the crossframe to web connections. The procedures for performing this work are detailed within the contents of this report.

If the 300 feet half-width removal limits, which are the preferred removal limits, cannot be accomplished in one construction season, an acceptable design alternative is to remove up to 600 feet of half-width deck provided the appropriate retrofits have been installed prior to deck removal.

The fatigue life of the existing bridge has not been discussed in this study which focuses on evaluating deck replacement alternatives. Fatigue life is a concern, although predictions have not specifically been addressed within the contents of this report. We believe that it would be appropriate to recommend that consideration be given to providing the bottom flange retrofits at approximately three crossframe stations in each span. The position of the crossframes to be retrofitted should be near the center of each span in the superstructure. Engineering judgment is necessary to establish criteria for predicting the locations of where retrofits, for

fatigue life concerns, are considered to be appropriate. Professor Dennis R. Mertz, Ph.D., P.E. informed us that, “Estimating the remaining life of distortion-induced fatigue details is foolhardy at best. Even fatigue-life estimates for load-induced fatigue details can be misleading. Due to the uncertainties involved and the probabilistic nature of the fatigue limit state as defined by AASHTO, estimated fatigue lives are lower bounds. If the remaining life of bridges with lower fatigue category details is estimated, many times a negative life for successfully performing in-service bridges results. If this is the case for load-induced fatigue, the problem of accuracy only magnifies with distortion-induced fatigue. I do not recommend estimating the remaining fatigue life of distortion-induced fatigue details. The proper retrofit detail will extend the life indefinitely if the web gap is sufficiently stiffened.”

3-D FINITE ELEMENT MODELING OF CUY-480-18.42 FOR HALF WIDTH DECK REPLACEMENT



UNIT 1R

CROSS FRAMES RETROFIT LOCATIONS - UNIT 1	
UIC6	
UIC17	
UIC28	
UIC29	
UIC30	
UIC31	


 DESIGN AGENCY
ELROBINSON
 180 WATERMARK DRIVE
 SUITE 300
 COLUMBUS, OHIO 43260
 Phone: 614-885-0900

DESIGNED	FA	CHECKED
DRAWN	JEC	REVISED
REVIEWED	DFT	DATE
STRUCTURE FILE NUMBER		
1812521 & 1812548		


RETROFIT LOCATIONS FOR 600 FT POURS
 CUY-480-18.42 L&R
 I-480 OVER CUYAHOGA RIVER VALLEY

CUY-480-18.42
 PID No.

1 / 5



3-D FINITE ELEMENT MODELING OF CUY-480-18.42 FOR HALF WIDTH DECK REPLACEMENT



UNIT 2R

CROSS FRAMES RETROFIT LOCATIONS - UNIT 2	
U2C8	
U2C20	
U2C31	
U2C32	
U2C33	
U2C34	


 DESIGN AGENCY

 100 WATERMARK DRIVE
 SUITE 200
 CUYAHOGA RIVER VALLEY
 OHIO 44129-1002
 PHONE 419-984-0822

DESIGNED	FA	CHECKED

DRAWN	JEG	REVIEWED

DATE	02/20/2012


STRUCTURE FILE NUMBER
 181821 & 181248

RETROFIT LOCATIONS FOR 600 FT POURS
 CUY-480-18.42 L&R
 I-480 OVER CUYAHOGA RIVER VALLEY

CUY-480-18.42
 PID No.

2 / 5

3-D FINITE ELEMENT MODELING OF CUY-480-18.42 FOR HALF WIDTH DECK REPLACEMENT




 DESIGN AGENCY
E.L. ROBINSON
 181 WATERMARK DRIVE
 COLUMBIANA, OHIO 43085
 PHONE: 614-398-0422


DESIGNED	FA	CHECKED
DRAWN	JEG	REVISED
REVIEWED	DFT	DATE
STRUCTURE FILE NUMBER		
1812521 & 1812548		
DATE		
02/20/2012		

RETROFIT LOCATIONS FOR 600 FT POURS
 CUY-480-18.42 L&R
 I-480 OVER CUYAHOGA RIVER VALLEY


CUY-480-18.42
 PID No.

3 / 5

3-D FINITE ELEMENT MODELING OF CUY-480-18.42 FOR HALF WIDTH DECK REPLACEMENT



3-D FINITE ELEMENT MODELING OF CUY-480-18.42 FOR HALF WIDTH DECK REPLACEMENT



CROSS FRAMES RETROFIT LOCATIONS - UNIT 5	
U5C6	
U5C7	
U5C15	
U5C16	
U5C24	

References

- Fisher, John W. (1984). *Fatigue and Fracture in Steel Bridges: Case Studies*. John Wiley & Sons, New York
- Fisher, John W. and Mertz, Dennis R. (1985) *Hundreds of Bridges – Thousands of Cracks*, Civil Engineering – ASCE, Vol. 55, No. 4 pp. 64-67
- Fisher et al. (1998) – A Fatigue Primer for Structural Engineers. National Steel Bridge Alliance
- Physical Condition Report of Valley View Bridges over the Cuyahoga River (2008)
- Physical Condition Report (In-Depth Inspection) of Valley View Bridges over the Cuyahoga River (2008)
- Annual Inspection of the Valley View Bridge (2009)
- 2010 Routine Inspection Report of I-480 Valley View Bridge Over the Cuyahoga River
- LARSA 4D Version 7.05.35 LARSA, Inc. 68 S Service Road Suite 100 Melville, New York 11747
- LUSAS Version 14.7-1 LUSAS 66 High Street Kingston upon Thames Surrey United Kingdom
- “Behavior and Rehabilitation of Distortion-Induced Fatigue Cracks in Bridge Girders”, 2001, D’Andrea, M., M.Sc. Thesis, Dept. of Civil Eng., University of Alberta. Edmonton, Alberta, Canada.
- “Fatigue Prone Steel Bridge Details: Investigation and Recommended Repairs”, 2003, Zhao, Y., Ph.D Dissertation, Department of Civil, Environmental, and Architectural Engineering, University of Kansas
- AASHTO Standard Specifications for Highway Bridges, 17th Editions - 2002

APPENDIX A

Estimated Construction Cost & Schedule

3-D FINITE ELEMENT MODELING OF CUY-480-18.42 FOR HALF WIDTH DECK REPLACEMENT

E.L. Robinson Engineering of Ohio

Estimate 90591

Estimated Cost:\$60,008,910.40

Contingency: 29.60%

Estimated Total: \$77,771,547.88

CUY-480-1842L/R (I.R. 480 E.B.W.B. VALLEY VIEW BRIDGES)

Base Date: 06/21/12

Spec Year: 10

Unit System: E

Work Type: BRIDGE REHABILITATION

Highway Type:

Urban/Rural Type: URBAN CLASS

Season:

County: CUYAHOGA

Midpoint of Latitude:

Midpoint of Longitude:

District: 12

Federal/State Project Number: 90591

Prepared by E.L. Robinson

Estimate: 90591

E.L. Robinson Engineering of Ohio

Line #	Item Number	Quantity	Units	Unit Price	Extension
	<u>Description</u>				
	<u>Supplemental Description</u>				

Group 0002: Structures Over 20 Foot Span

0006	202E11305	68,017.000	SY	\$225.00000	\$15,303,825.00
	PORTIONS OF STRUCTURE REMOVED, AS PER PLAN				
0007	202E22901	578.000	SY	\$31.50000	\$18,207.00
	APPROACH SLAB REMOVED, AS PER PLAN				
0009	509E10001	5,810,100.000	LB	\$1.10000	\$6,391,110.00
	EPOXY COATED REINFORCING STEEL, AS PER PLAN				
0010	512E10101	19,753.000	SY	\$14.00000	\$276,542.00
	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE), AS PER PLAN				
0011	513E17001	325.000	FT	\$1,558.00000	\$506,350.00
	STRUCTURAL STEEL MEMBERS, MODULAR EXPANSION JOINT, LEVEL UF, AS PER PLAN				
0012	513E20001	265,600.000	EACH	\$2.30000	\$610,880.00
	WELDED STUD SHEAR CONNECTORS, AS PER PLAN				
0013	514E00051	6,625.000	SF	\$9.44043	\$62,542.85
	SURFACE PREPARATION OF EXISTING STRUCTURAL STEEL, AS PER PLAN				
0014	514E00057	6,625.000	SF	\$2.55866	\$16,951.12
	FIELD PAINTING OF EXISTING STRUCTURAL STEEL, PRIME COAT, AS PER PLAN				
0015	514E00061	6,625.000	SF	\$1.85249	\$12,272.75
	FIELD PAINTING STRUCTURAL STEEL, INTERMEDIATE COAT, AS PER PLAN				
0016	514E00067	6,625.000	SF	\$3.15475	\$20,900.22
	FIELD PAINTING STRUCTURAL STEEL, FINISH COAT, AS PER PLAN				
0017	519E11101	5,982.000	SF	\$75.00000	\$448,650.00
	PATCHING CONCRETE STRUCTURE, AS PER PLAN				
0018	530E00400	1.000	EACH	\$5,406,184.46000	\$5,406,184.46
	SPECIAL - STRUCTURE, MISC.: 10% CONTINGENCY				
0019	601E20001	477.000	SY	\$33.54423	\$16,000.60
	CRUSHED AGGREGATE SLOPE PROTECTION, AS PER PLAN				
0020	607E39901	16,620.000	FT	\$25.00000	\$415,500.00
	VANDAL PROTECTION FENCE, 6' STRAIGHT, COATED FABRIC, AS PER PLAN				
0027	898E10201	18,468.000	CY	\$950.00000	\$17,544,600.00
	QC/QA CONCRETE, CLASS QSC2, SUPERSTRUCTURE (DECK), AS PER PLAN				
0028	898E10709	1,083.000	SY	\$232.19912	\$251,471.65
	QC/QA CONCRETE, CLASS QSC2, SUPERSTRUCTURE (APPROACH SLAB), (T=17"), AS PER PLAN				
0029	898E11001	2,660.000	CY	\$599.60000	\$1,594,936.00
	QC/QA CONCRETE, CLASS QSC2, SUPERSTRUCTURE (PARAPET), AS PER PLAN				

Total for Group 0002:\$48,896,923.65

Group 0003: Roadway

0005	103E06000	1.000	LS	\$270,309.22000	\$270,309.22
	PREMIUM FOR CONTRACT PERFORMANCE BOND, PAYMENT BOND AND MAINTENANCE BOND				
0008	203E98500	1.000	LS	\$250,000.00000	\$250,000.00
	ROADWAY, MISC.: LUMP				
0021	614E18002	1.000	LS	\$5,000,000.00000	\$5,000,000.00
	MAINTAINING TRAFFIC, MISC.: MOT				
0022	619E16020	36.000	MNTH	\$1,843.56414	\$66,368.31
	FIELD OFFICE, TYPE C				
0023	623E10000	1.000	LS	\$270,309.22000	\$270,309.22
	CONSTRUCTION LAYOUT STAKES				
0024	624E10001	1.000	LS	\$5,000,000.00000	\$5,000,000.00
	MOBILIZATION, AS PER PLAN PROJECT ACCESS				
0025	832E15000	1.000	LS	\$5,000.00000	\$5,000.00
	STORM WATER POLLUTION PREVENTION PLAN				

9:51:00AM

Thursday, June 21, 2012

Page 2 of 3

3-D FINITE ELEMENT MODELING OF CUY-480-18.42 FOR HALF WIDTH DECK REPLACEMENT

Estimate: 90591

E.L. Robinson Engineering of Ohio

<u>Line #</u>	<u>Item Number</u>	<u>Quantity</u>	<u>Units</u>	<u>Unit Price</u>	<u>Extension</u>
	<u>Description</u> <u>Supplemental Description</u>				
0026	832E30000 EROSION CONTROL	1.000	EACH	\$250,000.00000	\$250,000.00
Total for Group 0003:					\$11,111,986.75

3-D FINITE ELEMENT MODELING OF CUY-480-18.42 FOR HALF WIDTH DECK REPLACEMENT

E.L. Robinson Engineering of Ohio

Estimate: 90591

E.L. Robinson Engineering of Ohio

<u>Line #</u>	<u>Item Number</u>	<u>Quantity</u>	<u>Units</u>	<u>Unit Price</u>	<u>Extension</u>
	<u>Description</u>				
	<u>Supplemental Description</u>				

Group 1503: Connection Plate Retrofits

0011	513E95020	1.000	LS	\$1,362,500.00000	\$1,362,500.00
	STRUCTURAL STEEL, MISC.: CONNECTION PLATE RETROFITS				
0012	513E95020	1.000	LS	\$1,000,000.00000	\$1,000,000.00
	STRUCTURAL STEEL, MISC.: ACCESS				

Total for Group 1503:\$2,362,500.00

Estimate 90591

Estimated Cost:\$2,362,500.00

Contingency: 29.60%

Estimated Total: \$3,061,800.00

CUY-480-1842L/R (I.R. 480 E.B.W.B. VALLEY VIEW BRIDGES - Connection Plate Retrofit)

Base Date: 06/21/12

Spec Year: 10

Unit System: E

Work Type: BRIDGE REHABILITATION

Highway Type:

Urban/Rural Type: URBAN CLASS

Season:

County: CUYAHOGA

Midpoint of Latitude:


Midpoint of Longitude:

District: 12

Federal/State Project Number: 90591

Prepared by E.L. Robinson

3-D FINITE ELEMENT MODELING OF CUY-480-18.42 FOR HALF WIDTH DECK REPLACEMENT



Project: CUY-480-18.42 Construction : Task Progress Summary External Tasks Deadline
 Date: Mon 8/6/12 Split Milestone Project Summary External Milestone



CUY-480-18.42
PID 90591



APPENDIX B

Existing Plans Including Retrofit Plans

E-N


T-18

CONVENTIONAL SIGNS

PROPERTY LINE	---	---
EXISTING RIGHT OF WAY	---	---
SUBDIVISION LINE	---	---
SUBLOT LINE OR EXISTING EASEMENT	---	---
ORIGINAL TOWNSHIP LOT LINE	Z	Z
CORPORATION LINE	.	.
LIMITED ACCESS LINE	LA	LA
LIMITED ACCESS LINE AND RIGHT OF WAY LINE	LA & RW	LA & RW
RIGHT OF WAY LINE AND HIGHWAY EASEMENT LINE	R/W	R/W
AERIAL EASEMENT LINE	AERIAL	AERIAL
TEMPORARY RIGHT OF WAY	T	T
SEWER EASEMENT LINE	S	S
SLOPE EASEMENT LINE	SL	SL
CHANNEL EASEMENT	X	X
PARTICIPATION LINE	P	P
CENTER LINE	---	---
FENCE LINE	x	x
GUARD RAIL (EXISTING)	---	---
GUARD RAIL (PROPOSED)	---	---
RAILROAD	---	---
POWER POLES	⊕	⊕
TELEPHONE POLES	⊕	⊕
POWER AND TELEPHONE POLES	⊕	⊕
LIGHT POLES	⊕	⊕
TREES (EXISTING)	⊕	⊕
ELECTRICAL TOWER	⊕	⊕
WATER LINE	/	/
GAS LINE	G	G
TELEPHONE CONDUIT	T	T
EXISTING SEWERS (R/W PLANS)	S	S
EXISTING STORM SEWER (DRAINAGE PLANS)	S	S
EXISTING SANITARY SEWER (DRAINAGE PLANS)	S	S
OIL LINE	o	o
FIRE HYDRANT (EXISTING)	⊕	⊕
FIRE HYDRANT (PROPOSED)	⊕	⊕
MANHOLE (EXISTING)	⊕	⊕
MANHOLE (PROPOSED STORM)	⊕	⊕
MANHOLE (PROPOSED SANITARY)	⊕	⊕
CATCH BASIN OR INLET (EXISTING)	⊕	⊕
CATCH BASIN OR INLET (PROPOSED)	⊕	⊕

STATE OF OHIO
 DEPARTMENT OF HIGHWAYS
CUY-480-18.43
PART 2 - SUPERSTRUCTURE

CUYAHOGA COUNTY
 CITY OF GARFIELD HEIGHTS
 CITY OF INDEPENDENCE
 VILLAGE OF VALLEY VIEW
GRADE SEPARATION WITH THE BALTIMORE & OHIO R.R.



INDEX OF SHEETS

TITLE SHEET	1
SCHEMATIC PLAN AND DESIGN DESIGNATION	2
GEOMETRICS TABLE AND SURVEY TIES	3
TYPICAL SECTIONS	4-6
GENERAL NOTES	7
COMPUTATIONS AND SUB-SUMMARIES	8-9
GENERAL SUMMARY	10
PAVEMENT PLANS	11-12
PROFILE SHEETS	13-16
GRADING AND DRAINAGE PLANS	17-21
CROSS SECTION SHEETS	22-38
TRAFFIC CONTROL PLANS	39-60
LIGHTING PLANS	61-72
STRUCTURES OVER 20' SPAN	73-100
RIGHT OF WAY PLANS	101-112

Sheet Nos. 69, 79, 81, 82, 85,
 98, & 100 REVISED 11-16-70 ERL
 Sheet Nos. 2, 10, 11, 13, 14, 23, 24, 25, 26, 27, 28,
 46, 73, 74, 75, 76, 86, 88, 89, 90, 91, 93, 94, 97, 98,
 & 99, revised; 86A & 88A added, 8-15-73. NAA

SUPPLEMENTAL SPECIFICATIONS			
NUMBER	DATE	NUMBER	DATE
801	1-1-69	1001	1-1-69
808	1-1-69	816	1-1-69
811	1-1-69		
836	6-17-69		
815	1-1-69		
938	8-2-69		

STANDARD DRAWINGS			
NUMBER	DATE	NUMBER	DATE
BP-1	6-1-65	AS-1-67	1-11-68
BP-2	12-1-68	RB-1-55	2-2-59
BP-3	12-1-68	SD-1-69	12-1-69
BP-4	12-1-68	BR-1-67	1-23-68
BP-7	1-1-66		
F-1	3-10-69		
F-2	3-10-69		
GR-2B	2-15-68		
GR-5	1-15-68		
GR-6	7-15-68		
HL-1	11-1-65		
HL-2	11-1-65		
HL-3	11-1-65		
HL-4	1-1-66		
MC-3	6-20-69		
MC-4	6-13-69		
GR-1	1-1-67		

LINE DATA

BEGIN PROJECT STA. 994 + 50 @ I-480
 END PROJECT STA. 1048 + 50 @ I-480
 ADD FOR STATION EQUATION: STA. 1040 + 50.00 BACK EQUALS
 STA. 1040 + 25.85 AHEAD = 24.15 LIN. FT.
 NET LENGTH OF PROJECT: 5424.15 LIN. FT. = 1.027 MILES
 ADD WORK STA. 992 + 48 TO STA. 994 + 50 = 202 LIN. FT.
 STA. 1048 + 50 TO STA. 1049 + 30 = 80 LIN. FT.
 NET LENGTH OF WORK: 5706.15 LIN. FT. = 1.081 MILES.

PREPARED AND RECOMMENDED BY
HOWARD NEEDLES TAMMEN & BERGENDOFF
 CONSULTING ENGINEERS
 KANSAS CITY CLEVELAND NEW YORK

H.G. SOURS
 ASSOCIATE
 COLUMBUS

Browning Crow
BROWNING CROW



FILE NO.	CUYAHOGA COUNTY	00347
	DATE OF LETTING	
	CONTRACT NO.	

LIMITED ACCESS

THIS IMPROVEMENT IS ESPECIALLY DESIGNED FOR THROUGH TRAFFIC AND HAS BEEN DECLARED A LIMITED ACCESS HIGHWAY OR FREEWAY BY ACTION OF THE DIRECTOR OF HIGHWAYS IN ACCORDANCE WITH THE PROVISIONS OF SECTION 5511.02, REVISED CODE OF OHIO.

FED. RD. DIVISION	STATE	PROJECT	
2	OHIO	I-480-4(41)172	1 112

CUYAHOGA COUNTY
 CUY-480-18.43 PART 2
 PROJECT DESIGNATION CUY-80-18.43 PART 2
 APPEARING THROUGHOUT THIS PLAN SHALL BE CONSIDERED TO READ CUY-480-18.43 PART 2.

I-480-4(41)172
1969 SPECIFICATIONS

THE STANDARD SPECIFICATIONS OF THE STATE OF OHIO, DEPARTMENT OF HIGHWAYS, INCLUDING CHANGES AND SUPPLEMENTAL SPECIFICATIONS LISTED IN THE PROPOSAL SHALL GOVERN THIS IMPROVEMENT.

THE RIGHT OF WAY FOR THIS IMPROVEMENT WILL BE PROVIDED BY THE STATE OF OHIO.

I HEREBY APPROVE THESE PLANS AND DECLARE THAT THE MAKING OF THIS IMPROVEMENT WILL NOT REQUIRE THE CLOSING OF THE HIGHWAY TO TRAFFIC AND THAT PROVISIONS FOR THE MAINTENANCE AND SAFETY OF TRAFFIC WILL BE AS SET FORTH ON THE PLANS AND ESTIMATES.

APPROVED DATE 9-1-70	<i>Charles M. Jurick</i> DIVISION DEPUTY DIRECTOR
APPROVED DATE 9-2-70	<i>C. H. Alvarado</i> ENGINEER OF BRIDGES
APPROVED DATE 9-2-70	<i>R. E. Bath</i> ENGINEER OF LOCATION AND DESIGN
APPROVED DATE 9-3-70	<i>George J. Thormann</i> DEPUTY DIRECTOR OF DESIGN AND CONSTRUCTION
APPROVED DATE	DEPUTY DIRECTOR OF RIGHT OF WAY
APPROVED DATE 9-10-70	<i>Thomas M. Major</i> DEPUTY DIRECTOR OF PLANNING AND PROGRAMMING
APPROVED DATE 9-10-70	<i>R. M. ...</i> FIRST ASSISTANT DIRECTOR
APPROVED DATE 9-10-70	<i>R. E. ...</i> DIRECTOR OF HIGHWAYS

DEPARTMENT OF TRANSPORTATION
 FEDERAL HIGHWAY ADMINISTRATION
 BUREAU OF PUBLIC ROADS
 APPROVED
 DIVISION ENGINEER DATE

MICROFILMED
DEC 10 1984

SCHEMATIC PLAN

FED. RD. DIVISION	STATE	PROJECT
2	OHIO	

2
112

CUYAHOGA COUNTY
CUY. - 80-18.43 Part 2

PROPOSED STRUCTURE

TYPE: Continuous welded steel girder with floor system and reinforced concrete deck and substructure.

SPANS: Unit 1 - 220', 300' and 275'
Units 2, 3 and 4 - 25' cantilever, 2 @ 300' and 275'
Unit 5 - 25' cantilever, 2 @ 225' and 180'

ROADWAY: Unit 1L - Varies 71'-0" to 71'-4" face to face of parapets.
Unit 1R - Varies 71'-0" to 86'-6" face to face of parapets.
Units 2, 3, 4 and 5 - 71'-0" face to face of parapets.

LOADING: HS 20-44 and Interstate Alternate Loading

SKEW: None

WEARING SURFACE: 1" Monolithic Concrete


APPROACH SLABS: AS-1-67 (25' long)

ALIGNMENT: Tangent

SUPERELEVATION: Normal Crown

URBAN RADIAL (WITHOUT LEE AND BEDFORD FREEWAYS)

DESIGN DESIGNATIONS	EAST END OF PROJECT	WEST END OF PROJECT
Current A.D.T. 1970	69,199	70,460
Design Year A.D.T. 1990	79,085	89,668
D.D.H.V.	7,567A.M. 7,096P.M.	8,313
D (Directional Distribution)	62% - 38%	62% - 38%
T (Per Cent B.C. Trucks)	3	3
V (Design Speed)	60 MPH	60 MPH



PLAN


Note: For Curve Data See Sheet No. 3
Curves are identified like this: (2)

Profile Grades have been revised to accommodate the addition of the 2" Surface Course to the Bridge.

LEGEND (Traffic Volumes)


0000 - Directional Average Daily Traffic
(000) - Directional Hourly Volumes (A.M. Peak)
00 - Directional Hourly Volumes (P.M. Peak)

Note:
Directional Design Hourly Volumes for each movement were computed at 5.7474% of the A.D.T. (or 11.4949% of the directional A.D.T.) based on a 9% peak hour factor, a 62%-38% distribution by direction and 3% trucks.



Note: The Superstructure is not part of this contract.

SCALE: 1" = 200'
HOWARD, NEEDLES, TAMMEN & BERGENDOFF
MADE I.M. DATE 7-15-69 CONSULTING ENGINEERS
TRCD. I.N. DATE 10-16-69
KANSAS CITY CLEVELAND NEW YORK



STA. 1040+50.00 BACK = AHEAD STA. 1040+25.85
STA. EQUATION

3-7


MICROFILMED
DEC 18 1964

FED. RD. DIVISION	STATE	PROJECT	73 112
2	OHIO		


CUYAHOGA COUNTY
CUY -80-1843 Part 2

CURVE DATA - @ LANE E-S

P.I. Sta. +93+07.64
Δ = 5°14'06"
D = 0°40'00" Left
R = 8594.37'
T = 392.91'
L = 785.27'
E = 8.98'



PLAN
Scale: 1" = 200'
+2.62%



ELEVATION

FOUNDATION DATA

All piles are 12 BP 53 or 14" C.I.P. concrete with an allowable design load of 65 tons per pile at the piers and 40 tons at the abutments. The tabulation to the right gives the pile type, and estimated average pay length.

Substructure Unit	Pile Type	Estimated Pile Length
West Abutment	14" C.I.P.	64'
Pier 1L	14" C.I.P.	75'
Pier 1R	14" C.I.P.	75'
Pier 2L	14" C.I.P.	105'
Pier 2R	14" C.I.P.	110'
Pier 3	14" C.I.P.	103'
Pier 4	14" C.I.P.	92'
Pier 5	14" C.I.P.	98'
Pier 6	14" C.I.P.	99'
Pier 7	14" C.I.P.	104'
Pier 8	14" C.I.P.	94'
Pier 9	14" C.I.P.	99'
Pier 10	14" C.I.P.	97'
Pier 11	14" C.I.P.	86'
Pier 12	14" C.I.P.	54'
Pier 13L	Spread Footing Allowable Bearing Capacity - 6 Tons per sq. ft.	
Pier 13R		
Pier 14L		
Pier 14R		
East Abutment	12 BP 53	38'

PROPOSED STRUCTURE

TYPE: Continuous welded steel girder with floor system and reinforced concrete deck and substructure.

SPANS: Unit 1 - 220', 300' and 275'
Units 2, 3 and 4 - 25' cantilever, 2 @ 300' and 275'
Unit 5 - 25' cantilever, 2 @ 225' and 180'

ROADWAY: Unit 1L - Varies 71'-0" to 71'-4" face to face of parapets.
Unit 1R - Varies 71'-0" to 86'-6" face to face of parapets.
Units 2, 3, 4 and 5 - 71'-0" face to face of parapets.

LOADING: HS 20-44 and Interstate Alternate Loading

SKEW: None 2" Asphalt Concrete

WEARING SURFACE: 1" Monolithic Concrete

APPROACH SLABS: AS-1-67 (25' long)

ALIGNMENT: Tangent

SUPERELEVATION: Normal Crown

TRAFFIC DATA: (1990)
I-80 - 44,834 A.D.T. (Each Way)
5,154 D.D.H.V.

PROPOSED
132 KV TRANSMISSION LINE DATA

	Minimum Clear	
	Vertical	Lateral
Left Bridge	45' ±	20' ±
Right Bridge	44' ±	20' ±
Future Bridge	44' ±	20' ±

All clearances are measured at 60° F. Lateral clearances are measured from power line with 45° sideswing to the nearest light pole.

Note:
For light pole locations see Lighting Plans.

PROPOSED
345 KV TRANSMISSION LINE DATA

	Minimum Clear	
	Vertical	Lateral
Left Bridge	41' ±	47' ±
Right Bridge	42' ±	45' ±
Future Bridge	41' ±	37' ±

All clearances are measured at 60° F. Lateral clearances are measured from power line with 45° sideswing to the nearest light pole.

EXISTING
132 KV TRANSMISSION LINE DATA

	Elevation	
	Ground	Power Line
Tower No. 2533	709.5	672.0
Tower No. 2534	694.5	657.0
Low Pt. at 60° F (350'± South of Tower No. 2534)	671.0	632.0

To be replaced by the proposed 345 KV transmission line prior to start of bridge construction.

H.N.T.B. BR. NO. 38L AND 38R

HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK

GENERAL PLAN AND ELEVATION

I-80 OVER CUYAHOGA RIVER VALLEY
BR. NO. CUY-80-1843 L & R STA. 996+22.25 TO STA. 1037+77.75

DATE: 8-22-64	DATE: 8-22-64	DATE: 8-22-64	DATE: 8-22-64
DRWN: HNTB	TRACED	CHECKED: JWP	REVIEWED: WJ
			REVISED

1. DESIGN SPECIFICATION

This structure conforms to Standard Specifications for Highway Bridges adopted by the American Association of State Highway Officials, 1965, including the 1966 - 1967 Interim Specifications and the Ohio "Supplement" to these specifications.

2. DESIGN DATA

Design Loading - HS-20-44 and the Interstate Alternate Loading.
Concrete Class C - unit stress 1,200 p.s.f. for superstructure. unit stress 1,333 p.s.f. for abutments.
Structural Steel - ASTM A588 - unit stress 27,000 p.s.f.
ASTM A36 - unit stress 20,000 p.s.f.
ASTM A237, Class B - Minimum Yield Point 55,000 p.s.f.
ASTM A486, Class 90 - Minimum Yield Point 60,000 p.s.f.
ASTM A193, Grade B7 - Minimum Yield Point 105,000 p.s.f.
Reinforcing Steel - ASTM A615, A616, A617 - unit stress 20,000 p.s.f.

3. SUPPLEMENTAL SPECIFICATIONS

Reference shall be made to Supplemental Specifications No. 808, Chemical Admixtures for Concrete, dated 11-14-69, No. 811, Examination of Welds, dated 1-1-69, and No. 836, Concrete Curing and Protective Membrane, dated 6-17-69.

4. REFERENCE DRAWINGS

Reference shall be made to Standard Bridge Drawings RB-1-55, revised 2-2-59, SD-1-69, dated 6-12-69 (Sheets 1, 2 and 3 of 4) and to AS-1-67, revised 6-12-69.

5. DIMENSIONS

Dimensions given are measured horizontally and at 60° F. unless otherwise noted.

6. CONCRETE DECK

- (a) The steel girders shall be fabricated with camber, as specified on the plans, to compensate for the deflections due to the weight of concrete and steel. The theoretical deflections are tabulated on the plans.
- (b) The final surface of the roadway shall conform to the elevations shown on the plans. To compensate for deflections due to dead load of the concrete, the screeds used to strike off the surface of the concrete to the final desired grade line shall be adjusted by amounts equal to deflections shown for this dead load. The theoretical elevations required at the curbs before concrete is placed are tabulated on Sheet 27/28. Screeds may require further adjustments due to irregularities in the fabricated steel.
- (c) The depth of concrete over each stringer or girder (top of concrete to top of flange or top of web) at the supports is given on the plans. The concrete slab shall be of uniform thickness between stringers and girders with adjustments obtained by varying the thickness of the haunches over the stringers or girders.
- (d) The aforementioned depth of concrete over each stringer or girder is the nominal dimension. The quantity of deck concrete to be paid for shall be based on this dimension even though deviation from it may be necessary because the top flanges may not have the exact camber or conformation required to place it parallel to the finished grade. Deduction shall be made for the volume of encased steel plates in accordance with Section 511.19 of the Construction and Material Specifications.

7. REINFORCING STEEL

- (a) All bars are designated in the plans by bar numbers. The bar size is indicated by the first digit of three-digit numbers and by the first two digits of four-digit numbers. All bar dimensions are given out to out. All bars of a series shall vary in length by a constant increment.
- (b) The clear distance between reinforcing steel and face of concrete shall be 2" unless otherwise shown on the plans.

8. STRUCTURAL STEEL

All girder webs, flanges, splice plates, web stiffeners and sign support parts on the exterior face of exterior girders, and certain parts of the expansion joints identified in the plans shall be ASTM A588 Structural Steel. The ASTM A588 structural steel shall meet Supplementary Requirement S1 of AASHTO M222. All bolted connections of ASTM A588 Structural Steel shall be made with High Strength Steel Bolts having the corrosion characteristics of ASTM A588 steel and having all the mechanical properties of ASTM A325 High Strength Steel Bolts.

All other structural steel parts, except as noted in the plans, shall be ASTM A36 Structural Steel. All bolted connections of ASTM A36 Structural Steel shall be made with ASTM A325, 1" Ø High Strength Steel Bolts, except as noted in the plans.

All bolting shall be in accordance with Item 513.10.

9. WELDING

- (a) Electrodes and flux-electrode combinations for welding A588 steel shall be as listed in the following table:

Base Metal	Shielded Metal-Arc	Submerged Arc	Gas Metal-Arc	Flux Cored Arc
A588 used in a painted application	AWS A5.1 E7015, 16, 18 or 28	AWS A5.17 F71, F72, F73 or F74-Exxxx	AWS A5.18 E70S-1B, 2, 3, 6 or E70U-1	AWS A5.20 E70T-1, 5 or 6

- (b) Welds on non-stress carrying members are shown thus:



10. COORDINATION OF WORK

- (a) The work under this Contract shall be coordinated with the work of the Contractor for Part 1 - Substructure.
- (b) All anchor bolts will be installed by the Contractor for Part 1 - Substructure, but the locations shall be checked by survey as a part of this Contract. The Contractor shall submit an as built anchor bolt layout plan to the Director in triplicate for approval prior to start of steel erection.
- (c) Top of masonry elevations shall be checked as a part of this Contract. Variations from plan elevation will be corrected by the Contractor for Part 1 - Substructure in accordance with Section 513.24.
- (d) The surveys of anchor bolt locations and top of masonry elevations shall be included for payment in the unit prices bid for other items of work in this Contract.

11. ITEMS NOT INCLUDED IN BRIDGE PLANS

The following items are not included in the bridge plans. See Roadway Plans for details.

- (1) Approach roadway
- (2) Approach slabs
- (3) Lighting
- (4) Signing
- (5) Guard Rail

12. DECK POURING SEQUENCE AND METHOD:

See notes on sheet 25/28.

ESTIMATED QUANTITIES						
ITEM	TOTAL	UNIT	DESCRIPTION	ABUT-MENTS	SUPER-STRUCTURE	
					GENERAL	
509	5,029,864	Lbs.	Reinforcing Steel	1223		5,028,641
511	35,34	Cu.Yd.	Class C Concrete, Abutments	35(34)		5,030,279
511	(17,795)	Cu.Yd.	Class C Concrete, Superstructure		18064	(17,795)
513	27,669,500	Lb.	Structural Steel (ASTM A588)			27,669,500
513	11,263,400	Lb.	*Structural Steel (ASTM A36)			11,263,400
514	38,932,900	Lb.	Field Painting of Structural Steel			38,932,900
518	972	Lin.Ft.	8" Ø Standard Pipe Collector System Including Specials and Accessories			972
518	112	Each	Scuppers Including Supports			112
518	224	Cu.Yd.	Porous Backfill	224		
625			See Sheet 62 for Lighting Summary			
808	(17,795)	Units	Chemical Admixture for Concrete Type A, B or D		18064	(17,795)

For additional Bridge Quantities refer to Sheet 56/112

* Item 513, Structural Steel (ASTM A36), includes 606,800 pounds of ASTM A237 - Class B, Steel Forgings; 575,800 pounds of ASTM A486 - Class 90, Steel Castings and all other miscellaneous metals except ASTM A588.

JACKING HOLES, as specified on Standard Drawing AS-1-67 shall not be provided.

H.N.T.B. BR. NO. 38L AND 38R



HOWARD, NEEDLES, TAMMEN, & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK

GENERAL NOTES AND ESTIMATED QUANTITIES




I-80 OVER CUYAHOGA RIVER VALLEY
BR. NO. CUY-80-1843 L&R STA. 996+22.25 TO STA. 1037+77.75

CUYAHOGA COUNTY OHIO
DRAWN CHB TRACED SEM CHECKED WJA REVIEWED WJA REVISION 11-16-70
DATE 2-19-69 DATE 2-26-69 DATE 3-22-69 DATE 5-22-70 SHEET 2/28

SEE MODIFICATION OF END DAMS AT REAR ABUTMENT SH. NO. 8-A 112



Note:
All reinforcing bar marks shall be prefixed:
AA for Left Bridge, West Abutment
AC for Right Bridge, West Abutment



- SEQUENCE OF CONSTRUCTION**
1. Erect Superstructure steelwork.
 2. Place Superstructure concrete.
 3. Place embankment and/or backfill.
 4. Place remaining abutment concrete.

Notes:
For Curb and Parapet Details see Sheet 4/28.
Portions of abutments shown in phantom will be constructed with Part 1 - Substructure.
For end dam and curb plate details see Sheet 14/28.
The following abbreviation is used:
ff = far face

H.N.T.B. BR. NO. 381 AND 38R

HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK

WEST ABUTMENTS

I-80 OVER CUYAHOGA RIVER VALLEY
BR. NO. CUY-80-1843 L & R STA. 996+22.25 TO STA. 1037+77.75

CUYAHOGA COUNTY OHIO








DRAWN	TRACED	CHECKED	REVIEWED	REVISED
DATE 1-14-69	DATE 2-13-69	DATE 3-10-69	DATE 8-21-70	

SHEET 3 / 28

REV. 3-15-73

FED. RD. DIVISION	STATE	PROJECT	76 112
2	OHIO		

CUYAHOGA COUNTY
CUY-80-18.43 Part 2




Notes:
For Sequence of Construction and additional notes see Sheet 3/28.
The following abbreviations are used:
RN = Right Bridge, North Wingwall
LS = Left Bridge, South Wingwall
RS = Right Bridge, South Wingwall
LN = Left Bridge, North Wingwall
L = Left Bridge
R = Right Bridge
ff = far face
ef = each face

All reinforcing bar marks shall be prefixed as follows:
AA-West Abutment, Left Bridge
AB-East Abutment, Right Bridge
AC-West Abutment, Right Bridge
AD-East Abutment, Left Bridge

Note:
Tar paper to be included with "Item 511" for payment.

H.N.T.B. BR. NO. 38L AND 38R	
HOWARD, NEEDLES, TAMMEN & BERGENDOFF CONSULTING ENGINEERS KANSAS CITY CLEVELAND NEW YORK	
EAST ABUTMENT AND CURB AND PARAPET DETAILS	
I-80 OVER CUYAHOGA RIVER VALLEY	
BR. NO. CUY-80-1843 L & R	STA. 996+22.25 TO STA. 1037+77.75
CUYAHOGA COUNTY	OHIO
DRAWN: MCB	TRACED: GEM
DATE: 7-14-69	DATE: 7-17-69
CHECKED: CHD	REVIEWED: WJ
DATE: 3-10-69	DATE: 8-21-70
SHEET 4/28	


CUYAHOGA COUNTY
 CUY-80-1843 Part 2



FRAMING PLAN-UNIT IR

Note:
 All Crossframes are set perpendicular to Girder E.

Notes:
 The Contractor shall submit to the Director for approval three prints showing his proposed erection procedure.
 All stringers are 24 WF 68.
 For stringer field splice details see Ohio Standard Drawing SD-1-69.
 Crossframe types are designated with the prefix CF.
 The bearings under the flared Girders E, F and G shall be set parallel with the bearings of the West Abutment and Piers 1 and 2.



SCHEMATIC FRAMING PLAN

Girder Notes:

The girders shall be fabricated to compensate for the effects of dead load deflections and under full dead load shall parallel the profiles formed by the top of pavement elevations directly over the center line of the girders.
 Top and bottom flange plates are to be the same.
 Additional shop splices in the webs and flanges, as required by available plate lengths, will be permitted. The locations and details of all additional splices shall be submitted to the Director for approval prior to ordering of materials.
 Intermediate stiffeners shall be placed as shown on the framing plan equally spaced between crossframes or between crossframes and girder field splices except the first two stiffener spaces from the abutments shall be one-half of this spacing. Additional intermediate stiffeners shall be placed in pairs at crossframes and 1'-2" from bearing stiffeners at piers.
 Intermediate stiffeners, which are not placed in pairs, shall be welded to the bottom flange between the center of pier and a point midway between the top and bottom longitudinal stiffener overlap, or between the center of pier and an intermediate expansion joint, whichever comes first. All other intermediate stiffeners which are not placed

in pairs shall be welded to the top flange. These stiffeners shall be welded to the flange on both sides of the stiffener with fillet welds of the same size as the web to flange weld at the same location. The end of the stiffener which is not welded to the flange shall have a clearance of 1/4" from the flange.
 Intermediate stiffeners which are placed in pairs shall not be welded to a flange but shall have contact bearing with the flange to which adjacent stiffeners are welded. The end of the stiffener which is not in contact with the flange shall have a clearance of 1/4" from the flange.
 Bearing stiffeners at piers and abutments shall be placed in pairs on all girders.
 Bearing stiffeners at abutments shall be vertical but all other transverse stiffeners shall be perpendicular to the top flange.
 Longitudinal stiffener plates shall be placed only on the interior side of the webs. They shall be placed in segments between transverse stiffeners and web splice plates.
 All girder field splices shall be made with 1" diameter high strength steel bolts. The bolts shall be placed with their heads on the outside face of exterior girders and on the bottom of all flange plates.





H.N.T.B. BR. NO. 38L AND 38R

HOWARD, NEEDLES, TAMMEN & BERGENDOFF
 CONSULTING ENGINEERS
 KANSAS CITY CLEVELAND NEW YORK

FRAMING PLAN UNIT I

I-80 OVER CUYAHOGA RIVER VALLEY
 BR. NO. CUY-80-1843 STA. 996+22.25 TO STA. 1037+77.75

CUYAHOGA COUNTY OHIO
 DRAWN/EN TRACED/LL CHECKED/JS REVIEWED/WF REVISION
 DATE/6/10/68 DATE/2/22/69 DATE/1/2/68 DATE/8-22-70 SHEET 5/28



WELD SIZE WEB TO FLANGE	
Flange Plate Thickness	Fillet Weld Size
1 1/2"	3/8"
1 3/8" thru 2 1/4"	3/8"
2 1/2" thru 4"	1/2"

Notes:
For girder notes see Sheet 5/28
For locations of intermediate stiffeners between crossframes see Sheet 5/28
For girder web and flange plate transitions see Sheet 13/28
For girder shop weld details see Sheet 10/28

DIMENSIONS						
	M	N	P	R	S	T
GIRDER E	70'-0"	45'-0"	24'-0"	30'-0"	35'-0"	40'-0"
GIRDER F	70'-0"	45'-0"	24'-0"	30'-0"	35'-0"	40'-0"
GIRDER G	70'-0 1/2"	45'-0"	24'-0 1/2"	30'-0 1/2"	35'-0 1/2"	40'-0 1/2"
GIRDER H	70'-0 3/8"	45'-0 1/8"	24'-0 3/8"	30'-0 3/8"	35'-0 3/8"	40'-0 3/8"

DIMENSION	WEB PLATES					FLANGE PLATES									
	A	B	C	E	F	G	H	J	K	L					
SIZE	120x 1/2"	1/2"	120x 1/2"	40x2	34x2 1/2	40x3	24x1 1/2	30x2 1/2	34x3 1/2	40x4	34x2 1/2	40x3	34x1 1/2	40x2	24x2 1/2
GIRDER E	150'-0"	48'-0"	160'-0"	—	65'-0"	—	160'-0"	—	75'-0"	—	140'-0"	—	30'-0"	—	75'-0"
GIRDER F	150'-0 1/2"	48'-0"	160'-0 1/2"	110'-0 1/2"	—	65'-0"	—	160'-0 1/2"	—	75'-0"	—	140'-0 1/2"	—	30'-0"	—
GIRDER G	150'-0 1/4"	48'-0 1/4"	160'-0 1/4"	110'-0 1/4"	—	65'-0 1/4"	—	160'-0 1/4"	—	75'-0 1/4"	—	140'-0 1/4"	—	30'-0"	—
GIRDER H	150'-0 3/8"	48'-0 3/8"	160'-0 3/8"	—	65'-0 3/8"	—	160'-0 3/8"	—	75'-0 3/8"	—	140'-0 3/8"	—	30'-0 1/8"	—	75'-0 3/8"

H.N.T.B. BR. NO. 381 AND 38R




HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK

GIRDER DETAILS-UNIT I

I-80 OVER CUYAHOGA RIVER VALLEY
BR. NO. CUY-80-1843 STA. 996+22.25 TO STA. 1037+77.75

CUYAHOGA COUNTY OHIO

DATE 6/1/68 TRACED MS CHECKED T/S REVIEWED W/ REVISION
DATE 6/20/68 DATE 11/21/68 DATE 2-21-70 SHEET 6/28



WELD SIZE	
WEB TO FLANGE	
Flange Plate Thickness	Fillet Weld Size
1 1/2"	5/16"
1 3/4" and 2"	3/8"
2 1/2" thru 3 1/2"	1/2"

Notes:
 For girder notes see Sheet 5/28.
 For girder web and flange plate transitions see Sheet 13/28.
 For girder shop weld details see Sheet 10/28.
 For details of flange width taper at Expansion Joint 4, see View K-K Sheet 17/28.
 For girder and stringer designation for the right bridge see sheet 5/28.

H.N.T.B. BR NO. 381 AND 38R

HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK




FRAMING PLAN AND GIRDER DETAILS UNITS 2, 3 & 4

I-80 OVER CUYAHOGA RIVER VALLEY
BR. NO. CUY-80-1843 STA. 996+22.25 TO STA. 1037+77.75

CUYAHOGA COUNTY OHIO

DRAWN/JEH	TRACED/JW	CHECKED/JS	REVIEWED/WJ	REVISED
DATE 6-12-68	DATE 6-20-68	DATE 11-21-68	DATE 8-21-70	

SHEET 7/28



WELD SIZE	
WEB TO FLANGE	
Flange Plate Thickness	Fillet Weld Size
1 1/4" and 1 1/2"	5/16"
1 3/4" thru 2 1/4"	3/8"
2 1/2" thru 3 1/2"	1/2"

Notes:
 For girder notes see Sheet 5/28
 For girder web and flange plate transitions see Sheet 13/28
 For girder shop weld details see Sheet 10/28
 For girder and stringer designation for the right bridge see sheet 5/28

H.N.T.B. BR. NO. 38L AND 38R


HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK

FRAMING PLAN AND GIRDER DETAILS
UNIT 5


I-80 OVER CUYAHOGA RIVER VALLEY
BR. NO. CUY-80-1843 STA. 996+22.25 TO STA. 1037+77.75

CUYAHOGA COUNTY OHIO


DRAWN/LEH	TRACED/PL	CHECKED/TJS	REVIEWED/WF	REVISED
DATE: 6/13/68	DATE: 6/21/68	DATE: 11/20/68	DATE: 8-21-70	SHEET 8/28




TYPICAL FIELD WEB SPLICE




SECTION A-A
Shown for Splices
1R
4L and R
10L and R
16L and R
22L and R.




SECTION A-A
Shown for Splices
1L
2L
3L
24L and R
25L and R.



SECTION A-A
Shown for Splices 2R and 3R.
Not shown but similar, except as noted for Splices
26L and R
27L and R
28L and R.



SECTION A-A
Shown for Splices
5L and R 17L and R
6L and R 18L and R
11L and R 23L and R
12L and R.
Not shown but similar, except as noted for Splices
7L and R 19L and R
13L and R.



SECTION A-A
Shown for Splices
8L and R
9L and R
14L and R
15L and R
20L and R
21L and R.

The following abbreviations are used:
L = Left Bridge
R = Right Bridge
For Flange Transition Detail see sheet 13/28


H.N.T.B. BR. NO. 38L AND 38R

HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK


FIELD SPLICE DETAILS
INTERIOR GIRDERS
I-80 OVER CUYAHOGA RIVER VALLEY
BR. NO. CUY-80-1843 STA. 996+22.25 TO STA. 1037+77.75
CUYAHOGA COUNTY OHIO

DATE 9-19-68 TRACED C.P. CHECKED 7/5 REVIEWED W/ REVISION 11-16-78
DATE 9-20-68 DATE 11-14-68 DATE 2-21-70 SHEET 9/28


CUYAHOGA COUNTY
CUY-80-1843 Part 2






SECTION A-A
Shown for Splices
1L
2R
3R.



SECTION A-A
Shown for Splice 1R.




SECTION A-A
Shown for Splices
2L 15L and R
3L 20L and R
8L and R 21L and R
9L and R 24L and R
14L and R 25L and R.
Not shown but similar, except as noted for Splices
26L and R
27L and R
28L and R.




Note:
All of the above full penetration welds shall be back-gouged and welded after welding for side.
Butt welds on girder flange plates shall be ground flush, the finish grinding being parallel to the direction of stress.
*For plate thickness over 1 1/2", use joint preparation conforming to B-U3a-S or B-U7-S, Figure 216, A.W.S. Specifications.


GIRDER SHOP WELDING DETAILS



SECTION A-A
Shown for Splices 5L and R.



SECTION A-A
Shown for Splices
6L and R 17L and R
11L and R 18L and R
12L and R 23L and R.



SECTION A-A
Shown for Splices 7L and R
10L and R
13L and R
16L and R
19L and R
22L and R.
Not shown but similar, except as noted for Splices 4L and R.

Notes:
For flange shop weld at Pier, see Sheet 13/28.
For typical field web splice and additional note see Sheet 9/28.
For Flange Transition Detail see sheet 13/28

FIELD SPLICE DETAILS - EXTERIOR GIRDERS

H.N.T.B. BR. NO. 38L AND 38R

HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK


GIRDER SPLICE DETAILS

I-80 OVER CUYAHOGA RIVER VALLEY
BR. NO. CUY-80-1843 STA. 996+22.25 TO STA. 1037+77.75


CUYAHOGA COUNTY OHIO

DRAWN M.C.B. TRACED C.P. CHECKED T.S. REVIEWED W.F. REVISION 11-16-70
DATE 9-24-68 DATE 9-25-68 DATE 11-14-68 DATE 8-21-70 SHEET 10/28


*Note: See Framing Plan - Unit 1R Sheet 5128 for Stringer Spacing




CF-1, CF-3, CF-4



CF-7 THRU CF-35




DETAIL D
(Typical except where lateral plate is required)




CF-2, CF-5, CF-6


Note: For location of crossframes see Framing Plans.




DETAIL A



DETAIL B




DETAIL C




SECTION A-A

Note: Lateral plates are required in the interior bays at Piers 1, 4, 5, 7, 8, 10, 11, and 14 and at the first crossframe on both sides of these piers for connecting lateral bracing.




FLANGE TRANSITION DETAIL


Note: All bolts are 1" High Strength.



GIRDER WEB TRANSITION DETAIL
Note: Dimensions are measured parallel or perpendicular to grade.



DETAIL E



FLANGE SHOP WELD AT PIER

Note: The above full penetration weld shall be back gouged and welded after welding for side.

H.N.T.B. BR NO. 38L AND 38R

HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK

INTERMEDIATE CROSSFRAME AND GIRDER DETAILS

I-80 OVER CUYAHOGA RIVER VALLEY
BR. NO. CUY-80-1843 STA. 996+22.25 TO STA. 1037+77.75


CUYAHOGA COUNTY OHIO

DRAWN 7/5	TRACED CFM	CHECKED JH	REVIEWED WJ	REVISED 11-16-70
DATE 11-15-68	DATE 1-21-69	DATE 2-19-68	DATE 8-21-70	SHEET 13/28

FED. RD. DIVISION	STATE	PROJECT
2	OHIO	


86
112

CUYAHOGA COUNTY
CUY-80-1843 Part 2




PART PLAN - WEST ABUTMENT UNIT IR
Details at all other abutments shall be similar


Note: Anchor bars and anchor plates not shown (See Section B-B).




DETAIL A




SECTION E-E



SECTION A-A



ELEVATION




SECTION F-F


CURB PLATE DETAILS

Notes:
For additional notes concerning joint lubrication, 3/8 inch diameter bolts, anchor bars, anchor plates, painting and joints in end dam components see Ohio Standard Drawing SD-1-69, Sheet 1 of 3.
Portions of end dams which will be in contact with steel or with concrete shall not be painted. All other portions shall be cleaned and painted in accordance with Item 514.
All parts of the end dam and end crossframe, including the bearing stiffeners and lateral plates shall be ASTM A588 steel.


FOR END DAM MODIFICATIONS SEE SHEET 86A/112



SECTION B-B




SECTION C-C




SECTION D-D AT CROWN

Welded Butt Joint in Superstructure End Dam. The End Dam on the Abutment shall be butted but not welded.




SECTION G-G


H.N.T.B. BR. NO. 38L AND 38R	
HOWARD, NEEDLES, TAMMEN & BERGENDOFF CONSULTING ENGINEERS KANSAS CITY CLEVELAND NEW YORK	
END CROSSFRAME DETAILS	
I-80 OVER CUYAHOGA RIVER VALLEY	
BR. NO. CUY-80-1843	STA. 996+22.25 TO STA. 1037+77.75
CUYAHOGA COUNTY	OHIO
DRAWN BY	TRACED BY
DATE 8-1-68	DATE 9-17-68
CHECKED BY	REVIEWED BY
DATE 2-18-69	DATE 8-22-70
SHEET 14/28	




SECTION A-A




DETAIL A



REVISED PART DECK SECTION
(See original plans for parapet dimensions not shown)




SECTION B-B




SECTION THRU ROADWAY END DAM

SECTION THRU ROADWAY END DAM & 24 WF 160 END BEAM

END DAM MODIFICATION AT FORWARD ABUTMENTS



SECTION C-C



ELEVATION OF CURB PLATES
(Asphalt concr., etc., & retainer bars not shown)

TYPE 3 SCUPPER MODIFICATION

92 SCUPPERS AT PIERS 3, 6, 9 & 12
Raise scuppers 2 1/4" providing longer support bolts if necessary. Weld galv. 6" std. pipe to the bottom of each scupper pipe outlet as reqd. to project into the horizontal conductor assembly. (2 1/4" max.) The 6" pipe downspouts (8 ea.) from the transverse trough to the hor. collector system shall be lengthened as described above and included with Type 3 Scupper Modification for payment.

TYPE 2 SCUPPER MODIFICATION

10 SCUPPERS AT THE REAR ABUTMENT END OF THE RIGHT BRIDGE

Raise scuppers 2 1/4" providing longer support bolts if necessary. Weld a 10" length of 6" standard pipe (galvanized) to the bottom of each scupper pipe outlet. (This ends the pipe approx. 8" below the girder bottom flange). Touch up areas damaged by welding with zinc-rich paint.

MODIFICATION OF END DAMS & CURB PLATES AT REAR ABUTMENTS

Note 1: New curb plates may be provided in lieu of welding extensions on the original plates.

TYPE 1 SCUPPER MODIFICATION


10 SCUPPERS AT THE REAR ABUTMENT END OF THE LEFT BRIDGE

Remove enough concrete in shaded areas to permit welding. Patch with mortar include with scupper modification for payment. PLAN


Scupper addition shall be A36 steel, galvanized in accordance with T11 after shop welding is completed. Touch up areas damaged by field welding with zinc-rich paint.

STATE OF OHIO DEPARTMENT OF HIGHWAYS DIVISION OF DESIGN AND CONSTRUCTION BUREAU OF BRIDGES					
MODIFICATION OF END DAMS AND SCUPPERS, PARAPET REVISION					
I-480 OVER CUYAHOGA RIVER VALLEY CUYAHOGA COUNTY					
DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE
NAA	NAA		CPD	WJJ	8-15-73


CUYAHOGA COUNTY
CUY-80-1843 Part 2




AT PIERS UNIT 1R




AT CROSSFRAMES CF-7 THROUGH CF-35
(UNIT 1R)




AT ABUTMENT END CROSSFRAME




AT CROSSFRAMES WITH
LATERAL BRACING EXTENDING IN
ONE DIRECTION ONLY
(UNIT 1R)




AT PIERS (EXCEPT UNIT 1R)



AT INTERMEDIATE CROSSFRAME
(EXCEPT UNIT 1R)



AT CROSSFRAMES WITH LATERAL
BRACING EXTENDING IN ONE
DIRECTION ONLY
(EXCEPT UNIT 1R)



LATERAL BRACING CONNECTION
AT MID-PANEL

Note:
Lateral Bracing Connections in interior bays to be the same as for exterior bay lateral connections.

TYPICAL CONNECTIONS

H.N.T.B. BR. NO. 38L AND 38R

HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK

LATERAL BRACING DETAILS

I-80 OVER CUYAHOGA RIVER VALLEY
BR. NO. CUY-80-1843 L&R STA. 996+22.25 TO STA. 1037+77.75


CUYAHOGA COUNTY OHIO

DRAWN	TRACED	CHECKED	REVIEWED	REVISED
JEH	GEM	CHB	W	
DATE 1-27-69	DATE 1-30-69	DATE 2-6-69	DATE 2-21-70	


SHEET 15/28

CUYAHOGA COUNTY
CUY-80-1843 Part 2


Butt Joint in Expansion Pl.,
 24"x 3/4" Support Pl. and 5"x 3/4"
 Hold-down Pl.



Note "A": A325 bolts shall be provided at 8" centers between alternating rib plates. Respace bolts as required for edge distance or clearance with 12" maximum and 4" minimum spacing to provide required number of bolts.




SECTION B-B
 FOR REVISED SECTION B-B SEE SHEET 93/112




PART SECTION C-C

Butt joint in 24"x 3/4" Support Plate
 Butt joint in Expansion Plate and 5"x 3/4" Hold-down Plate.




SECTION J-J

1" High Strength Bolts @ 8" Ctrs. (Typical, except as noted)
 1/2" Min. Clear




PART SECTION G-G

Note:
 For Section H-H see Sheet 17/28



SECTION A-A



SECTION D-D

1 1/2" x 3/8" x 8" Bar Anchor @ 12" Centers (May be 3/4" x 6" end-welded Stud) (Typ.)


H.N.T.B. BR NO. 38L AND 38R

HOWARD, NEEDLES, TAMMEN & BERGENDOFF
 CONSULTING ENGINEERS
 KANSAS CITY CLEVELAND NEW YORK


**INTERMEDIATE EXPANSION
 JOINT DETAILS**

I-80 OVER CUYAHOGA RIVER VALLEY
 BR. NO. CUY-80-1843 STA. 996+22.25 TO STA. 1037+77.75

CUYAHOGA COUNTY OHIO
 DRAWN CHD TRACED CP CHECKED JH REVIEWED WJ REVISIONS
 DATE 11-5-69 DATE 2-14-69 DATE 2-17-69 DATE 8-22-70 SHEET 16/28




EXPANSION PLATE DETAIL




EXPANSION PLATE TIP DETAIL


FOR REVISED SECT. E-E SEE SHEET 93/112



SECTION E-E




SECTION F-F



REVISED SECTION B-B, SH. 88/112

Note A:
Bolts provided for supporting expan. pl. from channel can be used from stringer or girder flange. Provide new longer bolts for support from channel as needed.




REVISED SECTION E-E, SH. 88/112


SECTION D-D, SH. 88/112

Field weld a 1/4 inch filler bar to the bottom of the 3/8 inch end plates at the joint ends of the parapet. (A-36). See OPTION.

OPTION: At the option of the Contractor the 1/4 inch filler bars may be omitted and a smooth transition in the parapet provided.



REVISED PART OF SECTION H-H, SH. 89/112



SUBDRAINAGE & SURFACE COURSE DETAILS

The PVC drain pipes shall be spaced at approx. 6' intervals with a pipe placed as near as practicable to the downhill end of the drain tube adjacent to each expansion joint. The pipes shall be relocated or extended so that any discharge clears bridge seats or structural members, such as sign supports, by at least 6".

The structural tube may be placed in any convenient lengths using butt joints. The price per lin. ft. for this drainage system shall include all PVC pipe and fittings (schedule 40), structural tubes and all labor necessary to complete this item. The quantity will be the actual lengths of structural tube required.

The steel for the structural tube shall conform to the following:
 PREGALVANIZED, ASTM A446, Grade A Steel, Galvanizing as per ASTM A525.
 POSTGALVANIZED, ASTM A569 or A366, Galvanizing as per 711.02.
 Any damaged galvanizing shall be repaired as per AASHTO M36.
 The minimum steel thickness shall be 0.105".

The drain pipe and elbow shall comply with the dimensions and markings of ASTM D1785 and ASTM D2466, Type I and II respectively. The solvent cement for the pipe and fittings shall conform to ASTM D2564.

ESTIMATED QUANTITIES				
Item	Total	Unit	Description	As Built
511	*	Cu. yd.	Class C concrete, superstructure	
518	16,399	Lin. Ft.	Subdrainage for wearing course, as per plan	
Spec.	2	Each	Rear end dam modification	
Spec.	2	Each	Forward end dam modification	
Spec.	8	Each	Expansion joint modification	
Spec.	10	Each	Type I scupper modification	
Spec.	10	Each	Type 2 scupper modification	
Spec.	92	Each	Type 3 scupper modification	
404	3570 ^Δ	Cu. yd.	Asphalt concrete	
Spec.	893	Cu. yd.	Sand asphalt, see proposal note	
Spec.	64,705	Sq. yd.	Membrane waterproofing, see proposal note	
808	*	Units	Chemical admixture for concrete, Type A, B, or D	
407	‡	Tons	Cover aggregate	
407	‡	Gals.	Tack coat: T02.04, M3-2 or R3-1; or T02.02, R0-70 or R0-250	


* For quantity see Sh. 74/112

‡ For quantity see Sh. 10/112

^Δ Quantity shown is Bridge quantity. For quantity on approach slabs see Sh. 10/112.





PAYMENT for the modification items shall include all the new steel as well as the labor required to complete the modification. Unless otherwise noted all new steel shall be A588.

STATE OF OHIO DEPARTMENT OF HIGHWAYS DIVISION OF DESIGN AND CONSTRUCTION BUREAU OF BRIDGES					
EXPANSION JOINT MODIFICATION DECK DRAINAGE DETAILS ESTIMATED QUANTITIES I-480 OVER CUYAHOGA RIVER VALLEY, CUYAHOGA COUNTY					
DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE
NAA	NAA		CPD	WJJ	8-15-73



*N Varies between interior girders to provide 1/8" per ft. slope from crown. N is 10 1/4" between interior and exterior girders.

Note: The upper bearing plates at expansion joint 1, shall be rotated with respect to Unit 1 Girders F, G and H.





Notes:

Rollers, Gear Plates and Bearing Plates shall be alloy steel forgings conforming to ASTM A237-63T, Class B with a minimum yield strength of 55,000 p.s.i. and shall be paid for at the unit price bid for "Item 513, Structural Steel (A36)".

For girder web shop splices see Sheet 10/28.

For material identification in expansion joint see Sheet 18/28.



H.N.T.B. BR. NO. 38L AND 38R

HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK

INTERMEDIATE EXPANSION JOINT AND CROSSFRAME DETAILS

I-80 OVER CUYAHOGA RIVER VALLEY
BR. NO. CUY-80-1843 STA. 996+22.25 TO STA. 1037+77.75


CUYAHOGA COUNTY OHIO

DRAWN CHD	TRACED CP	CHECKED UH	REVIEWED WF	REVISED
DATE: 11-5-68	DATE: 2-15-69	DATE: 2-17-69	DATE: 8-22-70	

SHEET 17/28

FED. RD. DIVISION	STATE	PROJECT	90 112
2	OHIO		

CUYAHOGA COUNTY
 CUY-80-18.43 Part 2



AT INTERIOR GIRDER

Asphalt Concrete Surface
 Course not shown.

ALL WIND SHEAR KEY PARTS

MATERIAL DESIGNATIONS (ALL LIKE PARTS)
 ⦿ A.S.T.M. A-588 STRUCTURAL STEEL
 ⦿ BOLTS WITH A.S.T.M. A-588 CORROSION CHARACTERISTICS
 AND A.S.T.M. A-325 MECHANICAL PROPERTIES
 SEE PLANS FOR MATERIAL TYPES OF REMAINING PARTS


H.N.T.B. BR.NO. 38L AND 38R				
HOWARD, NEEDLES, TAMMEN & BERGENDOFF CONSULTING ENGINEERS KANSAS CITY CLEVELAND NEW YORK				
PERSPECTIVE INTERMEDIATE EXPANSION JOINT				
I-80 OVER CUYAHOGA RIVER VALLEY				
BR.NO. CUY-80-1843 L & R		STA. 996+22.25 TO STA. 1037+77.75		
CUYAHOGA COUNTY OHIO				
DRAWN/RH	TRACED	CHECKED	REVIEWED	REVISED
DATE 3/26/69	DATE	DATE 4/6/69	DATE 8/22/70	DATE
				SHEET 18/28

REV. 8-15-73


FED. RD. DIVISION	STATE	PROJECT
2	OHIO	

91
112


CUYAHOGA COUNTY
CUY-80-18.43 Part 2



ELEVATION




SECTION A - A




SECTION C - C


Note:
Only 21WF55 of crossframe has been shown. For details of crossframe and lateral bracing see Sheets 13/28 and 15/28.



SECTION B - B



DETAIL A



SECTION D - D
(Pl. 3/8 x 9/16 not shown)

Notes:
For signing and sign post details see Traffic Control Plans.
All connections shall be made with 1" high strength steel bolts.
All sign support parts, except as otherwise noted, on the outside of the exterior girders shall be A.S.T.M. A-588 structural steel. All parts inside of the exterior girder shall be A.S.T.M. A-36 structural steel.

H.N.T.B. BR. NO. 381 AND 382

HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK

SIGN SUPPORT NO. 100 AND NO. 103


I-80 OVER CUYAHOGA RIVER VALLEY
BR. NO. CUY-80-18.43 L&R STA. 996+22.25 TO STA. 1037+77.75

CUYAHOGA COUNTY OHIO


DRAWN: C.H.B.	TRACED: C.P.	CHECKED: J.M.S.	REVIEWED: W.W.
DATE: 3-7-69	DATE: 3-15-69	DATE: 7-16-70	DATE: 8-2-70

SHEET 19/28


REV. 8-15-73



SOUTH ELEVATION
Girder D shown, Details at Girder A are similar.




SECTION A-A
(Cross Bracing and Sign Post not shown)




SECTION D-D
(Pl. 3/8 x 9 3/4 not shown)

Note:
Only 21WF55 of crossframe has been shown. For details of crossframe and lateral bracing see Sheets 13/28 and 15/28



SECTION B-B

1 3/8" hole for 1 1/4" x 2'-8" High Strength Anchor Bolt (A.S.T.M. A193, Grade B7) threaded 10". Provide 2 beveled washers, 3 lock washers and 3 heavy hex nuts per bolt. (Assemble and tighten base plate support before installing ST7WF24).



SECTION C-C

For notes see Sheet 19/28

H.N.T.B. BR. NO. 38L AND 38R
HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK

SIGN SUPPORT NO. 104 AND NO. 106
I-80 OVER CUYAHOGA RIVER VALLEY

BR. NO. CUY-80-1843 L&R STA. 996+22.25 TO STA. 1037+77.75


CUYAHOGA COUNTY	OHIO
DRAWN: CHB	TRACED: CP
CHECKED: JMS	REVIEWED: WJS
DATE: 3-14-80	DATE: 3-17-80
	DATE: 7-16-79
	DATE: 2-22-79

SHEET 20/28


FED. RD. DIVISION	STATE	PROJECT
2	OHIO	

93
112


CUYAHOGA COUNTY
CUY-80-18.43 Part 2



ELEVATION



SECTION A-A




SECTION B-B

Note:
For notes see Sheet 19 | 28


H.N.T.B. BR. NO. 38L AND 38R				
HOWARD, NEEDLES, TAMMEN & BERGENDOFF CONSULTING ENGINEERS KANSAS CITY CLEVELAND NEW YORK				
CORPORATION LIMIT SIGN SUPPORTS				
1-80 OVER CUYAHOGA RIVER VALLEY				
BR. NO. CUY-80-1843 L & R			STA. 996+22.25 TO STA. 1037+77.75	
OHIO				
DRAWN	TRACED	CHECKED	REVIEWED	REVISED
DATE 6-17-70	DATE 6-19-70	DATE 7-16-70	DATE 8-21-70	SHEET 21 28

REV. 8-15-73


REVISIONS
DEC 1 1964



EXPANSION BEARING




FIXED BEARING




BEARING DIMENSIONS											
BEARING	LOCATION	NO. REQ'D	GIRDER	TYPE	A	B	C	D	E	F	WEIGHT
FB-A	PIERS 1, 4, 5, 7, 8, 10 and 11	28	Interior	Fixed	3'-0"	1'-0"	1'-1 1/2"	1'-9"	4'-0"		159,012
EB-B		28	Exterior	Exp.	2'-6"	11"	1'-0"	1'-7"	1'-8"	3'-10"	259,924
FB-C	PIER 14	4	Interior	Fixed	2'-0"	6"	7 1/2"	1'-3"	3'-0"		17,844
EB-D		4	Exterior	Exp.	1'-8"	6"	7"	1'-11"	1'-2"	2'-10"	27,800

Note: Weights given are total for all bearings, including high strength bolts, nuts and washers and 1/4" sheet lead.




SECTION THRU PIN




SECTION PIN END

PIN DETAILS




PINTLE DETAIL



DETAIL A

BEARINGS




BOLT DETAIL

Notes:
 Rockers for Abutments shall conform to the requirements set forth by Ohio Standard Drawing RB-1-55.
 All castings shall be ASTM A 486, Class 90 Cast Steel, with a 60,000 p.s.i. minimum yield point. All fillets shall be 3/4" radius, except as shown.
 All rollers, pins, base plates, gears and gear racks shall be ASTM A 237, Class B Steel Forgings, with a 55,000 p.s.i. minimum yield point.
 All nuts, bolts, washers and rings shall be Structural Carbon Steel (A 36).
 Provide 1/4" sheet lead between masonry and bearing and fill space around anchor bolts with molten lead before placing nuts.
 All base plates and castings shall be scribed with longitudinal and transverse center lines.

ABUTMENT ROCKER DIMENSIONS (Inches)															
ROCKER NO.	NO. REQ'D	A	B	C	D	F	G	H	K	L	M	R	T	Y	WEIGHT
Mod. R-300	4	3 1/2	22	3 1/2	3 1/2	3 1/2	12	19 1/2	14	28	25	12 1/2	3	1 1/2	4,392
R-350	2	3 1/2	22	4	3 1/2	4	12	20 1/2	15	30	25	13 1/2	3 1/2	1 1/2	2,586
R-425	6	3 1/2	24	4	3 1/2	1	12	22 1/2	16	32	28	14 1/2	3 1/2	1 1/2	9,414
R-500	2	4	26	4	3 1/2	1	13	24 1/2	17	34	31	16	4	1 1/2	3,848
R-600	2	4	27	4	4	1	14	25 1/2	22	37	34	17	4 1/2	1 1/2	4,938

Note: For dimension locations and details see Ohio Standard Drawing RB-1-55, revised 2-2-59. Rocker details, except for anchor bolt holes in base plate, shall be the same as given on Ohio Standard Drawing RB-1-55, but with dimensions as shown here. Bevel top sole plates to match grade.

ROCKERS-ABUTMENTS



ROCKER BASE PLATE

H.N.T.B. BR. NO. 36L AND 38R

HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK

BEARINGS - PIERS 1, 4, 5, 7, 8, 10, 11 AND 14

ROCKERS - ABUTMENTS

I-80 OVER CUYAHOGA RIVER VALLEY
BR. NO. CUY-80-1843 STA. 996+22.25 TO STA. 1037+77.75

CUYAHOGA COUNTY OHIO


DRAWN/15	TRACED/16	CHECKED/16	REVIEWED/16	REVISED
DATE 8-68	DATE 8-68	DATE 1-16-69	DATE 8-21-70	SHEET 22/28

MICHJFLMRE
DEC 1 0 1984


FED. RD. DIVISION	STATE	PROJECT
2	OHIO	

95
112


CUYAHOGA COUNTY
CUY-80-1843 Part 2




SIDE ELEVATION




ELEVATION




ELEVATION OF GEARING




SECTION A-A




SECTION THRU PIN



SECTION PIN END



DETAIL A



SECTION B-B

For notes see Sheet 22/28.

BEARING DIMENSIONS																					
BEARING	LOCATION	NO. ROLLERS	GIRDER	A	B	C	D	E	F	G	H	J	K	L	M	N	P	R	S	T	LBS.
EB-E	PIER 2	4	Interior	2'-3"	11"	5'-0"	3'-0"	1'-0"	1'-1 1/2"	1'-7"	1'-11"	4'-4"	13"	3 3/8"	6 1/2"	7"	9"	6"	6 1/8"	9 1/2"	68,808
EB-F		4	Exterior	2'-3"	11"	5'-0"	2'-6"	9"	10 1/2"	1'-2"	1'-6"	3'-6"	12"	3 3/8"	6"	6"	8"	5"	5 1/8"	8 1/2"	56,576
EB-G	PIERS 3,	12	Interior	2'-8 1/2"	1'-4"	5'-11"	3'-0"	1'-0"	1'-1 1/2"	1'-2"	1'-6"	3'-6"	11"	2 1/2"	5 1/2"	5"	7"	4"	4 1/8"	7 1/2"	190,248
EB-H	6 AND 9	12	Exterior	2'-8 1/2"	1'-4"	5'-11"	2'-6"	9"	10 1/2"	11"	1'-3"	3'-0"	11"	2 1/2"	5 1/2"	5"	7"	4"	4 1/8"	7 1/2"	166,392
EB-J	PIERS 12	8	Interior	2'-4"	1'-0"	5'-2"	2'-0"	6"	7 1/2"	1'-0 1/2"	1'-4 1/2"	3'-3"	13"	3 3/8"	6 1/2"	7"	9"	6"	6 1/8"	9 1/2"	107,728
EB-K	AND 13	8	Exterior	2'-4"	1'-0"	5'-2"	1'-8"	4"	5 1/2"	8 1/2"	1'-0 1/2"	2'-7"	12"	3 3/8"	6"	6"	8"	5"	5 1/8"	8 1/2"	88,288

Note: Weights given are total for all bearings, including high strength bolts, nuts and washers and 1/2" sheet lead bearing pad.

H.N.T.B. BR NO. 38L AND 38R

HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK

BEARINGS - PIERS 2, 3, 6, 9, 12 AND 13

I-80 OVER CUYAHOGA RIVER VALLEY
BR. NO. CUY-80-1843 STA. 996+22.25 TO STA. 1037+77.75




CUYAHOGA COUNTY OHIO

DRAWN JLS	TRACED RLV	CHECKED CJB	REVIEWED WJ	REVISED
DATE 8-68	DATE 8-68	DATE 1-14-69	DATE 8-22-70	SHEET 23/28

FED. RD. DIVISION	STATE	PROJECT
2	OHIO	


96
112

CUYAHOGA COUNTY
CUY-80-1843 Part 2




PIPE SUPPORTS AT WEST ABUTMENTS
Each 6" ϕ scupper pipe at the West Abutments shall be supported by two 6L8.2 channel supports with 3/4" ϕ U-bolts, one 2'-0" above the bottom flange and the other 7'-0" above the bottom flange.

COLLECTOR SYSTEM AT PIERS 3, 6 AND 9
(Similar at Pier 12, except as noted. No Collector System at West Abutments)



SECTION B-B
FOR SCUPPER MODIFICATION SEE SHEET 96A 112




Notes:
The collector system shall be 8" alloy steel pipe, 707.11, or hot-dip galvanized steel pipe. Joints shall be made by welding or by the use of a clamp-type coupling with a ring gasket. All welding shall be done before galvanizing. Pipe supports shall be A588 steel or hot-dip galvanized steel. On bolts, galvanizing as called for in ASTM A153 is acceptable.
The 8" ϕ pipe collector system including fittings, supports and accessories shall be paid for at the unit price bid for "Item 518, 8" ϕ Pipe Collector System."
Scuppers and supports shall be structural carbon steel ASTM A36. Support Ls 2x2x1/4, pipe and supports at west abutment shall be included with "Item 518, Scuppers" for payment. For additional scupper details see Ohio Standard Drawing SD-1-69 Sheet 3 of 4.

H.N.T.B. BR NO. 381 AND 38R	
HOWARD, NEEDLES, TAMMEN & BERGENDOFF CONSULTING ENGINEERS KANSAS CITY CLEVELAND NEW YORK	
DRAINAGE DETAILS	
I-80 OVER CUYAHOGA RIVER VALLEY BR. NO. CUY-80-1843 STA. 996+22.25 TO STA. 1037+77.75	
CUYAHOGA COUNTY OHIO	
DRAWN T.J.S.	TRACED C.P.
DATE 9-11-68	DATE 9-30-68
CHECKED J.E.H.	REVIEWED W.F.
DATE 2-17-69	DATE 8-21-70
SHEET 24/28	

Note: Longitudinal curb reinforcement per unit consists of 4 Lines of 28-S601 except as follows:
UNIT 1L - 4 Lines of 28-S601 and 1-S602.
UNIT 5L and 5R - 4 Lines of 23-S601 and 1-S602.

Note: A haunch width of 9" shall be used for computing quantity of concrete. However, the haunch width may vary between 6" and 12" provided that the slope shall be not more than 1:4 for a haunch less than 9" in width.
All Girder haunch depths are measured from top of web to top of pavement @ 1/2 Bearing.




TYPICAL CROSS SECTION
(Except Unit 1R)

Note: All reinforcing bar marks shall be prefixed as follows:
SL = Left Bridge
SR = Right Bridge

3'-2" (Varies to 3'-6" Max. in Span 1L)
See Detail A

† Haunch depth shall be 11 1/2" For details of Surface for UNIT 5 (Land R) exterior course and Subdrainage see sheet 88A/112



TYPICAL CROSS SECTION - UNIT 1R


* See Slab Plan for spacing.

Dimensions are given for Pier 2R only
See Framing Plan, Sheet 5/28

408 @ 6 1/2"		514 @ 7"		413 @ 8"		Reinforcing bar Spacing
Bearing West Abutment		Expansion Joint 1				
204-S606	204-S608	257-S610	257-S609	207-S613	206-S612	Bottom
204-S616	204-S618	257-S620	257-S622	207-S624	206-S625	Top
204-S607	204-S609	257-S611	257-S612	207-S614	206-S615	Bottom
204-S617	204-S619	257-S621	257-S623	207-S614	206-S615	Top
204-S606	204-S608	257-S610	257-S609	207-S613	206-S612	Bottom
204-S616	204-S618	257-S620	257-S622	207-S624	206-S625	Top

153 Lines of 28-S601 and 1-S602 (See Typical Cross Section Unit 1R for spacing)

SLAB PLAN - UNIT 1R




ADDITIONAL REINFORCING BARS AT PIERS

Note: The Contractor shall submit a deck pouring sequence and method to the Director for approval. Concrete shall be placed symmetrically about longitudinal centerline of deck. No longitudinal construction joints will be permitted. The deck shall be poured west to east, beginning at the West Abutment, due to design consideration of detrimental deflection at the deck expansion joints.

SLAB REINFORCEMENT QUANTITIES				
Unit	Longitudinal reinforcement	S603	S604	S605
1L	99 Lines of 28-S601 and 1-S602	2548	2548	1274
1R	See Unit 1R Slab Plan			
2, 3 and 4 (L and R)	99 Lines of 32-S601	2874	2874	1437
5L and 5R	99 Lines of 23-S601 and 1-S602	2090	2090	1045

Note: For parapet joints and longitudinal reinforcement in the parapet see Sheet 26/28



DETAIL A

Pier	A	B	C	No. of Bars
1L	57'-0"	57'-0"	3'-0"	42 Lines of 3-S626
1R	57'-0"	57'-0"	3'-0"	60 Lines of 3-S626
2L, 5L, 8L, 8R, 11L & 11R	63'-0"	63'-0"	3'-0"	42 Lines of 4-S627
2R	63'-0"	63'-0"	3'-0"	60 Lines of 4-S627
3L, 3R, 6L, 6R, 9L, 9R, 12L & 12R	21'-6"	30'-0"	0	42 Lines of 2-S628
4L, 4R, 7L, 7R, 10L & 10R	66'-0"	66'-0"	3'-0"	42 Lines of 4-S629
13L & 13R	52'-0"	52'-0"	3'-0"	42 Lines of 3-S630
14L & 14R	44'-0"	44'-0"	3'-0"	42 Lines of 3-S631

H.N.T.B. BR. NO. 38L AND 38R


HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK

TYPICAL CROSS SECTION AND DECK REINFORCEMENT





BR. NO. CUY-80-1843 STA. 996+22.25 TO STA. 1037+77.75

CUYAHOGA COUNTY OHIO

DRAWN/EL	TRACED/LL	CHECKED/JS	REVIEWED/WF	REVISED
DATE 7-14-68	DATE 7-16-68	DATE 9-9-68	DATE 8-22-70	SHEET 25/28




Note:
All reinforcing bar marks for parapet shall be prefixed as follows:
SL = Left Bridge
SR = Right Bridge



REINFORCING SCHEDULE					
LIGHT STANDARD SUPPORT					
MARK	NO.	LENGTH	SHAPE	SER. INCR.	WEIGHT
L501	19	13'-1 1/4"	101		259
L502	19	9'-3 3/4"	101		183
L503	2	17'-0 1/4"	141		35
L504	4	7'-4 1/4"	115	(31)	34
L505	4	5'-8 1/4"	163		24
L506	4	6'-7 1/4"	164	(27)	30
L507	4	6'-4 1/4"	165	(26)	29
L508	16	2'-5 1/4"	105	(40)	60
L509	12	2'-6 1/4"	104		31
L510	2	3'-8 1/4"	142	(8)	9
L511	2	5'-9 1/4"	166	(12)	13
L512	10	3'-4 1/4"	142	(35)	41
L513	10	5'-4 1/4"	160		56
L514	2-3	3'-5 1/4"	100	6"	25
L515	2	4'-8 1/4"	Str.	(10)	13
TOTAL WEIGHT =					802

For 1 (one) Light Standard Support on Bridge
TOTAL WEIGHT = 802



H.N.T.B. BR. NO. 38L AND 38R

HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK

PARAPET AND
LIGHT SUPPORT DETAILS

BR. NO. CUY-80-1843 STA. 996+22.25 TO STA. 1037+77.75


CUYAHOGA COUNTY OHIO

DRAWN/LEH	TRACED/GCM	CHECKED/JS	REVIEWED/WF	REVISED 11-18-70
DATE 9-5-68	DATE 7-2-68	DATE 9-9-68	DATE 8-22-70	SHEET 26/28

Note: See Lighting Plans for additional details.

UNIT NO. 1												UNIT NO. 3						UNIT NO. 4						UNIT NO. 5								
Station	Elev. A	Girder A	Girder B	Girder C	Girder D	Elev. B	Girder E	Girder F	Girder G	Girder H	Elev. C	Station	Elev. A	Girder A	Girder B	Girder C	Girder D	Elev. B	Station	Elev. A	Girder A	Girder B	Girder C	Girder D	Elev. B	Station	Elev. A	Girder A	Girder B	Girder C	Girder D	Elev. B
996+25	713.63	713.65	714.00	714.01	713.66	713.64	713.66	714.09	713.84	713.41	713.39	1013+45	758.69	758.71	759.06	759.08	758.73	758.71	1022+45	782.27	782.29	782.64	782.66	782.31	782.29	1031+45	805.85	805.87	806.22	806.24	805.89	805.87

UNIT NO. 2						
Station	Elev. A	Girder A	Girder B	Girder C	Girder D	Elev. B
1004+45	735.11	735.13	735.48	735.50	735.15	735.13



TYPICAL CROSS-SECTION
2 1/2" Surface Course not shown

TOP OF PIER ELEVATIONS																	
Location	Girder A	Girder B	Girder C	Girder D	Girder E	Girder F	Girder G	Girder H	Location	Girder A	Girder B	Girder C	Girder D	Girder H			
Pier 1	699.57	700.83	700.85	699.59	699.46	700.78	700.59	699.27	Pier 8	754.52	755.81	755.83	754.54	754.54	755.83	755.81	754.52

Note:
Elevations A, B and C shown at curbs are those which are required before concrete is placed. Proper allowance has been made for the dead load deflections caused by the weight of the reinforced concrete.
Elevations shown over the girders are final top of (pavement) elevations.
reinforced concrete slab

H.N.T.B. BR. NO. 381 AND 382

HOWARD, NEEDLES, TAMMEN & BERGENOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK

TOP OF PAVEMENT ELEVATIONS
AND TOP OF PIER ELEVATIONS
I-80 OVER CUYAHOGA RIVER VALLEY
BR. NO. CUY-80-1843 L & R STA. 996+22.25 TO STA. 1037+77.75

CUYAHOGA COUNTY OHIO

DATE 10/18/84	TRACER/EA	CHECKED 7/5	REVIEWED
DATE 10/22/84	DATE 10/28/84	DATE 8-22-84	DATE

SHEET 27/28

APPENDIX C

Project Background Documents

C. RECOMMENDATIONS

To be further determined and finalized based on the meeting with ODOT on March 26, 2012. A draft matrix is provided below that will be further enhanced. All the options seem to have merit and there are reasonable increased benefits as cost increase. The “other” considerations for the owner in the decision making would seem to be the deciding factor. At this time, ELR did not make a recommendation prior to the March 26 meeting but if desired by ODOT we could.

CUY-480-18.42- COST MATRIX

Options	Cost (millions)	Time of Disruption (years)	Most Benefit	Least Benefit
1A-New structure	\$255	3	All new	Most cost
1B-New median structure	\$215	2	Least disruption to traffic	Span type/configuration dictated by existing
2-New superstructure	\$160	4	All new superstructure	No additional roadway capacity
3-New deck and intermediate girders	\$100	4 ½	Elimination of fatigue concerns	Most disruption to traffic
4-New deck	\$65	3	Least cost	Uncertainty



Meeting Minutes

Date of Meeting: August 19, 2011
1:00 p.m.

To: Poonsak Sritalapat
ODOT – District 12

From: Dave Traini
E.L. Robinson Engineering of Ohio Co.

Subject: CUY-480-1842 L&R
Deck Replacement Study Scope of Services

Attached for your reference and use are the meeting minutes from the Deck Replacement Study Scope of Services held August 19, 2011 at The Ohio Department of Transportation – District 12 office at 5500 Transportation Blvd, Garfield Heights, Ohio.

Attendees:	Poonsak Sritalapat	ODOT District 12
	Mike Kubek	“
	Dick Walters	“
	Jim Calanni	“
	Mike Herceg	“
	Chris Ondash	“
	Lou Hazapis	“
	Dennis O’Neil	“
	Tim Keller	ODOT Central Office
	Ananda Dharma	ODOT Central Office
	Dave Traini	E. L. Robinson Engineering
	Rick Rockich	“
	Jonathan Hren	“
	George Maki	“

Issues Discussed

Mr. Sritalapat opened the meeting.

A draft scope was distributed to all attendees. A listing of the various maintenance of traffic scenarios and cross-sections of the MOT phases were also provided.

It was emphasized that the objective of the study is to determine the optimum approach for the I-480 deck replacements that will provide the least inconvenience and be the safest to the motoring public.

A status of the I-77 bridge project over the canal and Granger Road to the west was given. Some construction is expected to begin in 2013 but will really begin in 2014 and last through 2016 with some clean-up expected in 2017.

It is expected to take two construction seasons to do the I-480 project. (One for each bridge) It would be very unwise to have restricting traffic control in place in the winter on the I-480 bridges due to plowing and maintenance reasons.

The District ideally would like work on I-480 to be performed during 2012 and 2013 or after I-77 Bridge over the canal and Granger Rd, in the year 2017 and 2018. However, the maintenance of traffic on the I-77 project and the I-480 project may be looked at together to develop the best maintenance of traffic plan.

If the findings of this study dictate the deck replacement will need to occur in the future, a parapet repair and fence replacement contract could be let to address the immediate safety concerns of the existing parapets. It is estimated about \$2 to \$3 million for the cost of parapet repairs; this work would eventually be removed when future deck replacement occurs.

Mr. Walters outlined the goal of the deck replacement study following the Draft Scope dated 8-15-2011.

Task 1

This task will be skipped based on the BARS analysis provided by Central Office. Note the controlling rating for the two bridges was HS19.4 and 19.8 rating.

Task 2.0 and 2.2

The strength of the cross-frames and out-of-plane bending is a perceived problem with part width deck removal. How the various stages of construction outlined in Task 2.0 affect the stresses in the crossframes and connection details shall be investigated. Out-of-plane bending stresses must be checked. The effects of fatigue shall be studied, attempting to predict future impacts due to the stage construction loadings.

MOT-Scenario #1 is the suggested MOT plan that detrimental effects such as differential deflection, out-of-plane bending and excessive crossframe/diaphragm stresses would be minimized by placing balanced/symmetrical loads on the superstructure. 3-D analysis response of the superstructure is required to verify whether cross members can be retained (no work, preferred), need reinforcement or have to be removed during the phase construction. Special deck placement sequences may be utilized to benefit the superstructure responses.

Task 3.0

Provide overview of the various possible rehabilitation and replacement solutions. Cost, assessment of future life, disruption to public and construction duration should all be considered.



This task can be performed concurrently with Tasks 2.0 and 2.2. The draft scope provides some options.

ELR should not limit their options to the items discussed or items in the scope but may suggest any innovative solution to replace the decks safely and at a minimum of inconvenience to the public. New ideas can be discussed with ODOT and studied further if deemed appropriate.

The following are misc. topics that were discussed.

- Stay-in-place forms would only be considered in a new bridge as they would add too much weight to the existing bridges. Lightweight concrete could be an option.
- For the replacement option for Task 3.0, a new bridge constructed in between the existing bridges is the best solution for Maintenance of Traffic.
- Six lanes of traffic on one bridge with 10'-6" lanes is feasible but most likely unreasonable. Minimum width of traffic lanes for MOT is 12 feet.
- The District determined that based on the findings of the recent inspection reports that the present condition of existing substructures is adequate. The substructures have been in service for 35 years and show no signs of distress. Some options may increase or rearrange the points of loading and if necessary will be investigated later. Jim Calanni will however look into past inspection reports and/or discuss with Youssef Seif.
- Mr. Maki mentioned that the original design had asphalt drains that dripped drainage onto the outside of the exterior girder bottom flanges and then ran down on top of the pier caps. A contract was let to plug the asphalt drains and redirect that drainage into the cross drains at the expansion joints. This may have caused some deicing salts to be present on the existing pier caps.
- Five lanes of traffic on one bridge and part width on the other will be necessary to adequately maintain the high traffic volume.
- Fatigue Life Analysis, to determine remaining life, is not required.

Request for Additional Information

- Deck cores were taken. The District will provide information from these deck cores including deck thickness and any other useful data such as compressive strength, if available.
- District will provide full BARS output.

Study time frame:

The time frame for completing this study is ASAP.

Tim Keller needs a proposal from ELR. After he receives the proposal he would have a contract ready in probably 2-3 days.

The meeting was adjourned at 2:30 p.m.



Meeting minutes as taken by Dave Traini, P.E. of EL Robinson Engineering. These minutes are presented to the best of my knowledge as recorded August 19, 2011. Any comments or revisions should be submitted within three days of receipt.