REF NO.	ITEM NUMBER	ITEM EXTENSION	ITEM DESCRIPTION	WORK TYPE	UNIT	ESTIMATED QUANTITY	UNIT PRICE BID DOLLARS I CTS	TOTAL AMOUNT BID DOLLARS I CTS
			ROADWAY					
1	201	11000	CLEARING AND GRUBBING	01	-	LS		
1A	SPECIAL	20120010	TREE REMOVED, 4"-12"	01	EACH	2		
1B	201	21800	TREE REMOVED, 18"	01	EACH	4		
1C	201	23000	TREE REMOVED, 30"	01	EACH	1		
1D	201	24800	TREE REMOVED, 48"	01	EACH	1		
2	SPECIAL	20126450	STUMP REMOVED, 4"-12"	01	EACH	11		
3	201	26500	STUMP REMOVED, 18"	01	EACH	10		
4	201	26510	STUMP REMOVED, 30"	01	EACH	1		
5			NOT USED					
6	202	23000	PAVEMENT REMOVED	16	SY	3,730		
7	202	30000	WALK REMOVED	NR	SF	56		
8	202	32000	CURB REMOVED	NR	FT	147		
9	202	32500	CURB AND GUTTER REMOVED	NR	FT	387		
10	202	35100	PIPE REMOVED, 24" AND UNDER	NR	FT	371		
11	202	38000	GUARDRAIL REMOVED	NR	FT	256		
12	202	58000	MANHOLE REMOVED	NR	EACH	1		
13	202	58100	CATCH BASIN REMOVED	NR	EACH	4		
14	202	75000	FENCE REMOVED	NR	FT	124		
15	202	75255	GATE REMOVED FOR REUSE, AS PER PLAN	37	EACH	1		
16	202	98100	REMOVAL MISC.: FLAG POLE REMOVED	NR	EACH	1		
17	202	98100	REMOVAL MISC.: LIGHT REMOVED	NR	EACH	1		

REF NO.	ITEM NUMBER	ITEM EXTENSION	ITEM DESCRIPTION	WORK TYPE	UNIT	ESTIMATED QUANTITY	UNIT PRICE BID DOLLARS I CTS	TOTAL AMOUNT BID DOLLARS I CTS
18	203	10000	EXCAVATION	04	CY	3,070		
19	203	20001	EMBANKMENT, AS PER PLAN	04	CY	316		
20	204	10000	SUBGRADE COMPACTION	04	SY	4,187		
21	204	30020	GRANULAR MATERIAL, TYPE C	07	CY	426		
22	204	51000	GEOGRID	07	SY	856		
23	SPECIAL	69012010	GEOTEXTILE FABRIC	07	SY	856		
24	209	60201	LINEAR GRADING, AS PER PLAN	04	SY	2,930		
25	606	15050	GUARDRAIL, TYPE MGS	36	FT	37.5		
26	606	26100	ANCHOR ASSEMBLY, TYPE E	36	EACH	1		
27	606	26500	ANCHOR ASSEMBLY, TYPE T	36	EACH	1		
28	606	35000	BRIDGE TERMINAL ASSEMBLY, TYPE 1	36	EACH	2		
29	608	10001	4" CONCRETE WALK, AS PER PLAN	38	SF	1,146		
30	608	52000	CURB RAMP	38	SF	210		
31	623	40501	REFERENCE MONUMENT, AS PER PLAN	NR	EACH	1		
32	623	40520	RIGHT-OF-WAY MONUMENT	NR	EACH	2		
						SECTION TOTAL ROADWAY :		
			EROSION CONTROL					
33	659	00300	TOPSOIL	46	CY	300		
34	659	10001	SEEDING AND MULCHING, AS PER PLAN	46	SY	2,930		
35	659	14000	REPAIR SEEDING AND MULCHING	46	SY	130		
36	659	20000	COMMERCIAL FERTILIZER	46	TON	0.35		
37	659	31000	LIME	46	ACRE	0.06		

REF NO.	ITEM NUMBER	ITEM EXTENSION	ITEM DESCRIPTION	WORK TYPE	UNIT	ESTIMATED QUANTITY	UNIT PRICE BID DOLLARS I CTS	TOTAL AMOUNT BID DOLLARS I CTS
38	659	35000	WATER	46	MGAL	16		
39	670	00520	SLOPE EROSION PROTECTION MAT, TYPE B	35	SY	535		
40	832	15000	STORM WATER POLLUTION PREVENTION PLAN	08	-	LS		
41	832	15002	STORM WATER POLLUTION PREVENTION INSPECTIONS	08	-	LS		
42	832	15010	STORM WATER POLLUTION PREVENTION INSPECTION SOFTWARE	08	-	LS		
43	832	30000	EROSION CONTROL	08	EACH	60,000	$ 1.00	$ 60,000.00
			SECTION TOTAL EROSION CONTROL :					
			DRAINAGE					
44	602	20000	CONCRETE MASONRY	35	CY	0.4		
45	605	14021	6" BASE PIPE UNDERDRAINS WITH GEOTEXTILE FABRIC, AS PER PLAN	35	FT	852		
46	611	97400	CONDUIT, MISC.: 6" CONDUIT, TYPE B, FOR DRAINAGE CONNECTION, AS PER PLAN	35	FT	50		
47	611	97400	CONDUIT, MISC.: 6" CONDUIT, TYPE C, FOR DRAINAGE CONNECTION, AS PER PLAN	35	FT	50		
48	611	01401	6" CONDUIT, TYPE E, AS PER PLAN	35	FT	70		
49	611	04401	12" CONDUIT, TYPE B, AS PER PLAN	35	FT	339		
50	611	05901	15" CONDUIT, TYPE B, AS PER PLAN	35	FT	36		
51	611	07401	18" CONDUIT, TYPE B, AS PER PLAN	35	FT	75		
52	611	08901	21" CONDUIT, TYPE B, AS PER PLAN	35	FT	180		
53	611	98181	CATCH BASIN, NO. 3A, AS PER PLAN (CUYAHOGA COUNTY NO. 3C)	35	EACH	3		
54	611	98391	CATCH BASIN, NO. 7, AS PER PLAN	35	EACH	1		
55	611	98471	CATCH BASIN, NO. 2-2B, AS PER PLAN	35	EACH	3		
56	611	98631	CATCH BASIN ADJUSTED TO GRADE, AS PER PLAN	35	EACH	3		

REF NO.	ITEM NUMBER	ITEM EXTENSION	ITEM DESCRIPTION	WORK TYPE	UNIT	ESTIMATED QUANTITY	UNIT PRICE BID DOLLARS I CTS	TOTAL AMOUNT BID DOLLARS I CTS
57	611	98631	CATCH BASIN ADJUSTED TO GRADE, AS PER PLAN A	35	EACH	1		
58	611	98631	CATCH BASIN ADJUSTED TO GRADE, AS PER PLAN B	35	EACH	1		
59	611	98635	CATCH BASIN RECONSTRUCTED TO GRADE, AS PER PLAN	35	EACH	1		
60	611	98690	CATCH BASIN, MISC.: TEMPORARY PLATE	35	EACH	1		
61	611	98701	INLET, SIDE DITCH, AS PER PLAN	35	EACH	1		
62	611	99575	MANHOLE, NO. 3, AS PER PLAN (WITH NO. 37 COVER)	35	EACH	2		
63	611	99575	MANHOLE, NO. 3, AS PER PLAN A	35	EACH	1		
64	611	99655	MANHOLE ADJUSTED TO GRADE, AS PER PLAN	35	EACH	1		
65	611	99661	MANHOLE RECONSTRUCTED TO GRADE, AS PER PLAN	35	EACH	1		
66	SPECIAL	61199820	MISCELLANEOUS METAL	35	LB	5,000		
						SECTION TOTAL DRAINAGE :		
			PAVEMENT					
67	254	01001	PAVEMENT PLANING, ASPHALT CONCRETE, AS PER PLAN, 1.25"	13	SY	184		
68	254	01001	PAVEMENT PLANING, ASPHALT CONCRETE, AS PER PLAN, 3"	13	SY	1,222		
69	302	46001	ASPHALT CONCRETE BASE, PG64-22, AS PER PLAN	10	CY	359		
70	304	20001	AGGREGATE BASE, AS PER PLAN	09	CY	682		
71	407	20000	NON-TRACKING TACK COAT	11	GAL	571		
72	441	50101	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22, AS PER PLAN	10	CY	85		
73	441	50101	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG70-22M, AS PER PLAN	10	CY	97		
74	441	50301	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (448), PG64-22, AS PER PLAN	10	CY	245		
75	452	12010	8" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC 1P	38	SY	32		

REF NO.	ITEM NUMBER	ITEM EXTENSION	ITEM DESCRIPTION	WORK TYPE	UNIT	ESTIMATED QUANTITY	UNIT PRICE BID DOLLARS I CTS	TOTAL AMOUNT BID DOLLARS I CTS
76	609	12001	COMBINATION CURB AND GUTTER, TYPE 2, AS PER PLAN A	38	FT	584		
77	609	12001	COMBINATION CURB AND GUTTER, TYPE 2, AS PER PLAN B	38	FT	118		
78	609	18001	COMBINATION CURB AND GUTTER, TYPE 3, AS PER PLAN	38	FT	47		
79	609	24511	CURB, TYPE 4-C, AS PER PLAN	38	FT	29		
80	609	26001	CURB, TYPE 6, AS PER PLAN	38	FT	165		
81	875	10000	LONGITUDINAL JOINT ADHESIVE	10	LB	192		
SECTION TOTAL PAVEMENT :								
			WATER WORK					
82	202	75610	VALVE BOX REMOVED	35	EACH	1		
83	638	07500	12" GATE VALVE	35	EACH	1		
84	638	08620	12" INSERTING VALVE AND VALVE BOX	35	EACH	2		
85	638	10300	FIRE HYDRANT EXTENDED AND ADJUSTED TO GRADE	35	EACH	1		
86	638	10400	FIRE HYDRANT ADJUSTED TO GRADE	35	EACH	1		
87	638	10700	FIRE HYDRANT REMOVED AND DISPOSED OF	35	EACH	2		
88	638	10801	VALVE BOX ADJUSTED TO GRADE, AS PER PLAN	35	EACH	3		
89	SPECIAL	63820172	12" WATER MAIN DIP CLASS 52 BOLTLESS RESTRAINED JOINTS AND FITTINGS	35	FT	240		
90	SPECIAL	63820750	6" FIRE HYDRANT FURNISHING AND SETTING, COMPLETE	35	EACH	2		
91	SPECIAL	63820884	CUT AND PLUG EXISTING 12" WATER LINE	35	EACH	2		
SECTION TOTAL WATER WORK :								
			TRAFFIC CONTROL					
92	630	03100	GROUND MOUNTED SUPPORT, NO. 3 POST	42	FT	144.5		

REF NO.	ITEM NUMBER	ITEM EXTENSION	ITEM DESCRIPTION	WORK TYPE	UNIT	ESTIMATED QUANTITY	UNIT PRICE BID DOLLARS I CTS	TOTAL AMOUNT BID DOLLARS I CTS
93	630	80101	SIGN, FLAT SHEET, AS PER PLAN	42	SF	42.3		
94	630	84900	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL	42	EACH	8		
95	630	85100	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	42	EACH	3		
96	630	85200	REMOVAL OF GROUND MOUNTED SIGN AND DELIVERY	42	EACH	6		
97	630	85201	REMOVAL OF GROUND MOUNTED SIGN AND DELIVERY, AS PER PLAN	42	EACH	1		
98	630	86002	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	42	EACH	18		
99	630	89816	REMOVAL OF WOOD POLE AND REERECTION	42	EACH	1		
100	630	97700	SIGNING, MISC.: SIGN ADJUSTED	42	EACH	1		
101	646	10000	EDGE LINE, 4"	45	MILE	0.25		
102	646	10200	CENTER LINE	45	MILE	0.22		
103	646	10400	STOP LINE	45	FT	65		
104	646	10500	CROSSWALK LINE	45	FT	90		
105	646	20000	RAILROAD SYMBOL MARKING	45	EACH	1		
106	646	20200	PARKING LOT STALL MARKING	45	FT	1,242		
			SECTION TOTAL TRAFFIC CONTROL :					
			RETAINING WALLS					
107	503	11100	COFFERDAMS AND EXCAVATION BRACING	53	-	LS		
108	503	21301	UNCLASSIFIED EXCAVATION, AS PER PLAN	38	-	LS		
109	504	11100	STEEL SHEET PILING LEFT IN PLACE (MINIMUM SECTION MODULUS OF 30 CUBIC INCHES PER FOOT OF WALL)	53	SF	125		
110	509	10001	EPOXY COATED REINFORCING STEEL, AS PER PLAN	23	LB	10,644		
111	511	46213	CLASS QC1 CONCRETE WITH QC/QA, RETAINING/WINGWALL INCLUDING FOOTING, AS PER PLAN	38	CY	68		

REF NO.	ITEM NUMBER	ITEM EXTENSION	ITEM DESCRIPTION	WORK TYPE	UNIT	ESTIMATED QUANTITY	UNIT PRICE BID DOLLARS I CTS	TOTAL AMOUNT BID DOLLARS I CTS
112	511	53012	CLASS QC2 CONCRETE, MISC.: MOMENT SLAB WITH QC/QA, AS PER PLAN	38	CY	21		
113	511	71200	CONCRETE, MISC.: ARCHITECTURAL TREATMENT	38	SF	543		
114	512	10050	SEALING OF CONCRETE SURFACES (NON-EPOXY)	57	SY	50		
115	512	33000	TYPE 2 WATERPROOFING	40	SY	2		
116	512	33300	TYPE A WATERPROOFING	40	SY	35		
117	512	44400	TYPE B WATERPROOFING	40	SY	2		
118	SPECIAL	51275500	SEALING: ELASTOMERIC PROTECTIVE AND DECORATIVE CONCRETE COATING	57	SY	22		
119	516	13200	1/2" PREFORMED EXPANSION JOINT FILLER	27	SF	71		
120	516	13601	1" PREFORMED EXPANSION JOINT FILLER, AS PER PLAN	27	SF	6		
121	517	75121	RAILING (CONCRETE PARAPET WITH TWIN STEEL TUBE RAILING), AS PER PLAN	38	FT	69		
122	518	21201	POROUS BACKFILL WITH GEOTEXTILE FABRIC, AS PER PLAN	35	CY	25		
123	518	40000	6" PERFORATED CORRUGATED PLASTIC PIPE	35	FT	92		
124	SPECIAL	53000200	STRUCTURES: PROTECTION OF FACILITIES	38	-	LS		
SECTION TOTAL RETAINING WALLS :								
			STRUCTURE OVER 20 FOOT SPAN (OLD ROCKSIDE 00.42 SFN 1876083)					
125	202	11003	STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN	19	-	LS		
126	202	23500	WEARING COURSE REMOVED	19	SY	348		
127	208	14001	VIBRATION CONTROL AND MONITORING, AS PER PLAN	53	-	LS		
128	503	11100	COFFERDAMS AND EXCAVATION BRACING	53	-	LS		
129	503	21301	UNCLASSIFIED EXCAVATION, AS PER PLAN	21	-	LS		
130	505	11100	PILE DRIVING EQUIPMENT MOBILIZATION	53	-	LS		

REF NO.	ITEM NUMBER	ITEM EXTENSION	ITEM DESCRIPTION	WORK TYPE	UNIT	ESTIMATED QUANTITY	UNIT PRICE BID DOLLARS I CTS	TOTAL AMOUNT BID DOLLARS I CTS
131	507	501	12" CAST-IN-PLACE REINFORCED CONCRETE PILES, DRIVEN, AS PER PLAN	53	FT	2,230		
132	507	551	12" CAST-IN-PLACE REINFORCED CONCRETE PILES, FURNISHED, AS PER PLAN	53	FT	2,370		
133	507	601	14" CAST-IN-PLACE REINFORCED CONCRETE PILES, DRIVEN, AS PER PLAN	53	FT	2,790		
134	507	651	14" CAST-IN-PLACE REINFORCED CONCRETE PILES, FURNISHED, AS PER PLAN	53	FT	2,950		
135	507	92201	PREBORED HOLES, AS PER PLAN	53	FT	300		
136	509	10001	EPOXY COATED REINFORCING STEEL, AS PER PLAN	23	LB	132,862		
137	511	33500	SEMI-INTEGRAL DIAPHRAGM GUIDE	21	EACH	2		
138	511	34447	CLASS QC2 CONCRETE WITH QC/QA, BRIDGE DECK, AS PER PLAN	21	CY	351		
139	511	40513	CLASS QC1 CONCRETE WITH QC/QA, PIER ABOVE FOOTINGS, AS PER PLAN	21	CY	276		
140	511	43513	CLASS QC1 CONCRETE WITH QC/QA, ABUTMENT INCLUDING FOOTING, AS PER PLAN	21	CY	132		
141	511	46513	CLASS QC1 CONCRETE WITH QC/QA, FOOTING, AS PER PLAN	21	CY	104		
142	511	51513	CLASS QC2 CONCRETE WITH QC/QA, SIDEWALK, AS PER PLAN	21	CY	69		
143	511	71200	CONCRETE, MISC.: ARCHITECTURAL TREATMENT	38	SF	6,785		
144	512	10050	SEALING OF CONCRETE SURFACES (NON-EPOXY)	57	SY	233		
145	512	33300	TYPE A WATERPROOFING	40	SY	102		
146	512	44400	TYPE B WATERPROOFING	40	SY	15		
147	SPECIAL	51275500	SEALING: ELASTOMERIC PROTECTIVE AND DECORATIVE CONCRETE COATING	57	SY	391		
148	513	10000	STRUCTURAL STEEL MEMBERS, LEVEL UF	24	-	LS		
149	513	10260	STRUCTURAL STEEL MEMBERS, LEVEL 3	21	LB	418,100		
150	513	20000	WELDED STUD SHEAR CONNECTORS	25	EACH	4,230		

REF NO.	ITEM NUMBER	ITEM EXTENSION	ITEM DESCRIPTION	WORK TYPE	UNIT	ESTIMATED QUANTITY	UNIT PRICE BID DOLLARS I CTS	TOTAL AMOUNT BID DOLLARS I CTS
151	514	00800	FIELD PAINTING STRUCTURAL STEEL, INTERMEDIATE COAT	26	LB	418,100		
152	514	00850	FIELD PAINTING STRUCTURAL STEEL, FINISH COAT	26	LB	418,100		
153	516	10010	ARMORLESS PREFORMED JOINT SEAL	27	FT	78		
154	516	13600	1" PREFORMED EXPANSION JOINT FILLER	27	SF	14		
155	516	13900	2" PREFORMED EXPANSION JOINT FILLER	27	SF	156		
156	516	14020	SEMI-INTEGRAL ABUTMENT EXPANSION JOINT SEAL	27	FT	81		
157	516	44101	ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE) (BEARING - 1'-10" X 1'-6 1/2" X 2 13/16", LOAD PLATE - 1'-7 1/2" X 1'-11" X 1 13/16"), AS PER PLAN	27	EACH	12		
158	516	44201	ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE) (BEARING - 1'-2" X 1'-0" X 3 1/8", LOAD PLATE - 1'-3" X 1'-1" X 1 1/2"), AS PER PLAN	27	EACH	12		
159	517	75121	RAILING (CONCRETE PARAPET WITH TWIN STEEL TUBE RAILING), AS PER PLAN	21	FT	582		
160	518	21201	POROUS BACKFILL WITH GEOTEXTILE FABRIC, AS PER PLAN	35	CY	51		
161	518	40000	6" PERFORATED CORRUGATED PLASTIC PIPE	35	FT	104		
162	518	40010	6" NON-PERFORATED CORRUGATED PLASTIC PIPE, INCLUDING SPECIALS	35	FT	60		
163	523	20001	DYNAMIC LOAD TESTING, AS PER PLAN	53	EACH	4		
164	523	20501	RESTRIKE, AS PER PLAN	53	EACH	4		
165	526	25001	REINFORCED CONCRETE APPROACH SLABS (T=15"), AS PER PLAN	38	SY	223		
166	526	90030	TYPE C INSTALLATION	38	FT	78		
167	SPECIAL	53000200	STRUCTURES: PROTECTION OF FACILITIES	NR	-	LS		
168	SPECIAL	53000200	STRUCTURES: PRECONSTRUCTION CONDITION SURVEY	NR	-	LS		
169	SPECIAL	53000200	STRUCTURES: PROPOSED GAS LINE PIPE SLEEVES	NR	-	LS		
170	601	20000	CRUSHED AGGREGATE SLOPE PROTECTION	35	SY	3		

REF NO.	ITEM NUMBER	ITEM EXTENSION	ITEM DESCRIPTION	WORK TYPE	UNIT	ESTIMATED QUANTITY	UNIT PRICE BID DOLLARS	UNIT PRICE BID I CTS	TOTAL AMOUNT BID DOLLARS	TOTAL AMOUNT BID I CTS
171	601	23021	ARTICULATING CONCRETE BLOCK REVETMENT SYSTEM, TYPE 3, AS PER PLAN	35	SY	940				
172	601	34001	ROCK CHANNEL PROTECTION, TYPE A WITHOUT FILTER, AS PER PLAN	35	CY	305				
173	625	33000	STRUCTURE GROUNDING SYSTEM	21	EACH	1				
174	SPECIAL	69098400	CONTRACTOR ACCESS	NR	-	LS				
175	SPECIAL	69098400	WORK INVOLVING ASBESTOS CONTAINING MATERIALS	NR	-	LS				
SECTION TOTAL STRUCTURE OVER 20 FOOT SPAN (OLD ROCKSIDE 00.42 SFN 1876083) :										

REF NO.	ITEM NUMBER	ITEM EXTENSION	ITEM DESCRIPTION	WORK TYPE	UNIT	ESTIMATED QUANTITY	UNIT PRICE BID DOLLARS I CTS	TOTAL AMOUNT BID DOLLARS I CTS
			MAINTENANCE OF TRAFFIC					
176			NOT USED					
177	202	35100	PIPE REMOVED, 24" AND UNDER	NR	FT	95		
178	202	42040	ANCHOR ASSEMBLY REMOVED, TYPE T	NR	EACH	1		
179	202	47000	BRIDGE TERMINAL ASSEMBLY REMOVED	NR	EACH	1		
180	202	38000	GUARDRAIL REMOVED	NR	FT	75		
181	202	58100	CATCH BASIN REMOVED	NR	EACH	2		
182	203	10000	EXCAVATION	04	CY	459		
183	203	20001	EMBANKMENT, AS PER PLAN	04	CY	3,151		
184	204	30020	GRANULAR MATERIAL, TYPE C	04	CY	288		
185	204	51000	GEOGRID	07	SY	362		
186	204	10000	SUBGRADE COMPACTION	04	SY	2,681		
187-189			NOT USED					
190	410	12000	TRAFFIC COMPACTED SURFACE, TYPE A OR B	04	CY	15		
191-192			NOT USED					
193	502	11101	STRUCTURE FOR MAINTAINING TRAFFIC, AS PER PLAN	NR	-	LS		
194	606	15050	GUARDRAIL, TYPE MGS	36	FT	75		
195	606	26500	ANCHOR ASSEMBLY, TYPE T	36	EACH	1		
196	606	35000	BRIDGE TERMINAL ASSEMBLY, TYPE 1	36	EACH	1		
197	611	04401	12" CONDUIT, TYPE B, AS PER PLAN	35	FT	95		
198	611	98471	CATCH BASIN, NO. 2-2B, AS PER PLAN	35	EACH	2		

REF NO.	ITEM NUMBER	ITEM EXTENSION	ITEM DESCRIPTION	WORK TYPE	UNIT	ESTIMATED QUANTITY	UNIT PRICE BID DOLLARS	UNIT PRICE BID I CTS	TOTAL AMOUNT BID DOLLARS	TOTAL AMOUNT BID I CTS
199	614	11110	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	NR	HOUR	40				
200	614	12380	WORK ZONE IMPACT ATTENUATOR, 24" WIDE HAZARDS, (UNIDIRECTIONAL)	39	EACH	7				
201	614	13000	ASPHALT CONCRETE FOR MAINTAINING TRAFFIC	39	CY	20				
202	614	13310	BARRIER REFLECTOR, TYPE 1, BIDIRECTIONAL	39	EACH	30				
203	614	13314	BARRIER REFLECTOR, TYPE 3, BIDIRECTIONAL	39	EACH	6				
204	614	13360	OBJECT MARKER, TWO WAY	39	EACH	30				
205	614	21100	WORK ZONE CENTER LINE, CLASS I, 642 PAINT	39	MILE	0.60				
206	614	21550	WORK ZONE CENTER LINE, CLASS III, 642 PAINT	39	MILE	0.22				
207	614	22100	WORK ZONE EDGE LINE, CLASS I, 4", 642 PAINT	39	MILE	0.40				
208	614	22350	WORK ZONE EDGE LINE, CLASS III, 4", 642 PAINT	39	MILE	0.24				
209	614	24200	WORK ZONE DOTTED LINE, CLASS I, 4", 642 PAINT	39	FT	80				
210	614	26200	WORK ZONE STOP LINE, CLASS I, 642 PAINT	39	FT	100				
211	614	26610	WORK ZONE STOP LINE, CLASS III, 642 PAINT	39	FT	65				
212	614	32200	WORK ZONE RAILROAD SYMBOL MARKING, CLASS I, 642 PAINT	39	EACH	1				
212A	615	10001	ROADS FOR MAINTAINING TRAFFIC, AS PER PLAN	39	-	LS				
212B	615	20001	PAVEMENT FOR MAINTAINING TRAFFIC, CLASS A, AS PER PLAN	39	SY	1,741				
212C	615	25001	PAVEMENT FOR MAINTAINING TRAFFIC, CLASS B, AS PER PLAN	39	SY	634				
213	616	10000	WATER	NR	MGAL	12				
214	616	20000	CALCIUM CHLORIDE	NR	TON	1.2				
215	622	41100	PORTABLE BARRIER, UNANCHORED	39	FT	561				
216	659	10001	SEEDING AND MULCHING, AS PER PLAN	08	SY	1,638				

REF NO.	ITEM NUMBER	ITEM EXTENSION	ITEM DESCRIPTION	WORK TYPE	UNIT	ESTIMATED QUANTITY	UNIT PRICE BID DOLLARS I CTS	TOTAL AMOUNT BID DOLLARS I CTS
217	659	14000	REPAIR SEEDING AND MULCHING	08	SY	90		
218	659	35000	WATER	08	MGAL	11		
219	659	40000	MOWING	08	MSF	15.5		
220	670	00520	SLOPE EROSION PROTECTION MAT, TYPE B	35	SY	1,595		
SECTION TOTAL MAINTENANCE OF TRAFFIC :								
			INCIDENTALS					
221	614	11001	MAINTAINING TRAFFIC, AS PER PLAN	39	-	LS		
222	619	16021	FIELD OFFICE, TYPE C, AS PER PLAN	NR	MNTH	22		
223	623	10001	CONSTRUCTION LAYOUT STAKES AND SURVEYING, AS PER PLAN	NR	-	LS		
224	624	10000	MOBILIZATION	NR	-	LS		
225	SPECIAL	69098400	PROJECT DVD RECORDING (SEE PROPOSAL NOTE)	NR	-	LS		
226	SPECIAL	10810000	CPM PROGRESS SCHEDULE (SEE PROPOSAL NOTE)	NR	-	LS		
SECTION TOTAL INCIDENTALS :								
GENERAL CONTINGENCY FOR UNFORESEEN CONDITIONS (100% LOCAL):								**$ 400,000.00**
GRAND TOTAL BID :								