FED. RD. DIVISION	STATE	PROJECT	
2	OHIO	S-712(9)	

1/51

HANCOCK COUNTY
HAN-69-(1.14)(1.97)(2.31)(3.28)(4.23)(6.17)



DETOUR MAP
0 1 2 3 4 5 6
Scale in Miles

MICROFILMED
OCT 11 1976
REPRODUCTION

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
HAN-69-(1.14)(1.97)(2.31)(3.28)(4.23)(6.17)
HANCOCK COUNTY
ORANGE & UNION TOWNSHIPS

S-712(9)

MICROFILMED
JUL 15 1986

DESIGN DESIGNATION

CURRENT A. D. T. (1966 Est) (750)
DESIGN YEAR A.D.T. (1986) (940)
D. H. V. (95)
D. (60%)
T. (10%)
V. 50 M.P. H.

CONVENTIONAL SIGNS

County Line
Township Line
Section Line
Center Line
Property Line
Fence
Guard Rail (Existing)
Guard Rail (Proposed)
Power Poles
Telephone Poles
Trees and Stumps (Existing)
Trees and Stumps (To be removed)
Railroad
Right-of-Way — R/W

INDEX OF SHEETS

Title Sheet	1					
Typical Sections	2					
General Notes & Details	3 & 3A					
Summary	4					
Plan & Profile	5	9	14	18	23	27
Cross Sections	6-7	10-11	15-16	19-20	24-25	28-29
Channel Sections	8	12	17	21-22		
Intersections		13				
Structures 20' span & under					26	
Structures over 20' span	30-46					
Right-of-way	47-51					

Sheet Nos. 31, 34, 38 and 44 Rev. 4-16-70 -GFJ

LINE DATA

Begin Project, Sta. 60+00; Suspend Project, Sta. 69+25	PART-I	925	Lin.Ft.
Resume Project, Sta. 104+25; Suspend Project, Sta. 112+00	PART-II	775	Lin.Ft.
Resume Project, Sta. 121+75; Suspend Project, Sta. 131+50	PART-III	975	Lin.Ft.
Resume Project, Sta. 173+00; Suspend Project, Sta. 182+25	PART-IV	925	Lin.Ft.
Resume Project, Sta. 223+50; Suspend Project, Sta. 231+33	PART-V	783	Lin.Ft.
Resume Project, Sta. 326+00; End Project, Sta. 331+00	PART-VI	500	Lin.Ft.
Net length of Project		4,883	Lin.Ft. = 0.924 Mi.

Net length of Work equals Net length of Project.



SCALE IN MILES

0 1 2 3 4 5

LOCATION MAP

Portion to be improved
State Highways
Other Roads
Detour Route

SCALE

Plan 0 50 100
Profile (Horizontal) 0 50 100
Profile (Vertical) 0 5 10
Cross Sections 0 5 10

1967 SPECIFICATIONS

The Standard Specifications of the State of Ohio Department of Highways, including changes and supplemental specification listed in the proposal shall govern this improvement.

The Right-of-Way for this improvement will be provided by the State of Ohio.

I hereby approve these plans and declare that the making of this improvement will require the closing to traffic of the highway, except as noted on sheet 3, and that detours will be provided as indicated on the plans.

Approved Norman R Penn
Date 5-10-67 Division Deputy Director

Approved C. H. Albrecht
Date 12-5-67 Engineer of Bridges

Approved R. E. Lattle
Date 12-6-67 Engineer of Location and Design

Approved R. E. Hult
Date 12-7-67 Deputy Director of Design and Construction

Approved T M Boone
Date 12-21-67 Deputy Director of Right-of-Way

No RR, HBV 7 12-5-67

Approved Thomas M. Major
Date 12-21-67 Deputy Director of Planning and Programming

Approved E. W. Wilson
Date 12-21-67 First Assistant Director

Approved P. E. Masters
Date 12-21-67 Director of Highways

File No.	Hancock County HAM-69-(1.14)(1.97)(2.31)(3.28)(4.23)(6.17)
	Date of Letting 19
	Contract No.

STANDARD DRAWINGS

AS-1-54	8-10-65	MC-1	10-1-67	P-1-54	11-8-65
BP-5	6-1-65	MC-3	5-1-66	CS-1-65	6-1-65
BP-6	6-1-65	MC-4	6-1-65	SB-1-64 (Sh. 1 & 2)	11-8-65
CB-2-2-A&B	6-1-65	SP-53	6-30-61		
GR-1	1-1-67	FACI-1	9-15-67	BP-3	1-10-67
GR-2A	1-1-67	FACI-2	6-1-65		
L-1	6-1-65	A-1-54	11-8-65		

SUPPLEMENTAL SPECIFICATIONS

808	1-13-67
825	1-1-67
1001	3-21-66

Quantities Checked By	Date
W. E. S.	5-X-67

DEPARTMENT OF TRANSPORTATION
FEDERAL HIGHWAY ADMINISTRATION
BUREAU OF PUBLIC ROADS
APPROVED:

DIVISION ENGINEER DATE

FED. RD. DIVISION	STATE	PROJECT	
2	OHIO		

2
51

HANCOCK COUNTY
HAN-69-(1.14)(1.97)(2.31)(3.28)(4.23)(6.17)

TYPICAL SECTIONS

TYPE 4.04



Typical Section at left applies:

Part I

Sta. 62+00 to Sta. 63+38.24	=	138.24 Lin. Ft.
Sta. 64+41.76 to Sta. 67+20	=	278.24 Lin. Ft.

Part II

Sta. 105+60 to Sta. 107+47.69	=	187.69 Lin. Ft.
Sta. 108+20.31 to Sta. 109+75	=	154.69 Lin. Ft.
Total	=	758.86 Lin. Ft.



Typical Section at left applies:

Part I

Sta. 60+00 to Sta. 62+00	=	200 Lin. Ft.
Sta. 67+20 to Sta. 69+25	=	205 Lin. Ft.

Part II

Sta. 104+25 to Sta. 105+60	=	135 Lin. Ft.
Sta. 109+75 to Sta. 112+00	=	225 Lin. Ft.

Part III

Sta. 121+75 to Sta. 124+84.75	=	309.75 Lin. Ft.
Sta. 125+61.25 to Sta. 131+50	=	588.75 Lin. Ft.

Part IV

Sta. 173+00 to Sta. 177+04.99	=	404.99 Lin. Ft.
Sta. 178+41.01 to Sta. 182+25	=	383.99 Lin. Ft.

Part V

Sta. 223+50 to Sta. 231+33	=	783 Lin. Ft.

Part VI

Sta. 326+00 to Sta. 328+15.25	=	215.25 Lin. Ft.
Sta. 328+89.75 to Sta. 331+00	=	210.25 Lin. Ft.
Total	=	3660.98 Lin. Ft.

(1) Item 404 1 1/4" Asphalt Concrete (85-100).

(2) Item 402 1 3/4" Asphalt Concrete (85-100).

(3) Item 408 Bituminous Prime Coat using 702.09 RT-2 or RT-3 applied at the rate of 0.40 Gal. per Sq. Yd.

(4) Item 407 Tack Coat 702.04 MS-2 or .25-1 or 702.02 RC-70 or RC-250 applied at the rate of 0.10 Gal. per Sq. Yd.

(5) Item 304 5" Aggregate Base.

(6) Item 310 5" Subbase.

(7) Item 605 Aggregate Drains. See General Notes.

(8) Item 659 Seeding and Mulching.



DETAIL "M"

LONGITUDINAL TRANSITION SALVAGE TO NEW PAVEMENT

FED. RD. DIVISION	STATE	PROJECT	
2	OHIO	S-712(9)	

3/51

HANCOCK COUNTY
HAN-69-(1.14)(1.97)(2.31)(3.28)(4.23)(6.17)

GENERAL NOTES

ROUNDING OF CORNERS SHOWN ON CROSS SECTIONS ~ The rounded corners shown on Standard Drawing MC-1, apply to all cross sections, even though otherwise shown on these plans.

FIELD OFFICE ~ The contractor shall, in addition to the requirements of 105.15C, provide a suitable field office having a minimum of 300 sq. ft. of floor space. The contractor shall have a telephone installed and maintained in this office during the construction of this project. The contractor shall also provide and maintain sanitary provisions as per 107.06. All the above is included in the lump sum price bid for the field office.

ELEVATION DATUM ~ All elevations refer to U.S.G.S. datum.

CONNECTIONS TO EXISTING PIPE ~ At places where the plans provide for proposed pipe to be connected to existing pipe, it shall be the responsibility of the contractor to locate the existing pipe both as to line and grade before he starts to lay the proposed pipe. The cost of this operation shall be included in the unit price bid for the pertinent 603 conduit item.

ITEM 604 ~ All Standard 2-2A Catch Basins designated in these plans shall be built with a 12" sump.

EROSION CONTROL ~ Items 601 and 660 are provided in these plans for erosion control. The Engineer will check and non-perform or adjust locations and quantities for these items where indicated by field conditions during construction.

REMOVAL OF TREES AND STUMPS ~ All trees and stumps specifically marked for removal within the construction limits of this project shall be removed under the lump sum price bid for the Item 201 Clearing and Grubbing, except those trees and stumps designated by the Engineer to be preserved.

The following is an approximate estimate of the number of trees and stumps to be removed.

Sizes	No. of Trees						No. of Stumps					
	Part I	Part II	Part III	Part IV	Part V	Part VI	Part I	Part II	Part III	Part IV	Part V	Part VI
18"		2							1			
30"												
48"												

The above estimate is approximate and the State of Ohio reserves the right to order the removal of additional trees or stumps outside of the limits of construction but within the right-of-way and/or easement lines. Payment for the removal of these additional trees or stumps shall be included in the lump sum price bid for Item 201 Clearing and Grubbing.

SEEDING ~ Quantities for seeding are calculated for the soil areas between the work limits as shown on the cross sections.

SEEDING FORMULA ~ The following seed mixture shall, in lieu of the mixtures listed in 659.09 be used throughout the limits of this project.

60% Kentucky Blue Grass
25% Chewings Fescue
15% Red Top

Any stone or other debris 2" or greater in dimension shall be removed from the exposed surface of the seed bed.

DRIVEWAYS ~ All driveways shown on these plans shall be Type 1 Standard Drawing BP-6, modified by deleting the 12" offset at the edge of pavement. Field drives shall be 6", Item 304.

DETOUR LIMITATION ~ Two-way traffic shall be maintained at all times, except that for a period not to exceed 180 consecutive calendar days, through traffic may be detoured as shown on sheet No. 1. An Estimated Quantity of ten(10) C.Y. of Item 410-Traffic Compacted Surface has been carried to the General Summary to be used for maintaining traffic, As directed by the Engineer.

CONSTRUCTION LAYOUT STAKES ~ See note in the proposal describing the work included in this lump sum.

ITEM 605 AGGREGATE DRAINS ~ Aggregate drains shall be placed at fifty (50) foot intervals on each side of normal crowned sections, or as directed by the Engineer.

FEDERAL AID CONSTRUCTION IDENTIFICATION SIGNS ~ The contractor shall furnish, erect, maintain and subsequently remove Federal Aid Construction Identification Signs at each of the following approximate locations:

1. Sta. 60+00 (Right)
2. Sta. 331+00 (Left)

Sign Details shall be as specified on FACI Code N-54(1)96(2). The signs shall be erected in accordance with Standard Drawing FACI-2. Additional requirements shall be in accordance with notes in the proposal.

ESTIMATED QUANTITIES:

Specific locations and usage of estimated quantities set up on this plan to be used "as directed by the Engineer" shall be made a matter of record by incorporation into the final change order governing completion of this project.

GUARD RAIL MODIFIED AS PER PLAN: (See Detail on Sheet 3A)
Post spacing for all Type 4 guard rail shall be at 6'-3" intervals with Spacer blocks attached between the posts and rail element.
Type 4 guard rail shall be constructed with the new guard rail approach end assemblies on both ends, except when one end is adjacent to or continues across a bridge.
Type 4 guard rail with post spacing at 6'-3", spacer blocks, and new approach end assemblies will be paid for as 606 Guard Rail, Type 4 Modified as per plan, complete in place.

ADJUSTING GUARD RAIL LOCATIONS:
Prior to staking the guard rail, the Engineer shall make a field inspection and, if necessary, adjust the stations of the end posts to accommodate field conditions and to provide better protection for traffic.

DETAIL OF SODDING AT CATCH BASINS

AREA 16 SQ. YDS.





SECTION A-A



SECTION B-B

FED RD DIVISION	STATE	PROJECT	
2	OHIO		

3-A 51

APPROACH END ASSEMBLY
6 B 8.5 Steel posts only.



SINGLE RAIL ~ PLAN VIEW



SINGLE & BARRIER RAIL ~ ELEVATION



BARRIER RAIL ~ PLAN VIEW



POST A



All steel spacers and posts may be provided with additional holes so that these items will not be required to be made right and left handed.

POST B



POST C



Provide 4 additional shop holes in end of rail element for attachment to terminal anchor.

Top of rail element shall be flush with existing ground line.

POST D



All wood posts and wood spacer blocks shall be pressure treated as per 710.14.

POST E

* Tops of driven posts need not be trimmed.

NOTES

For details not shown, see Standard Drawings GR-1 and GR-2A.

All steel parts shall be galvanized in accordance with ASTM A123, A153 or A525, whichever may apply.

This drawing shall govern where a conflict arises.



POST BOLT WASHERS



POST BOLT: Same except for length.

SPLICE BOLT & NUT





TERMINAL ANCHOR DETAIL



METHOD 1 METHOD 2

ROUND WOOD POSTS *

Alternate methods of placing the spacer blocks on the round posts may be submitted for consideration and approval by the Engineer.

* Tops of driven posts need not be trimmed.

GUARD RAIL ~ APPROACH END ASSEMBLY

Rev. 8-28-67

FED. RD. DIVISION	STATE	PROJECT	
2	OHIO		

4
51

HANCOCK COUNTY
HAN-69-(1.14)(1.97)(2.31)(3.28)(4.23)(6.17)

PAVEMENT COMPUTATIONS

Station From	Station To	Lin. Ft.		404 1¼" Asphalt Concrete Cu. Yds.	402 1¾" Asphalt Concrete Cu. Yds.	407 Tack Coat Gals.	408 Bituminous Prime Coat Gals.	408 Cover Aggregate Cu. Yds.	304 Aggregate Base Cu. Yds.	310 Subbase Cu. Yds.	611 Reinforced Concrete Approach Slabs Sq. Yds.	203 Subgrade Preparation Sq. Yds.	202 Existing Pavement Removed & Disposed of (Four Sides) Sq. Yds.
Bridge No. 0121 Part I													
60+00	62+00	200.00	Salvage	14.16	14.91	17	1.17	1.17	35.46	17.05			
62+00	63+38.24	138.24	New	10.67	14.93		1.29	1.29	44.80	46.93		307	
63+38.24	64+41.76	103.52	Br&Appr.							19.15	111	98	40
64+41.76	67+20	278.24	New	21.47	30.06		2.60	2.60	90.17	94.46		618	
67+20	69+25	205.00	Salvage	13.76	15.02	17	1.21	1.21	33.28	20.09			
From Sheet No. 5									10.30				
Total Part I		925.00		60.06	74.92	34	6.27	6.27	214.01	197.68	111	1023	40
Bridge No. 0204 Part II													
104+25	105+60	135.00	Salvage	10.75	11.00	11	0.79	0.79	27.40	18.88			
105+60	107+47.69	187.69	New	14.48	20.28		1.75	1.75	60.83	63.72		417	
107+47.69	108+20.31	72.62	Br&Appr.							19.15	111	98	44
108+20.31	109+75	154.69	New	11.94	16.71		1.44	1.44	50.13	52.52		344	
109+75	112+00	225.00	Salvage	16.77	17.12	22	1.17	1.17	37.35	23.39			
Intersection No. 1-P				23.87	31.02	9	2.48	2.48	91.00	88.58		613	
From Sheet No. 9									9.10				
Total Part II		775.00		77.81	96.13	42	7.63	7.63	275.81	266.24	111	1472	44
Bridge No. 0237 Part III													
121+75	124+84.75	309.75	Salvage	24.62	28.59	22	1.96	1.96	73.33	50.06			
124+84.75	125+61.25	76.50	Br&Appr.							19.15	111		44
125+61.25	131+50	588.75	Salvage	46.45	57.43	22	4.56	4.56	139.58	121.76			
From Sheet No. 14									11.30				
Total Part III		975.00		71.07	86.02	44	6.52	6.52	224.21	190.97	111		44
Bridge No. 0336 Part IV													
173+00	177+04.99	404.99	Salvage	30.09	33.46	33	2.38	2.38	83.02	77.24			
177+04.99	178+41.01	136.02	Br&Appr.							19.15	111		62
178+41.01	182+25	383.99	Salvage	29.94	35.76	17	2.88	2.88	91.86	67.10			
From Sheet No. 18									30.90				
Total Part IV		925.00		60.03	69.22	50	5.26	5.26	205.78	163.49	111		62
Structure No. 0430 Part V													
223+50	231+33	783.00	Salvage	62.18	70.95	74	4.20	4.20	143.15	*72.04			44
From Sheet No. 23									30.90				
Total Part V				62.18	70.95	74	4.20	4.20	174.05	*72.04			44
Bridge No. 0622 Part VI													
326+00	328+15.25	215.25	Salvage	14.08	24.59	48							
328+15.25	328+89.75	74.50	Br&Appr.							19.15	111		40
328+89.75	331+00	210.25	Salvage	13.41	23.87	47							
Total Part VI		500.00		27.49	48.46	95				19.15	111		40
Grand Total				358.64	445.70	339	29.88	29.88	1093.86	909.57	555	2495	274

* Includes pavt. replacement for pipe crossover

MISCELLANEOUS COMPUTATIONS

	Part I	Part II	Part III	Part IV	Part V	Part VI
Seeding and Mulching						
From Table,	5040	4993	5380	4787	4377	2458
Deduct 660 Sodding	43		16	32	127	20
Deduct 601 Dumped Rock Channel Protection	42	42	42	44	62	52
Net Seeding, Sq. Yds.	4955	4951	5322	4711	4188	2386
Item 659 Comm. Fertilizer, 12-12-12						
Seeding and Mulching	4955	4951	5322	4711	4188	2386
660 Sodding	43		16	32	127	20
Quantity - 5Y. x 9 x 20 ÷ 1000 ÷ 2000	$\frac{4998 \times 9 \times 20}{2000000}$ = .450	$\frac{4951 \times 9 \times 20}{2000000}$ = .446	$\frac{5338 \times 9 \times 20}{2000000}$ = .480	$\frac{4743 \times 9 \times 20}{2000000}$ = .427	$\frac{4315 \times 9 \times 20}{2000000}$ = .388	$\frac{2406 \times 9 \times 20}{2000000}$ = .217
Item 605 Aggregate Drains						
Number of Drains	28	27	34	28	23	11
Average Length (est)	11.5	11.5	11.5	11.5	11.5	11.5
Quantity, Lin. Ft.	322	311	391	322	265	127

GENERAL SUMMARY

Item	6201 (* Exceptions as noted) Part I	Part II	Part III	Part IV	Part V	Part VI	Total	Unit	Description
									ROADWAY
201	Lump	Lump	Lump	Lump	Lump	Lump	Lump	Lump	Clearing and Grubbing
202					Lump		Lump	Lump	Existing Structures removed
202	4	3	2	1	2		12	Each	Catch Basin and Inlet removed
203	669	672	737	973	358	493	3902	Cu. Yd.	Excavation not including Embankment Construction
203	1234	1543	1201	767	471	196	5412	Cu. Yd.	Embankment
203	1023	1472					2495	Sq. Yd	Subgrade Preparation
606	705.46	604.76	497.00	352.96	637.50	551.00	3348.68	Lin. Ft.	Guard Rail, Type 4, modified as per plan
202	40	44	44	62	44	40	274	Sq. Yd	Pavement removed and disposed of
410							10	Cu. Yd.	Traffic Compacted Surface, Type A or B
									EROSION CONTROL
*659	4955	4951	5322	4711	4188	2386	26513	Sq. Yd	Seeding and Mulching, as per plan
*601	21	21	21	22	47	26	158	Cu. Yd	Dumped Rock Channel Protection
*660	43		16	32	127	20	238	Sq. Yd.	Sodding
*659	0.45	0.45	0.48	0.43	0.39	0.22	2.42	Ton	Commercial Fertilizer (12-12-12)
									DRAINAGE
603			10		10		20	Lin. Ft.	6" Conduit, Type F
603	10	20		50	24	10	114	Lin. Ft.	8" Conduit, Type F
603	32		45		18	10	105	Lin. Ft.	10" Conduit, Type F
603	26	40	10		10		86	Lin. Ft.	12" Conduit, Type F
603						10	10	Lin. Ft.	18" Conduit, Type F
603						10	10	Lin. Ft.	24" Conduit, Type F
603						10	10	Lin. Ft.	6" Conduit, Type E
603				6	38	38	82	Lin. Ft.	8" Conduit, Type E
603	28					50	78	Lin. Ft.	10" Conduit, Type E
603	12		18		22		52	Lin. Ft.	12" Conduit, Type E
603									
603						58	58	Lin. Ft.	24" Conduit, Type E
603	28		62	90	28		208	Lin. Ft.	12" Conduit, Type D
603		12					12	Lin. Ft.	8" Conduit, Type B with Class B Bedding
603		35					35	Lin. Ft.	12" Conduit, Type B with Class B Bedding
603					72		72	Lin. Ft.	8'-7" x 5'-11" Conduit, Type A with Class B Bedding, 707.03, 10-10 Gage
604	1	2	1		2		6	Each	Std. 2-2A Catch Basin, Modified as per plan
602					7.3		7.3	Cu. Yd	Concrete Masonry
605	322	311	391	322	265	127	1738	Lin. Ft.	Aggregate Drains
									PAVEMENT
310	198	266	191	164	72	19	910	Cu. Yds.	Subbase
304	214	276	224	206	174		1094	Cu. Yds.	Aggregate Base
408	627	763	652	526	420		2988	Gals.	Bituminous Prime Coat, 702.09 RT-2 or RT-3
408	6	8	7	5	4		30	Cu. Yds.	Cover Aggregate
407	34	42	44	50	74	95	339	Gals.	Tack Coat, 702.04 MS-2 or RS-1; 702.02 RC-70 or RC-250
402	75	96	86	69	71	49	446	Cu. Yds.	Asphalt Concrete (85-100)
404	60	78	71	60	62	28	359	Cu. Yds.	Asphalt Concrete (85-100)
611	111	111	111	111		111	555	Sq. Yds.	Reinforced Concrete Approach Slabs (T=13")
614	Lump	Lump	Lump	Lump	Lump	Lump	Lump	Lump	Maintaining Traffic
	Lump	Lump	Lump	Lump	Lump	Lump	Lump	Lump	Construction Layout Stakes
								Lump	Field Office
									STRUCTURES 20' SPAN AND OVER
									Han-69-0121, See Sheet No. 31
									Han-69-0204, See Sheet No. 34
									Han-69-0237, See Sheet No. 38
									Han-69-0336, See Sheet No. 41
									Han-69-0622, See Sheet No. 44

* Code No. Y005

EARTHWORK-203

Sheet No.	Part No.	Embankment, C.Y.	Excavation, C.Y.
5	I	1234	669
9	II	1543	672
14	III	1201	737
18	IV	767	973
23	V	471	358
27	VI	196	493
Totals		5412	3902

SEEDING-659

Sheet No.	Part No.	Sq. Yds.
6	I	5040
10	II	4993
15	III	5380
19	IV	4787
24	V	4377
28	VI	2458
Total		27035

PAVEMENT COMPUTATIONS, GENERAL SUMMARY & MISCELLANEOUS COMPUTATIONS

FED. RD. DIVISION	STATE	PROJECT		5
2	OHIO			51

HANCOCK COUNTY
HAN-69-(1.14)(1.97)(2.31)(3.28)(4.23)(6.17)

(Br. 0121)



EXISTING STRUCTURE
Span ~ 23'-0"
Type ~ Concrete Slab
Roadway ~ 24'-0"
Skew ~ None
Loading ~ CF 130

PROPOSED STRUCTURE
Type ~ Continuous Reinf. Conc. Slab with capped pile substructure
Spans ~ 16'-20'-16' 9" Bearings
Roadway ~ 36'-0" c/c Guardrail
Load Frequency ~ CF-130(5T)
Skew ~ 10° R.F.
Wearing Surface ~ 1" Monolithic Concrete
Approach Slabs ~ AS-1-54 (25' Long)
Alignment ~ Tangent



UTILITIES
Paulding Putnam Electric Co-op Inc.
General Telephone Co. Marion, Ohio



B.M. "X" in Top of S.W. abutment
Str. HAN-69-0121 Elev. 905.06

ROADWAY DRAINAGE "D"

Ref. No.	Station From	Station To	Side	601 Dumped Rock Channel Pad 18" Thick Cu. Yd.	660 Sodding Sq. Yd.	603 Conduit Lin. Ft. F 8"	F 12"	E 10"	E 10"	E 8"	E 12"	202 C.B.s & Inlets Removed Each	604 Catch Basin Std. 2-2-A (Mod.) Each	602	Bends & Branches Each
1-D	63+60	63+78	Lt.	5.2			16								1
2-D	63+72	63+90	Rt.	5.2			10								1
3-D	63+98	64+52	Lt.	5.2	27			16							1
4-D	64+02	64+24	Rt.	5.2		10		16							1
5-D	66+23	66+34	Lt.		16				22			1	1		2
6-D	66+29		Rt.						6			1			
7-D	63+22		Rt.								6	1			
8-D	63+20		Lt.								6	1			
Totals				20.8	43	10	26	32	28		12	4	1		

GUARD RAIL "G"

Ref. No.	Station From	Station To	Side	606 Guard Rail Type 4 Lin. Ft. Straight
1-G	61+93.22 *	66+05.72	Lt.	358.98
2-G	61+99.28 *	65+99.28	Rt.	346.48
Totals				705.46

*Deduct 53.52' for Bridge Rail

MICROFILMED JUL 15 1986

SIDE APPROACHES "A"

Item No.	Station	Side	304 Aggr. Base Cu. yd.	Conduit Type "D" Lin. Ft. 12"			Length Lin. Ft.	Remarks
1-A	66+26	Rt.	*10.3	28				Field Drive
Total			10.3	28				

*Place 304 Aggregate to 25' Length (Back of Radius)



Excavation 669 Cu. yds.
Embankment 1234 Cu. yds.

10 Yr. Hi-Water Elev. _____ 903.0
54 Yr. Hi-Water Elev. _____ 902.0
Flow Line Elev. _____ 896.4
Highest Known Hi-Water Elev. ___ 904.9

Sta. 58+00 to Sta. 69+00

PART-I


STRUCTURE NO. HAN-69-0121
Seeding Wide
Sq. Yd.
End Area Cut
End Area Fill
Cu. Yd. Cut
Cu. Yd. Fill
45 40 35 30 25 20 15 10 5 ℄ 5 10 15 20 25 30 35 40 45
R|W 60
162'
2:1
9012
906.50
63+62.48
904.75
Back of Abutment
Skew
2:1
900.8
5 12"F.T.
Add for Roadway Ditches Ahead
Back
9 63
R|W 13
9 50
R|W 60
265'
3:1
901.7
Back
Ahead
906.50
63+38.24
904.75
Begin Approach Slab
3:1
901.0
5 12"F.T.
Ahead 12 48
Back 12 59
R|W
13 88
R|W 65
667'
Sta. 63+20.24' Lt.
10" Dia. Inlet (Exist.)
Remove (202) Conn. Thru.
4:1
901.8
906.50
63+00
904.74
4:1
901.7
5 12"F.T.
Transition from 4:1 Slope @ Sta. 63+00 Rt. & Lt.
to 2:1 Slope @ Sta. 63+60 Rt. & Lt.
Sta. 63+22.24' Rt.
10" Dia. Inlet (Exist.)
Remove (202) Conn. Thru.
R|W
7 65
24 172
R|W
55'
903.5
906.50
62+00 Begin New Pavement
905.25
902.9
5 12"F.T.
R|W
6 28
528'
Transition from 10' Shoulder width @ Sta. 62+00 Rt. & Lt.
to 8' Shoulder width @ Sta. 61+75 Rt. & Lt.
19 63
R|W
40'
904.5
906.58
61+00
906.19
R|W
904.9
5 12"F.T.
4 6
222'
7 11
Exist. R/W
0'
Exist. R/W
0 0
60+00
907.24
Begin Work & Project
Sta. 60+00
59+45 Drive Rt.
907.72
59+00
907.93
Total Sheet #6 85 384
" " #7 141 705
" " #8 443 65
Total Part I 669 1234
58+50 Drive Rt.
908.04
Sta. 58+00 to Sta. 63+87
1844 Total Sheet #6
3196 " " #
58+00
908.14
5040 Total Part I
45 40 35 30 25 20 15 10 5 ℄ 5 10 15 20 25 30 35 40 45
HANCOCK COUNTY
HAN-69-11.11/11.97 21.23/23.28 W&I 23 (6.10)
FED. RD. DIVISION 2
STATE OHIO
PROJECT
SHEET 6


45 40 35 30 25 20 15 10 5 ℄ 5 10 15 20 25 30 35 40 45
Seeding
Wide Sq. Yd.
End Area
Cut Fill
Cu. Yd.
Cut Fill
Sta. 69+25, Suspend Project and Work
Exist. R/W
Sta. 69+25
69+00
907.24
Sta. 67+20, Begin Salvage
8' F.T.
903.5
906.50
67+00
905.12
10' F.T.
903.1
Sta. 66+34.31' Lt.
Std. C-2A' C.B. (Mod)
F.L.Elev. 902.50
10'(E) Back
10'(E) Ahead
2'x2' C.B.
10' F.T.
8' F.T.
+34 Lt.
904.77
906.50
66+42 Rt.
904.80
+39.8 Inlet 902.58
(Rem. & Conn. thru) 202
10' F.T.
Corr. For Dr. Rt.
Field Drive Rt.
10%
8' C.M.P. (Aban)
12'(D)
10' F.T.
906.50
66+26
904.74
902.3
10' F.T.
906.50
66+00
904.66
902.2
10' F.T.
4:1
901.5
10' F.T.
906.50
65+00
904.65
901.3
10' F.T.
Transition from 10' Shoulder width @ Sta. 66+00, Rt. & Lt.
to 8' Shoulder width @ Sta. 66+25 Rt. & Lt.
Transition from 2:1 Slope @ Sta. 64+20, Rt. & Lt.
to 4:1 Slope @ Sta. 65+00, Rt. & Lt.
Sta. 64+41.76 Ahead
Back
Ahead Sta. 64+17.52
Carried to Sheet No. 6
Sheet Total
End Sod, Sta. 64+52, Lt.
2.5:1
901.4
10' F.T.
Ahead
Back
906.50
64+41.76
904.73
End Approach Slab
2.5:1
900.76
10' F.T.
2:1
899.7
10' F.T.
906.50
64+17.52
904.82
Back of Abutment
Skew
2:1
900.1
10' F.T.
63+62.48
Begin Sod, Sta. 64+12, Lt.
Sheet Total
Sta. 64+13 to Sta. 69+00
HANCOCK COUNTY
HAN-69-11.00/15.52/16.71
SHEET NO. 5
TOTAL SHEETS 7

Seeding	
Wide	Sq. Yd.

End Area		Cu. Yd.	
Cut	Fill	Cut	Fill

5+00
902.21

Sta. 4+00 — 0 — 0

4+00
901.71

60 — 0

3+26 Ahead — 44 — 0
3+26 Back — 44 — 28

Back Only

3+26
901.21

43 — 11

895.10

Face of Abut.

Face of Abut.

156 — 22

3+14
904.01

895.15

172 — 35

Deduct for 202 Rem. of Exist. Structure — -40

Face of Abut.

Face of Abut.

175 — 46

2+86
904.16

53 — 12

895.20

Included in Roadway Sections

83 — 15

2+75
902.36

55* — 7

895.25

* Corrected for Deflection in Base Line

93 — 0

2+50
901.76

*90 — 0

895.30

25 — 0

2+00
901.56

10 — 0

895.35

Sta. 1+78 — 0 — 0

1+00
901.56

Carried to Sheet #6

Sheet Totals — 443 — 65

Channel Sections Sta 1+00 to Sta 5+00 Broken Back



Channel Alignment

HANCOCK COUNTY
HAN-69-11.23/11.60
OHIO
STATE
PROJECT

51

HANCOCK COUNTY
HAN-69-(1.14)(1.97)(2.31)(3.28)(4.23)(6.17)
(Br. 0204)

MICROFILMED
JUL 15 1986



ROADWAY DRAINAGE "D"

Ref. No.	Station From	Station To	Side	Bends & Branches Each	Catch Basins (Mod.) 204 Each	Catch Basins Removed 202 Each	Conduit Lin. Ft. 603 B 12"	Conduit Lin. Ft. 603 F 8"	Conduit Lin. Ft. 603 F 12"	Conduit Lin. Ft. 603 F 18"	Sodding 660 Sq. Yd.	Dump Rock Chan. Prot. 18" Thick 601 Cu. Yd.
1-D	105+48	105+58	Rt.		1	1	15	6				5.2
2-D	105+50	105+61	Lt.		1	1	14	6				5.2
3-D	106+05	107+88	Rt.						20			5.2
4-D	107+65	107+42	Lt.						20			5.2
5-D	107+80	107+94	Lt.							20		5.2
6-D	108+08	108+21	Rt.		1	1				20		5.2
7-D				1								
Totals				1	3	3	29	12	40	40	35	20.8

SIDE APPROACHES "A"

Ref. No.	Station From	Station To	Side	204 Aggr. Base Co. Rd.	Conduit Type D Lin. Ft.	Length Lin. Ft.	Remarks
1-A	99+29 Fld. Dr. Reloc.		Lt.	9.1		20	Field Drive
Totals				9.1			

GUARD RAIL "G"

Ref. No.	Station From	Station To	Side	606 Guard Rail Type 4 Lin. Ft. Straight
1-G	106+34.55	109+59.55*	Lt.	302.38
2-G	106+33.45	109+58.45*	Rt.	302.38
Totals				604.76

*Deduct 22.62' For Bridge

Sta. 102+00 to Sta. 114+00 PART-II

45 40 35 30 25 20 15 10 5 ℄ 5 10 15 20 25 30 35 40 45

Seeding Wide	Sq. Yd.	End Area Cut	End Area Fill	Cu. Yd. Cut	Cu. Yd. Fill
R/W 55'	67	4	68		
	500			16	75
	520			35	163
R/W 70'	50	20	42		
R/W 67'	340			31	61
	74			4	0
R/W 52'		8	13		
	202			10	17
	0	0	0		
Sheet No. 10				96	316
Sheet No. 11				195	1216
Sheet No. 12				381	11
Total Part II		Sheet Total		672	1543
Sta. 101+00 to Sta. 108+40					
1488 Sheet No. 10					
3505 Sheet No. 11					
4993'	Total Part II				

Correction for Intersection

Correction for Intersection

887.12
106+40
885.56

887.27
106+05
885.72

887.30
106+00
885.78

INTERSECTION 1-P

Sta. 105+81.45, 5 R @ 9 =
Sta. 100+00, Twp. Rd. 27

Prop. Grade Twp. Rd. #27

887.43
105+81.45 Twp. Rd. #27
886.01

Sta. 105+50, 34' Lt.
Std. 2-2A, C.B. (Mod)
F.L. Elev. 885.00

Sta. 105+48.36' Rt.
Std. 2-2A, C.B. (Mod)
F.L. Elev. 885.00

Sta. 105+60, Begin New Pavt.

Sta. 105+51.35' Lt.
885.00

12"x14"(B)

5 Remove (202) connect Thru.

887.61 Lt. +61 105+58 Rt. 887.64
886.38

Remove (202) connect Thru.

12"x15"(B)

Sta. 102+49.36' Rt.
885.40

885.2

887.75
105+47
886.55

Corr. for Dr. Lt.

Corr. for Dr. Lt.

(Relocate) Fld. Dr. Lt.

886.0

886.0

888.36
105+00 Drive Lt.
887.73

Sta. 104+30

Sta. 104+30

Sta. 104+25 Resume Project & Work

Exist. R/W

Exist. R/W

104+00
890.39

103+00
892.37

102+00
892.88

101+00
893.12

R/W

R/W

R/W

R/W

COUNTY OF HANCOCK

HAN-69-11.49 (21.49)

DWG. NO. 10

SHEET NO. 15

| Seeding | | |

End Area	Cu. Yds.		
Cut	Fill	Cut	Fill
0	0		
73	2	50	1
129	6	91	4
137	1	142	4
74	2	45	1
0	0	53	1
Sheet Totals		381	11

(Carried to Sheet No. 10)

FED. RD. DIVISION | STATE | PROJECT | 12 / 51

2 | OHIO

HANCOCK COUNTY
HAN-69-(1.14)(1.97)(2.31)(3.28)(4.23)(6.17)

Sta. 3+77

4+00
881.85

3+40
882.09

3+15
884.59

2+85.5
884.69

2+74
882.29

2+00
881.35

Sta. 2+35

87380

87370

87370

87365

Channel Alignment

6+00

P.I. 5+00

170°

Sta. 107+50 Han 69

Sta. 3+00 on ℄

4+00

Han. 69

108+00

107+00

100'-30'

100'

100'

Sheet Total

Seeding	Mulch Sq. Yd.

Channel Sections, Sta. 2+00 to Sta. 4+00, Cummins Ditch, 1st Crossing

FED. RD. DIVISION	STATE	PROJECT	
2	OHIO		

13
51

HANCOCK COUNTY
HAN-69-(1.14)(1.97)(2.31)(3.28)(4.23)(6.17)

INTERSECTION NO. 1-P

Sta. 105+81.45 Han-69
Scale 0 10 20 40 Feet





*ESTIMATED QUANTITIES

Item	203	Subgrade Preparation	613	Sq. Yd.
Item	310	5" Subbase	88.58	Cu. Yd.
Item	304	5" Aggregate Base	91.00	Cu. Yd.
Item	407	Bituminous Tack Coat	9	Gal.
Item	408	Bituminous Prime Coat	248	Gal.
Item	402	1¾" Asphalt Concrete	31.02	Cu. Yd.
Item	404	1¼" Asphalt Concrete	23.87	Cu. Yd.
Item	408	Cover Aggregate	2.48	Cu. Yd.

*Quantities carried to Pavement Computations, Sheet No. 4

Note: Pavement edge dimensions as shown on Typical Sections.

Intersection Detail No. 1-P

HANCOCK COUNTY
HAN-69-(1.14)(1.97)(2.31)(3.28)(4.23)(6.17)

(Br. 0237)





EXISTING STRUCTURE

Span ~ 25'-0"
Type ~ Concrete Slab
Roadway ~ 24'-0"
Skew ~ None
Loading ~ CF 130.

UTILITIES

General Telephone Co. Marion, Ohio
Ohio Power Co. Canton, Ohio

PROPOSED STRUCTURE

Type ~ Single span reinforced concrete slab with reinforced concrete wall abutments.
Span ~ 24'-0" f/f of abutments.
Roadway ~ 36'-0" f/f guard rail
Load Frequency ~ CF = 130 (57).
Skew ~ None
Wearing Surface ~ 1" Monolithic concrete.
Approach Slabs ~ A5-1-54 (25' long)
Alignment ~ Tangent.



Typical Section of Adjoining Pavement Applies Both Ends

B.M. #2 Spike in ℄, 31' Lt.
Sta. 121+58 Elev. 880.05

B.M. #3 Spike in Twin Ash, 36' Rt.
Sta. 129+24 Elev. 878.20

18" Ash
32" Oak
12" Ash
30" Elm
42" White Oak
24" Twin Ash

ROADWAY DRAINAGE "D"

Station From	Station To	Bends & Branches Each	602 Catch Basins 2'-A Each	602 Inlets Removed Each	603 Conduit Lin. Ft. F 12"	603 Conduit Lin. Ft. F 10"	603 Conduit Lin. Ft. E 12"	660 Sodding Sq. Yd.	601 Dump Rock Chan. Prot. 18" Thick Cu. Yd.	Side
124+97	125+11									Lt.
125+26	125+36								5.2	Lt.
124+95	125+11								5.2	Rt.
125+35	125+55	1	1	1		10	20		5.2	Rt.
125+35	126+00	1	1	1	10			16	5.2	Lt.
126+31.5				2	10		15	16		Lt.
Totals		2	2	4	10	10	35	16	20.8	

Ref. No.	1-D	2-D	3-D	4-D	5-D	6-D

SIDE APPROACHES "A"

Ref. No.	Station	Side	603 Conduit D Lin. Ft. 12"	304 Aggr. Base Cu. Yd.	Length Lin. Ft.	Remarks
1-A	125+79	Lt.	62	11.3	90	Farm Drive
Totals			62	11.3		

GUARD RAIL "G"

Ref. No.	Station From	Station To	Side	606 Guard Rail Type 4 Lin. Ft. Straight
1-G	123+82.23	*125+69.73	Lt.	161.00
2-G	123+00.98	*126+63.48	Rt.	336.00
Totals				497.00

*Deduct 26.50' for Bridge


879.78
879.54
879.35
879.20
879.09
879.02
879.00
879.00
879.00
879.00
879.00
879.00
879.00
879.01
879.05
879.11
879.19
Salvage
Salvage
889.49
889.14
889.14
887.89
885.72
884.25
114
115
116
117
118
119
890
885
880
875
870
865
150' V.C.
100' V.C.
-1.04%
0.00%
+0.38%
Sta. 1235+09.75
Sta. 1235+36.25
26.50' Bridge Limits
10'Rt.
12'Lt.
4'Lt.
8'Lt.
+30.32' Lt. Elev. 874.6
+30.32' Lt. Elev. 874.6
+38.26' Rt. 870.70
+38.26' Rt. 871.05
+38.26' Lt. 871.50
+38.26' Lt. 871.50
+38.26' Lt. 871.50


50 45 40 35 30 25 20 15 10 5 ℄ 5 10 15 20 25 30 35 40 45 50
SEEDING
WIDE SQ.YD.
END AREA CU. YD.
CUT FILL CUT FILL
Profile 10' Stone Dr. Lt.
R/W
Corr. for Dr. Lt.
5 12" F.T.
12"(D)
879.00
125+79
877.70
Corr. for Dr. Lt. 0 0
Ahead
Back
879.00
125+61.25
877.71
End Approach Slab
Sta. 125+61.25 Ahead 15 66
Back 20 61
873.4
873.7
10" F.T.
29 182
879.00
125+36.75
877.78
Back of Prop. Abutment
Ahead 43 337
BRIDGE NO. HAN. 69-0237
870.1
879.00
125+09.25
877.83
Back of Prop. Abutment
Back 63 89
Sta. 124+97 Lt.
Begin O.R.C.P.
Sta. 124+98 Rt.
Begin O.R.C.P.
34 68
879.00
124+84.75
877.83
Begin Approach Slab
Sta. 124+84.75 Ahead 12 61
Back 5 45
874.5
874.3
4" F.T.
10" F.T.
19 171
879.00
124+00
877.95
6 44
874.7
875.5
Transition from 8' Shoulder width @ Sta. 123+55 Lt.
to 10' Shoulder width @ Sta 123+80 Lt.
Transition from 8' Shoulder @ Sta. 122+75 Rt.
to 10' Shoulder width @ Sta 123+00 Rt.
28 113
879.02
123+00
878.29
876.3
876.5
9 17
122+00
879.47
Sta. 121+75, Resume Work & Project
Sta. 121+75 0 0
Exist. R/W
121+00
880.73
Sheet No. 15 131 573
Sheet No. 16 176 625
Sheet No. 17 430 3
Totals Part III 737 1201
120+00
882.17
Sta 120+00 to Sta 125+79
2071 Total Sheet No. 15
3309 Total Sheet No. 16
5380 Total Part III
HANCOCK COUNTY
HAN-69-(11.49)(11.93)2L2(A23)A (17)
15
51

SEEDING WIDTH	SEEDING SQ.YD.		END AREA CUT	END AREA FILL	CU. YD. CUT	CU. YD. FILL
		Sta. 131+50 Suspend Project & Work				
0		131+50	Sta. 131+50	0	0	
	122				6	7
44		Exist. R/W (A) 876.6 — 12'F.T. — 879.05 131+00 878.92 — (3) 876.8 (2) 10'F.T. — Exist. R/W		6	7	
	500				26	33
46		R/W (5) (X) 876.3 — 12'F.T. — 879.00 130+00 878.54 — (2) 876.6 (2) 10'F.T. — R/W		8	11	
	522				33	48
48		R/W (3) (7) 876.0 — 12'F.T. — 879.00 129+00 878.38 — (7) 876.4 10'F.T. — R/W		10	15	
	572				35	98
55		R/W (38) (6) 875.7 — 12'F.T. — 879.00 128+00 877.67 — (4) 875.6 10'F.T. — R/W		9	38	
	633				33	157
59		R/W (47) (1) 876.5 — 12'F.T. — 879.00 127+00 877.54 — 10'F.T. 875.0 — Ahead Sta. 125+61.25 — Carried to Sheet No. 15.	Sta. 127+00	9	47	
			Sta. 126+00	6	58	28 194
			Sheet Totals	15	66	15 88
				176	625	
	678	Transition from 10' Shoulder width @ Sta. 126+65 Rt. to 8' Shoulder width @ Sta. 126+90 Rt.				
63		Sta. 126+00, 32' Lt. Std. C-2-A, C.B. (mod) R/W F.L. Elev. 874.60 (3) 12"(D)(Back) 100, 32' Lt. 870.90 — (58) 12'F.T. — 879.00 126+00 877.69 — 10'F.T. (3) 873.8 — R/W				
	282					
68		125+61.25				
3309		Sheet Totals (Carried to Sheet No. 15)				

Sta 126+00 to Sta 131+00

HANCOCK COUNTY
HAN-69-11.14(X)97(2.31)(32.20)(4.23)(6.17)

OHIO — DISTRICT 2 — STATE PROJECT

16 — 51

End Area	Cu. Yds.
Cut / Fill	Cut / Fill
0 / 0	
83 / 0	114 / 0
128 / 0	47 / 0
115 / 1	37 / 1
68 / 2	56 / 1
34 / 0	50 / 0
0 / 0	430 / 3

Sta 4+00

Sta 3+28
878.19

Proposed Abutment

Sta 3+14
878.39

Proposed Wing Wall

Proposed Abutment

Sta 2+86
878.77

Proposed Wing Wall

Sta 2+75
878.27

Sta 2+50
877.47

Sta 2+00
(Carried to Sheet No. 3)

Channel Alignment

P.I. Sta 125+51 Hon 69
= Sta 3+00 on ℄

147°

4+00

P.I. 4+36

93°

℄ Hon 69

126+00

125+00

83°

2+00

P.I. 1+45

156°

1+00

Seeding	Wide	Sq. Yd.

Channel Sections, Sta. 2+00 to Sta. 4+00, Cummins Ditch, 2nd Crossing

Sheet Total

ENG. DIV.	STATE	PROJECT	
2	OHIO		

17
51

HANCOCK COUNTY
HAN-69-(1.14)(1.97)(2.31)(3.28)(4.23)(6.17)

HANCOCK COUNTY
HAN-69-(1.14)(1.97)(2.31)(3.28)(4.23)(6.17)
(Br. 0336)

Note : No Utilities either side

PROPOSED STRUCTURE
Type ~ Continuous Reinf. Conc. Slab with capped pile substructure.
Spans ~ 26.0'-32.5'-26.0' c/c Bearings.
Roadway ~ 36'-0" f/f guardrails.
Load Frequency ~ C.F.-130(57).
Skew ~ 10° R.F.
Wearing Surface ~ 1" Monolithic Concrete.
Approach Slabs ~ A5-1-54 (25' Long).
Alignment ~ Tangent.

EXISTING STRUCTURE
Span ~ 2 @ 25'-0"
Type ~ Concrete Slab
Roadway ~ 24'-0"
Skew ~ None
Loading ~ CF 130

Resume Work & Project Sta. 173+00

Suspend Project & Work Sta. 182+25

Sta. 172+00 P.O.T. Sta 172+00 24" Ut. 10'Dia. Inlet

Sta. 183+00 P.O.T. Sta 183+00

Sta. 184+00 End Sheet

Begin Sheet

Sta. 172+40 20' Rt. 10'Dia. Inlet

Sta. 181+40, 23' Rt. 10'Dia. Inlet Remove (202) Comm. Hhv.

Exist. R/W

Exist. R/W

8" F.T.

8" F.T.

C 8" F.T.

C 8" F.T.

N 0°-36' E

12"x30'(D)

12"x30'(D)

40" C.M.P.

30"x30'(D)

Wood Fence

Wood Fence

12' Dirt Fld. Dr.

12' Dirt Fld. Dr.

Fld. Dr.

CREEK

LITTLE

Willow

1-A 1-G 1-D 3-D 3-A 2-G 2-D 4-D 2-A 5-D

20'-0"
5¾" Bituminous Pav't.
5" Water Bound Macadam

Typical Section of Adjoining Pavement Applies Both Ends

B.M. Spike in 24" Hickory 170' Lt. Sta 175+87 Elev. 864.57

B.M. Chiseled Square in S.W. Abutment Elev. 865.70

MICROFILMED JUL 15 1986

ROADWAY DRAINAGE "D"

											Bends & Branches	Each	Each
											202 Inlet Removed	Each	Each
											604 Std. No. C.2A C.B.(Mod)	Each	Each
											603 Conduit Lin. Ft.	F	8"
												E	8"
											600 Sodding	Sq. Yds.	Sq. Yds.
											601 Dumped Rock Chan. Prot. 18" Thick	Cu. Yds.	Cu. Yds.
Side													
Station		To											
	From												
Ref. No.													
1-D	177+30	177+44										Lt.	4.5
2-D	177+28	177+43										Rt.	5.5
3-D	177+90	178+07										Lt.	7.2
4-D	178+01	178+20										Rt.	5.0
5-D	181+37	181+43										Rt.	
												Totals	22.2

													1
													1
													1



Cut	Fill	Cu. Yd. Cut	Cu. Yd. Fill
17	65		
		17	44
20	34		
28	42		
		66	165
			28
6	43		
		22	131
6	28		
		26	69
8	9		
		5	5
0	0		
		136	442
		141	308
		345	3
		351	14
		973	767

HANCOCK COUNTY
HAN-69-11.19/0.00-23.68

OHIO

19
51

FED. RD. DIVISION	STATE	PROJECT	
2	OHIO		

46
51

HAN-69-(1.14)(1.97)(2.31)(3.28)(4.23)(6.17)

REINFORCING STEEL LIST

Mark	No.	Length	Weight	Shp.
Abutment				
A501	78	4'-1"	332	B
A502	96	7'-8"	768	S
A503	16	27'-10"	464	S
A504	36	9'-2"	344	S
A505	4	8'-2"	34	S
A506	20	7'-2"	149	S
A507	8	6'-2"	51	S
A508	16	5'-2"	86	S
A509	32	6'-2"	206	S
A510	26	6'-4"	172	B
A511	4	2'-3"	9	S
A512	2	14'-0"	29	S
A513	8	25'-0"	209	S
A514	4	7'-7"	30	S
A515	4	3'-8"	15	S
A516	4	28'-0"	117	S
A517	12	30'-4"	380	S
A518	90	6'-10"	214	S
A519	10	21'-6"	224	S
A520	20	8'-0"	167	S
A521	4	5'-0"	21	S
A522	4	18'-2"	76	S
Superstructure				
A833	79	26'-2"	5519	B
B601	50	35'-6"	2666	S
C501	13	24'-0"	325	S
Replacement Bars				
RE601	1	6'-6"	-	S
RE601	1	5'-11"	-	S
RE501	1	5'-7"	-	S

Bending Diagrams

A501

3'-7"±

A510

5'-4"%

A833

24'-0"%

MICROFILMED
JUL 15 1986

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
DIVISION OF DESIGN AND CONSTRUCTION
BUREAU OF BRIDGES

4

REINFORCING STEEL LIST

BRIDGE NO. HAN-69-0622 OVER MARSH RUN HANCOCK CO.

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
UEM.	UEM.	UEM.	FPH	BFG	5-31-67	


Seeding
Wide Sq. Yd.
End Area
Cut Fill
Cu. Yd.
Cut Fill
Exist. R/W
Exist. R/W
183+00
868.60
8' F.T.
5
5 8' F.T.
Sta. 182+25
0 0
0 182+25
Sta. 182+25, Suspend Project & Work
28
20
R/W
R/W
867.36
182+00
867.30
865.3
3
5 8' F.T.
8' F.T.
3 0
230
15 8
49
R/W
R/W
884.5
4
8' F.T.
866.82
181+40
866.65
864.4
1
10" Inlet
5 8' F.T.
Remove (202)
Conn. Thru.
11 7
220
18 11
50
R/W
R/W
864.3
5
8' F.T.
866.37
181+00
866.13
864.1
3
5 8' F.T.
14 8
594
39 50
57
R/W
R/W
863.0
2
8' F.T.
866.50
180+00
865.57
5 8' F.T.
862.4
5
7 19
689
26 100
67
R/W
R/W
861.3
8' F.T.
866.50
179+00
865.95
5 8' F.T.
861.3
4
7 35
Transition from 10' Shoulder width @ Sta. 178+70 Rt. & Lt.
to 8' Shoulder width @ Sta. 179+10 Rt. & Lt.
Sta. 178+77 Corr. for Dr. Rt. & Lt.
8
417
-65
R/W
Corr. for Dr. Rt.
10%
10%
21 86
R/W
12" (D)
866.50
178+84 Field Dr. Lt., 178+77 Field Dr. Rt.
865.34
10" CMP
12" (D)
5 8' F.T.
-65 Corr. for Dr. Lt.
60
R/W
Ahead
Back
861.1
1
8' F.T.
11
861.50
178+41.01
865.37
End Approach Slab
31
861.1
5
5 8' F.T.
Ahead 12 44
Back 23 42
R/W
159
20 45
Ahead 178+16.77 22 58
R/W
861.0
8' F.T.
Profile 13' Fld. Dr. Lt. (Abandon)
861.50
178+27
865.37
Carried to Sheet No. 19
Sheet Totals 141 308
58
R/W
29
29
11
861.50
178+16.77
865.41
3
860.9
2
860.9
8" C.M.P.
150
Back of Prop. Abut.
66
235.7
177+95 Ahead
Carried to Sheet No. 19
STRUCTURE NO. HAN-69-0336
Sta. 177+16.77 to Sta. 183+00
HANCOCK
HAN-69-11.49/11.62 3R/Resurf/Widen
COUNTY
15
20

FED. RD. DIVISION	STATE	PROJECT	
2	OHIO		

21
51

HANCOCK COUNTY
HAN-69-(1.11A)(1.97)(2.31)(3.28)(4.23)(6.17)

Seeding
Wide Sq. Yd.

25 20 15 10 5 ℄ 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75 80 85 90 95 100 105 110 115 120 125

	End Area		Cu. Yd.	
	Cut	Fill	Cut	Fill
	111	4		
			52	1
	148	2		
			240	2
	72	0		
			53	0
Sta. 1+60	0	0		
Sheet Totals			345	3

Carried to Sheet No. 19

Channel Sections Sta. 1+00 to Sta. 2+70 Little Riley Creek

FED. ROAD DIVISION	STATE	PROJECT	
2	OHIO		

22
51

HANCOCK COUNTY
HAN-69-(1.14)(1.97)(2.31)(3.28)(4.23)(6.17)

25 20 15 10 5 ℄ 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75 80 85 90 95 100 105 110 115 120 125

Seeding	
Wide	Sq. Yd.

4+00
862.17

3+25
862.03

(56)

855.10

Face of Abut.

(170)

3+15
864.53

855.05

Face of Abut.

Face of Abut.

2+85
864.94

855.0

Deduct for 20⁵ Rem. of Exist. Structure

	End Area		Cu. Yd.	
	Cut	Fill	Cut	Fill
Sta. 3+92	0	0		
			70	0
	56	0		
			42	1
	170	1		
			203	8
	195	13		
			86	5
			-50	
Sta. 2+70	114	4		
carried to Sheet No. 19	Sheet Totals		351	14

25 20 15 10 5 ℄ 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75 80 85 90 95 100 105 110 115 120 125

Channel Sections Sta. 2+85 to Sta. 4+00 Little Riley Creek

HANCOCK COUNTY
HAN-69-(1.14)(1.97)(2.31)(3.28)(4.23)(6.17)
(Br. 0430)



ROADWAY DRAINAGE "D"

Ref. No.	Station From	Station To	Side	601 Dump Rock Channel Protection 18" Thick Cu. Yd.	660 Sodding Sq. Yd.	603 Conduit Lin. Ft. A 8"x5'-11"	E 12"	F 6"	F 10"	F 12"	F 18"	F 8"	202 Removal of Exist. Struct. Lump	604 Catch Basins (Type) 2-2A Each	602 Masonry C.Y.	202 C.B. Removed Inlet Removed Ends of Branches Each	202 Each
1-D	225+29		Rt.		32		24							2		1	2
2-D	225+90	226+85	Lt.	3	57			22			10						1
3-D	227+00	227+07	Lt.						10								
4-D	226+94	227+09	Rt.	4						18							1
5-D	226+73	227+26	Lt.	7			14					10					1
6-D	227+25	227+40	Rt.	6								14					1
*1-C	226+93	227+27	Rt. & Lt.	27	38	72							Lump		7.3		
Totals				47	127	72	38	22	10	18	10	24	Lump	2	7.3	1	1

* See Sheet No. 26 for Details

GUARD RAIL "G"

Ref. No.	Station From	Station To	Side	606 Guard Rail Type 4 Lin. Ft. Straight
1-G	225+62.5	227+62.5	Lt.	200.00
2-G	225+67	230+04.5	Rt.	437.50
Total				637.50

SIDE APPROACHES "A"

Ref. No.	Station	Side	304 Aggr. Base Cu. Yd.	Conduit Type D Lin. Ft. 12"		Length Lin. Ft.	Remarks
1-A	225+39	Lt.	*10.3			35	Field Drive
2-A	225+42	Rt.	*10.3			38	Field Drive
3-A	227+85	Lt.	*10.3	28		42	Field Drive
Totals			30.9	28			

* Place 304 Aggregate to 25' length (Back of Radius)

Sta. 222+00 to Sta. 233+00

PART - V

50 45 40 35 30 25 20 15 10 5 ℄ 5 10 15 20 25 30 35 40 45 50

SEEDING WIDE	SEEDING SQ.YD.	END AREA CUT	END AREA FILL	CU. YD. CUT	CU. YD. FILL

Sta. 227+10 Structure No. Han. 0430

855.45
227+02 Back of Abutment (Exist)
854.66

2:1 2:1

RW

F.L. Witch Ditch 7

10" F.T.

8'-7" x 5'-11" Structural Plate Pipe Arch

68 RW 364 RW 12 43 17 75

855.43
226+50
854.38

3:1 3:1

848.3 12" F.T. 10" F.T. 850.7

Transition from 8' Shoulder width at Sta. 225+37 Lt. to 10' Shoulder width at Sta. 225+62 Lt.

Transition from 8' Shoulder width at Sta. 225+42 Rt. to 10' Shoulder width at Sta. 225+67 Rt.

Transition from 4:1 side slopes at Sta. 226+00 Lt. & Rt. to 2:1 side slopes at Sta. 227+00 Lt. & Rt.

63 RW 497 RW 6 38 29 76

855.27
226+00
854.34

4:1

850.6 12" F.T. 10" F.T. 850.8

Sta. 225+90, Lt.
Begin Sod

Corr. for Dr. Rt. 1

854.75
225+42 Drive Right (Dirt)
854.28

10" C.M.P. 10" F.T.

-65 Corr. for Dr. Rt.

RW

854.74
225+39 Drive Left (Dirt)
854.28

-65 Corr. for Dr. Lt. 8" F.T. 12" F.T. Corr. for Dr. Lt. 1

Sta. 225+22, 32' Lt.
Std. No. 2-2A, C.B. (Mod)
F.L. Elev. 850.80

Sta. 225+23, 31.5' Rt.
Std. No. 2-2A, C.B. (Mod)
F.L. Elev. 850.80

63 RW 184 RW 16 20 11 17

(8"-16'(L)) 8" Ahead C.B. +29.5 Left. 854.73 225+29 854.24 Inlet Right (8"-8'(L))

12" F.T.

Remove (202)

10" F.T. (Ah. & Ba.)
Remove (202)

+22.3 Lt.
848.03±

+25, 30.5' Rt.
848.00±

51 RW 517 RW 5 11 22 22

854.49
225+00
854.08

851.3 12" F.T. 851.3 10" F.T.

42 RW 172 RW 7 1 7 1

851.5 12" F.T. 851.5 10" F.T.

224+00
853.67

20 223+50 Sta. 223+50, Resume Work & Project Sta. 223+50 0 0

Total Sheet No. 24 88 191
Total Sheet No. 25 270 280
Total Part V 358 471

Exist. R/W

12" F.T. 223+00 853.66 10" F.T.

Exist. R/W Exist. R/W

1604 Total Sheet No. 24
2773 Total Sheet No. 25

12" F.T. 222+00 854.21 10" F.T.

4377 Total Part V

Sta. 222+00 to Sta. 227+10

50 45 40 35 30 25 20 15 10 5 ℄ 5 10 15 20 25 30 35 40 45 50

HANCOCK COUNTY
HAN-69-(11.49)(11.82)(12.14)(12.46)

OHIO | SHEET NO. 2 | TOTAL SHEETS 25 | SCALES | ELEVATION | PLAN

15
24


50 45 40 35 30 25 20 15 10 5 ℄ 5 10 15 20 25 30 35 40 45 50
SEEDING WIDE SQ.YD.
END AREA CU.YD. CUT FILL CUT FILL
8"F.T.
233+00 859.85
Exist. R/W
232+00 859.19
Sta. 231+33, SUSPEND PROJ. & WORK
231+33 Drive Left. (Stone) 858.24
Sta. 231+20
231+00 857.61
230+00 856.21
229+00 854.96
228+00 854.47
Corr. for Dr. Lt.
Transition 10' shoulder width @ Sta. 227+62 Lt. to 8' shoulder width @ Sta. 227+87 Lt.
Transition 10' shoulder width at Sta. 230+05 Rt. to 8' shoulder width at Sta. 230+30 Rt.
12"(D)
227+85 Dr. Lt. (Relocated) 854.51
227+50 Drive Left. (Dirt) abon. 854.58
Sta. 227+50
Sta. 227+23.8
Sta. 226+50
Sheet Total (Carried to Sheet No. 24)
Transition 2:1 slopes at Sta. 227+30 Rt. to 4:1 slope at Sta. 229+00 Rt.
Transition 2:1 slopes at Sta. 227+25 Lt. to 4:1 slopes at Sta. 228+00 Lt.
227+23.8 Back of Abutment (Exist.) 854.67
Sta. 227+23.8 to Sta. 233+00
Sta. 226+50
Sheet Total (Carried to Sheet No. 24)
HANCOCK COUNTY
HAN-69-11.11/11.25-11.26
25
57

FED. RD. DIVISION	STATE	PROJECT	
2	OHIO		

26
51

HANCOCK COUNTY
HAN-69-(1.14)(1.97)(2.31)(3.28)(4.23)(6.17)
STRUCTURE 0430

STRUCTURE NO. I-C

Sta. 227+10, Han. 69

Scale: 0 5 10 20 Feet



*ESTIMATED QUANTITIES

602	Concrete Masonry, Class C	7.30	Cu. Yds
603	8'-7"x 5'-11" Conduit, type A with Class B Bedding, 707.03.10-10 Gage	72	Lin. Ft.
601	Dumped Rock Channel Protection	27	Cu. Yds.
660	Sodding	38	Sq. Yds.

Standard Drawing SP-53
Drainage Area = 1.67 Sq. Mi.
Q_{25} = 184 C.F.S.

* Quantities Carried to Line Sheet No. 23



ENDWALL DETAIL



Structure Detail No. 1-C

HANCOCK COUNTY
HAN-69-(1.14)(1.97)(23.31)(23.20)(23.23)(6.17) (Br. 0622)

UTILITIES

Hancock-Wood Electric Co-op Inc.; North Baltimore, Ohio
Community Telephone Co. Leipsic, Ohio

PROPOSED STRUCTURE

Type ~ Single span reinforced concrete slab with reinf. conc. wall abutments.
Span ~ 22'-0" c/c abutments.
Roadway ~ 36'-0" f/f guardrails.
Load Frequency ~ C.F. = 130 (57).
Skew ~ None
Wearing Surface ~ 1" Monolithic conc.
Approach Slabs ~ A5-1-54 (25' long).
Alignment ~ Tangent.

EXISTING STRUCTURE

Span ~ 22'-0"
Type ~ Concrete Slab
Roadway ~ 24'-0"
Skew ~ None
Loading ~ CF 130
Built ~ 1932
Condition ~ Fair

P.O.C. Sta. 323+00
P.T. Sta. 325+55.08
P.O.T. Sta. 334+00
Begin Sheet
End Sheet
Resume Work & Project Sta. 326+00
END Work & Project Sta. 331+00
5-712(9)
Exist. R/W
N 0°-27' W
Dist. Dr. 130
42" Conc. Pipes
Dist. Dr. 100
24"x 10'-0" RCP
10'x10'
8'x30' (E)
8'x38' (E)
8'x30' (W)
8'x10' (W)
8'-0" C.M.P. (Outlet)
10'x50' (E)
6'x10' (E)
24" Conc.
24"x30'
24"x58' (E)
18"x10'
18"x30'
18" F.F.
5'-5" F.F.
7" F.F.
6" F.F.
6" Wall Casing
Sta. 333+04.83 ℄ Dist. Dr.
30° Used Elbs
Sta. 334+00
Sta. 323+00
P.T. Sta. 325+55.08
Refs:-Buttons in Pavt.
30.63°
31.07'
35.98'
Ref. Button in Pavt.
D = 3°-00'
42.93'
28.97'
Ref. Button in Pavt.
20'-0"
3½" Bituminous Pavt.
5" Water Bound Macadam
Typical Section of Adjoining Pavement Applies Both Ends

B.M. No.1 Spike in ϕ 39" Rt. Sta. 323+45 Elev. 828.64

B.M. Chiseled Square on top of North Post of L Banister HAN-69-06.22 Elev. 831.93

B.M. No. 2 Chiseled "X" End Wall, 60' Lt. Sta. 332+75 Elev. 828.60

ROADWAY DRAINAGE "D"

Ref. No.	Station From	Station To	Side	601 Dump Rock Channel Paved 18" Thick Cu.Yd.	660 Seeding Sq.Yd.	603 Conduit Lin. Ft. E 6"	E 8"	E 10"	E 24"	F 8"	F 10"	F 18"	F 24"	Bends & Branches
1-D	328+00	328+43	Lt.	5.0	20									
2-D	327+91	328+86	Rt.	16.0		10	38	50	58	10	10	10	10	6
3-D	328+63	328+77	Lt.	5.0										
Totals				26.0	20	10	38	50	58	10	10	10	10	

GUARD RAIL "G"

Ref. No.	Station From	Station To	Side	606 Guard Rail Type 4 Lin. Ft. Straight
1-G	326+99.37*	329+39.37	Lt.	275.5
2-G	327+05.62*	330+05.62	Rt.	275.5
Totals				551.0

* Deduct 24.5' for Bridge

MICROFILMED JUL 15 1986

Salvage
Salvage
Sta. 328+40.25
Sta. 328+44.75
100' V.C.
200' V.C.
100' V.C.
24.5' Bridge Limits
+0.44%
-0.44%
+0.08%
+0.04%
8' Lt.
5' Rt.
8' Rt.
24' Rt.
4' Rt.
6' Rt.
7' Rt.
42" Lt.
+50 P.I. 828.40
+50 P.I. 828.10
+50 P.I. 828.40
10 Yr. Hi-Water Elev. ___ 828.5
5 Yr. Hi-Water Elev. ___ 826.5
Normal Water Elev. ___ 821.9
Flow Line Elev. ___ 821.4

Excavation	493	Cu.yds.
Embankment	196	Cu.yds.

Sta. 323+00 to Sta. 334+00 PART-VI

45 40 35 30 25 20 15 10 5 ℄ 5 10 15 20 25 30 35 40 45

Seeding		End Area		Cu. Yd.	
Width	Sq. Yd.	Cut	Fill	Cut	Fill

STRUCTURE NO. — HAN.-69-0622

Add for Channel Excavation 200

75 — R/W 55'

74 — 2:1 — 51 — 2:1 — R/W

26 — 829.03 — 328+39.75 — 828.71

BACK OF PROP. ABUTMENT

15 — 821.8 — 4 Stub — 8 F.T. — 24 F.T. — 822.1 — 19 — 2:1 — Back 60 125

208

Transition from 4:1 slope @ Sta. 328+15 Rt. to 2:1 slope @ Sta. 328+40 Rt. 66 64

78 — R/W 55'

7 — 3:1 — Back ① Cut — Ahead (27) — 829.03 — 328+15.25 — 828.55 — Back ① Cut — 10 — 4:1 — R/W — Ahead 85 17 — Back 60 17

51 — 824.2 — 5 F.T. — 7 — 824.1 — 24 F.T.

BEGIN APPROACH SLAB

Transition from 4:1 slope @ Sta. 328+00 Lt. to 2:1 slope @ Sta. 328+35 Lt.

117

Transition from 8' Shoulder width @ Sta. 326+75 Rt. & Lt. to 10' Shoulder width @ Sta. 327+00 Rt. & Lt. 21 8

60 — R/W 53'

5 — 4:1 — 11 — R/W

2 — 825.7 — ① — 829.01 — 328+00 — 828.51 — ① — 2:1 — 16 — 5 F.T. — 824.2 — 16 12

611

50 31

R/W — 4 — 12 — R/W

50 — 3 — 825.9 — 828.62 — 327+00 — 828.43 — 9 — 825.0 — 5 F.T. — 11 5

278

20 9

Exist. R/W — 8' C.M.P. — R/W — 0 0

326+00 — 828.36 — RESUME WORK & PROJECT

Exist. R/W — 8' C.M.P.

Field Dr. Lt. — 325+90 — 828.37

Exist. R/W — Exist. R/W

325+00 — 828.55

Total Sheet No. 28 357 112

Total Sheet No. 29 136 84

Total Part VI 493 196

324+00 — 828.94

324+00 to 325+00

325+00 to 326+00

1214 Total Sheet No. 28

1244 Total Sheet No. 29

323+00 — 829.93

2458 Total Part VII

45 40 35 30 25 20 15 10 5 ℄ 5 10 15 20 25 30 35 40 45

HANCOCK COUNTY — HAN-69-0622 (11.01) — 0.00 MILES

OHIO | STATE | FED. ROAD PROJECT | 2

15 — 20

45 40 35 30 25 20 15 10 5 ℄ 5 10 15 20 25 30 35 40 45

Seeding Wide	Seeding Sq. Yd.	End Area Cut	End Area Fill	Cu. Yd. Cut	Cu. Yd. Fill

334+00
832.93

333+96.5
832.82

333+04
830.36

7' F.T.
S 8 Inlet

Field Dr. Lt. 333+00
830.29

7' F.T.

332+00
828.83

7' F.T.

331+00
828.42

END WORK ℄ PROJECT

Exist. R/W

828.42
330+70
828.41

7' F.T.

0 Sta. 330+70 — Sta. 330+70 | 0 | 0

175 | 22 | 1

45 | Exist R/W | 826.8 | 828.62 | 330+00 | 828.42 | R/W | Sta. 330+00 | 17 | 1

7' F.T.

76 | 26

686 | Sta. 328+89.75 | Ahead | 20 | 12

Back | 40 | 12

Ahead Sta. 328+65.25 | 44 | 114 | 38 | 57

67 | R/W 51' | 34:1 | Ahead cut | Back (22) | Ahead cut | 34:1 | (Carried to Sheet No. 28) | Sheet Total | 136 | 84

826.5

Transition from 2:1 slope @ Sta. 328+70 Lt. to 4:1 slope @ Sta. 329+00 Lt.

829.03
328+89.75
828.82

END APPROACH SLAB

823.9

Transition from 2:1 slope @ Sta. 328+70 Rt. to 4:1 slope @ Sta. 329+02 Rt.

Transition from 10' shoulder width @ Sta. 330+00 Lt. to 8' shoulder width @ Sta. 330+25 Lt.

Transition from 10' shoulder width @ Sta. 328+90 Rt. to 8' shoulder width @ Sta. 329+10 Rt.

182 | 2:1 | 2:1

67 | R/W 55' | 201 | 8218 | 829.03
328+65.25
828.62

BACK OF PROP. ABUTMENT

℄ stub | ℄ F.T. | 822.0

75 | Sta. 328+39.75

1244 | Sheet Total (carried to Sheet No. 28)

Sta. 328+75 to Sta. 334+00

45 40 35 30 25 20 15 10 5 ℄ 5 10 15 20 25 30 35 40 45

HANCOCK COUNTY
HAN-68-11.49/23.30(23.30)

R/W 54'

R/W 53'

OHIO | NO. | REVISED | BY | DATE

15 | 29

FED. RD. DIVISION	STATE	PROJECT	
2	OHIO		

30/51

HANCOCK COUNTY
HAN-69-(1.14)(1.97)(2.31)(3.28)(4.23)(6.17)
3.9± Miles North of Ada



PROPOSED STRUCTURE

TYPE: Continuous Reinforced Concrete Slab with capped pile substructure
SPANS: 16'-20'-16' c/c Bearings
ROADWAY: 36'-0" f/f Guardrail
LOAD FREQUENCY: CF-130(57)
SKEW: 10° Right Forward
WEARING SURFACE: 1" Monolithic Concrete
APPROACH SLABS: AS-1-54 (25' long)
ALIGNMENT: Tangent



MICROFILMED
JUL 15 1968

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

1/3

SITE PLAN

BRIDGE NO. HAN-69-0121
OVER BINKLEY CREEK
HANCOCK CO SR-69

SEC.
STA. 63+63.24
STA. 64+16.76
SCALE 1" = 20'

PRESENT TOPOGRAPHY		PROPOSED WORK			
SURVEYED	DRAWN	DESIGNED	DRAWN	CHECKED	REVIEWED
AERIAL SURVEY	AERIAL SURVEY	R.E.J.	R.E.J.	N.J.B.	P.E.S.

BRG 1-31-67

01498

FED. RD. DIVISION	STATE	PROJECT		31 / 57
2	OHIO			

HAN-69-(1.14)(1.97)(2.31)(3.28)(4.23)(6.17)



GENERAL PLAN



Note: Only end piles shown. All piles shall be 14" cast-in-place reinforced concrete.

ELEVATION

ESTIMATED QUANTITIES

ITEM	TOTAL	UNIT	DESCRIPTION	SUPER	PIERS	ABUTS	GEN'L	AS BUILT	
202	Lump	Sum	Existing structure removed				Lump		
503	71	Cu. Yds.	Unclassified excavation			71			
505	Lump	Sum	First test pile				Lump		
507	480	Lin. Ft.	14" Cast-in-place reinforced concrete piles		240	240		0-159	4-81
509	24,770	Lbs.	Reinforcing steel	16,234	3,689	4,847			
511	87	Cu. Yds.	Class C concrete, superstructure and pier caps	74	13				
511	43	Cu. Yds.	Class E concrete, abutments			43			
517	107.04	Lin. Ft.	Railing (Two deep beam rails with steel posts and bolts)	107.04					
518	15	Cu. Yds.	Porous backfill			15			
601	197	Sq. Yds.	Crushed aggregate slope protection				197		
808	87	Units	Water-reducing, set-retarding admixture	74	13			0-87	—
825	230	Sq. Yds.	Concrete surface treatment	230					

GENERAL NOTES

REFERENCE shall be made to Standard Drawings A-1-54 and P-1-54, both revised 11-8-65, CS-1-65 dated 6-1-65, and to Supplemental Specifications 808 dated 1-13-67 & 825 dated 1-1-67.

DESIGN DATA:

Design Loading-CF 130(57)
Concrete Class C-Basic unit stress 1,333 p.s.i.
Concrete Class E-Basic unit stress 1,133 p.s.i.
Reinforcing Steel-ASTM A15, A16, A160, Deformed, Intermediate or Hard Grade. Basic unit stress 20,000 p.s.i.

REMOVAL OF EXISTING STRUCTURE:

When no longer needed to maintain traffic the existing structure shall be removed.

EXCAVATION QUANTITY for the abutments in addition to that outlined in Section 503.10 includes the removal of material bounded by the proposed bench, by the front vert. plane described in Sec. 503.10 and by the finished slope of the cut.

PILES shall be driven to a maximum bearing capacity of 18 tons per pile for the abutments and 23 tons per pile for the piers.

PIER PILE ENCASEMENT as shown on Standard Drawing No. P-1-54 may be omitted provided the tapered portion, if any, of all pier piles does not extend above the stream bed or the proposed surface of the ground. If the tapered portion of any pile extends above these limitations, the encasement will be required for all the pier piles. If the encasement is omitted the pile casings shall have a thickness of metal not less than No.7 ga. and the painting of the piles shall extend to low water elevation or, if the proposed surface of the ground is above low water, the painting shall extend to at least one foot below the proposed surface of the ground.

That portion of the lower guard rail that projects outside the bridge limits shall be included, for payment, with the bridge railing.



TWO DEEP BEAM RAILING

MICROFILMED
JUL 15 1986

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
DIVISION OF DESIGN AND CONSTRUCTION
BUREAU OF BRIDGES

GENERAL PLAN & ELEVATION GENERAL NOTES & ESTIMATED QUANTITIES

BRIDGE NO. HAN-69-0121
Over Binkley Creek
STA. 63+63.24 To 64+16.76

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
B.W.E.	E.P.M.III	E.P.M.III	FFE	BFG	1-31-67	

REV 4-16-70 GFJ

FED. RD. DIVISION	STATE	PROJECT	
2	OHIO		

32
51

HAN-69-(1.14)(1.97)(2.31)(3.28)(4.23)(6.17)



PIER PLAN



PIER ELEVATION



ABUTMENT PLAN



ABUTMENT ELEVATION

REINFORCING STEEL LIST

Mark	No.	Length	Weight	Shp
Superstructure				
A720	102	19'-3"	4013	S
B720	34	15'-3"	1,060	B
C720	32	13'-8"	894	B
D720	17	15'-6"	539	S
E720	16	11'-0"	360	S
F820	58	14'-10"	2,297	S
G820	28	9'-4"	698	S
H820	28	8'-4"	623	S
J601	30	11'-5"	514	S
K601	15	9'-2"	207	S
M601	52	36'-0"	2,812	S
N601	41	36'-0"	2,217	S
Piers				
P1001	8	36'-0"	1,239	S
P901	8	33'-0"	898	S
P701	72	4'-0"	589	S
P501	4	33'-0"	138	S
R502	64	9'-0"	601	B
P503	8	6'-4"	53	B
P401	48	5'-4"	171	B

Bending Diagram



Mark	No.	Length	Weight	Shp
Abutments				
R1001	16	19'-2"	1,320	S
R801	16	22'-5"	958	S
R501	16	22'-0"	367	S
R502	136	6'-7"	934	B
R503	8	18'-4"	153	S
R504	24	5'-4"	134	S
R505	28	7'-11"	231	B
R506	4	10'-7"	44	S
R507	16	5'-0"	83	S
R508	24	6'-6"	167	B
R509	24	8'-5"	211	B
R510	4	10'-10"	45	S
R401	56	5'-4"	200	B
Replacement bars				
RE1001	1	7'-2"	—	S
RE901	1	6'-10"	—	S
RE801	1	6'-6"	—	S
RE701	1	6'-2"	—	S
RE601	1	5'-11"	—	S
RE501	1	5'-7"	—	S
RE401	1	5'-4"	—	B

MICROFILMED
JUL 15 1986



COMPOSITE TRANSVERSE SECTION

* Note: The 16" & 11" dimensions shown include a 1" monolithic wearing surface.

For complete details refer to Standard Drawing CS-1-65 Sections B-B, C-C, & D-D

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
DIVISION OF DESIGN AND CONSTRUCTION
BUREAU OF BRIDGES

33

ABUTMENT and PIER DETAILS, COMPOSITE TRANSVERSE SECTION & REINFORCING STEEL LIST

BRIDGE No. HAN-69-0121 over Binkley Creek

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
BAE	BAE		FFE	BFG	1-31-67	

FED. RD. DIVISION	STATE	PROJECT	
2	OHIO	67 S-	

33
51

HANCOCK COUNTY
HAN-69-(1.14)(1.97)(2.31)(3.28)(4.23)(6.17)

5.5± Miles south of Mt. Cory

881.2 885.1 887.6 881.4 881.2 881.6 882.5 885.0 887.1 885.1 881.6 881.5 881.3 881.1 881.8 883.1 887.7

Elev. 875.7±

Transition slopes 2:1 to 4:1 at all four corners

CUMMINS DITCH

880

2:1 4:1 18° +59.55 +97.05

105 106 107 108 109 110 111

N 0°-12' E

End Appr. Slab Sta. 107+72.69

Begin Appr. Slab Sta. 107+95.31

885.21

+70.95 +108.45

890 889.5 889.2 885.6 885.4 883.3 881.6 881.7 881.7 882.9 883.6 880.9 884.8 882.6 882.3 881.5 883.5 891.0 885.5 883.2

EARTHWORK limits shown are schematic. Actual slopes shall conform to plan cross-Sections.

EXISTING STRUCTURE
SPAN – 23'-0" (Clear)
TYPE – Concrete Slab
ROADWAY – 24'-0"
SKEW – None
LOADING – H-15
BUILT – 1932
CONDITION – Poor
1984 DESIGN TRAFFIC = 884 A.D.T.
DRAINAGE AREA – 2.87 sq. mi.

Clears 5 Year High Water Elev. 3.5' ±

BRIDGE LIMITS 22.62'

Sta. 107+72.69

Sta. 107+95.31

B.M. YELLOW PAINTED SQUARE N.E. HEADWALL

B.M. No 2 Spike in 14" Walnut 50' Rt. Sta 105+57 Elev. 888.13

B.M. No. 1 Spike in ø 29' Rt. Sta 111+94 Elev. 892.14

Highest Known High Water Elev. 885.5
10-Year High Water Elev. 883.0
5-Year High Water Elev. 882.0

889.21 888.76 888.36 888.01 887.72 887.48 887.30 887.17 887.09 887.06 887.06 887.06 887.08 887.14 887.23 887.37

250' V.C. 300' V.C.

890 880 870 860

-2.12% 0.60% 0.00%

2:1 (Norm) 2:1 (Norm)

Limits of channel excavation

Ftg. Elev. 872.0

Excavate channel thru structure to Elev. 875.7±

105+50 El. 887.06

887.23 886.55 886.38 886.01 885.78 885.29 885.21 885.17 885.12 885.31 885.25

105 106 107 108 109 110

PROPOSED STRUCTURE

TYPE: Single span reinforced concrete slab with reinforced concrete wall abutments
SPANS: 20'-0" face to face of abutments
ROADWAY: 36'-0" f/f guard rail
LOAD FREQUENCY: CF=130(57)
SKEW: 18° R.F.
WEARING SURFACE: 1" monolithic concrete
APPROACH SLABS: AS-1-54 (25' long)
ALIGNMENT: Tangent

MICROFILMED JUL 15 1988

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

1/4

SITE PLAN

BRIDGE NO. HAN-69-0204
OVER CUMMINS DITCH
HANCOCK CO SR-69
SEC. STA. 107+72.69 107+95.31
SCALE 1" = 20'

PRESENT TOPOGRAPHY		PROPOSED WORK			
SURVEYED	DRAWN	DESIGNED	DRAWN	CHECKED	REVIEWED
		D.H.S.	D.H.S.	R.E.J.	P.E.S.

BFG 6-6-67 R.M.M.

0144B

FED. RD. DIVISION	STATE	PROJECT	
2	OHIO		

34/51

HAN-69-(7.14)(1.97)(2.31)(3.28)(4.23)(6.17)



GENERAL PLAN



ELEVATION

GENERAL NOTES

REFERENCE shall be made to Standard Drawings SB-1-64 sheets 1 and 2, revised 11-8-65 and to Supplemental Specifications 808 dated 1-13-67 and 825 dated 1-1-67.

DESIGN SPECIFICATIONS: This structure conforms to the requirements of "Design Specifications for Highway Structures" of the State of Ohio, Department of Highways, dated 9-1-57, together with current revisions thereof.

DESIGN DATA:
Design Loading - CF 130(57).
Concrete Class C - basic unit stress 1,333 p.s.i.
Concrete Class E - basic unit stress 1,133 p.s.i.

DESIGN DATA: (Cont.)
Reinforcing Steel - ASTM A15, A16, A160, Deformed, Intermediate or Hard Grade. Basic unit stress 20,000 p.s.i.

REMOVAL OF EXISTING STRUCTURE: When no longer needed to maintain traffic the existing structure shall be removed.

FOOTINGS shall extend a minimum of 3" into undisturbed rock or to the elevation shown, whichever is lower.

FOUNDATION BEARING PRESSURE: Footings are designed for a maximum bearing pressure of 4.0 tons per sq. ft.

For two deep beam railing see sheet 31

ESTIMATED QUANTITIES

Item	Total	Unit	Description	Super	Abuts.	Genl.	As Built	
202	Lump	Sum	Existing structure removed			Lump		
503	Lump	Sum	Cofferdams, Cribs and Sheeting			Lump		
503	155	Cu. Yds.	Unclassified excavation, including rock		155			
509	12,864	Lbs.	Reinforcing steel	7725	5139			
511	38	Cu. Yds.	Class C concrete, superstructure	38				
511	105	Cu. Yds.	Class E concrete, abutments above footings		105			
511	58	Cu. Yds.	Class E concrete, footings		58			
516	11	Sq. ft.	½" Preformed expansion joint filler, AASHO M-153			11		
517	45.24	Lin. ft.	Railing, (Two deep beam rails with steel posts and bolts)	45.24				
518	69	Cu. Yds.	Porous backfill			69		
808	38	Units	Water-reducing, set-retarding admixture	38			C-1 38	
825	100	Sq. Yds.	Concrete surface treatment	100				

MICROFILM
JUL 15 1986

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
DIVISION OF DESIGN AND CONSTRUCTION
BUREAU OF BRIDGES

2/4

GENERAL PLAN & ELEVATION, NOTES, & ESTIMATED QUANTITIES

BRIDGE No. HAN-69-0204
over CUMMINS DITCH

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
BWE	BWE	N.R.B	INNES 6-25-67	BFG	6-6-67	

REV 4-16-71 GFJ

FED. RD. DIVISION	STATE	PROJECT	
2	OHIO		

35
51

HAN-69-(1.14)(1.97)(2.31)(3.28)(4.23)(6.17)



ABUTMENT PLAN



ELEVATION

NOTES

FOOTINGS shall extend a minimum of 3" into undisturbed rock or to the elevation shown, whichever is lower.

POROUS BACKFILL shall extend from 6" below weepholes upward to the approach slab and to the surface of the earth shoulders. Backfill shall not be placed higher than one-third of the abutment height prior to placing of deck slab.

LEGEND: n.s. denotes near side; f.s. denotes far side.

DETAILS: Both forward and rear abutments identical.



VIEW A-A



VIEW B-B



SECTION C-C



SECTION D-D

MICRO
JUL 15 1986

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
DIVISION OF DESIGN AND CONSTRUCTION
BUREAU OF BRIDGES

3/4

ABUTMENT DETAILS
BRIDGE NO. HAN-69-0204 OVER CUMMINS DITCH

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED DATE	REVISED
HEN	HEN			BFG 6-6-67	

FED. RD. DIVISION	STATE	PROJECT	
2	OHIO		

36
51

HAN-69-(1.14)(1.97)(2.31)(3.28)(4.23)(6.17)



SUPERSTRUCTURE DETAILS

Longitudinal bars are spaced parallel to the face of abutment.

REINFORCING STEEL LIST

Mark	No.	Length	Weight	Shp
Superstructure				
A831	76	24'-2"	4904	B
B601	45	37'-4"	2523	S
C501	13	22'-0"	298	S
Abutments				
D601	34	10'-6"	536	B
D602	4	12'-0"	72	B
D603	50	4'-10"	363	B
D501	58	10'-1"	625	S
D502	8	4'-9"	40	S
D503	16	11'-10"	198	S
D504	16	6'-3"	104	S
D505	4	5'-2"	22	S
D506	50	10'-9"	561	S
D507	6	8'-10"	55	S
D508	6	3'-1"	19	S
D509	4	26'-11"	112	S
D510	4	30'-10"	129	S
D511	4	30'-1"	126	S
D512	36	33'-3"	1249	S

Bending Diagram



Mark	No.	Length	Weight	Shp
Abutments (Con't.)				
D513	4	5'-9"	24	S
D514	16	8'-2"	136	B
D515	30	9'-1"	284	B
D516	24	8'-4"	208	B
D517	16	7'-5"	124	S
D518	4	8'-11"	37	S
D519	4	7'-9"	32	S
D520	8	6'-7"	55	S
D521	2	6'-5"	13	B
D522	2	2'-10"	6	B
D523	2	3'-8"	8	B
Replacement Bars				
RE801	1	6'-6"	—	S
RE601	1	5'-11"	—	S
RE501	1	5'-7"	—	S

BAR SIZE is indicated in the bar mark. The first digit where three digits are used, and the first two digits where four are used, indicate the bar size number. For example, A700 is a No. 7 size bar and A1014 is a No. 10 size.

* SPECIAL NOTE :

EXCAVATION QUANTITY includes the removal of material described by the shaded area shown in Detail-A, for the full length of the abutment. The quantity shall be measured as a solid bounded on the bottom and sides by the planes described in Sec. 503.10 and bounded on the top by the limits of channel excavation.



SECTION A-A



DETAIL-A *

MICROFILM
JUL 15 1986

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
DIVISION OF DESIGN AND CONSTRUCTION
BUREAU OF BRIDGES

4/4

SUPERSTRUCTURE DETAILS & REINFORCING STEEL LIST, EXCAVATION QUANTITY DETAIL
Bridge No. - HAN-69-0204
over Cummins Ditch

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
B.W.E.	B.W.E. R.M.W.		INNES	BFG	6-6-67	

FED. RD. DIVISION	STATE	PROJECT	
2	OHIO	67 S-	

37/51

HANCOCK COUNTY
HAN-69-(1.14)(1.97)(2.31)(3.28)(4.23)(6.17)
5.2 ± Miles south of Mt. Cory

1984 DESIGN TRAFFIC = 884 A.D.T.

EXISTING STRUCTURE
SPAN ~ 25'-0"
TYPE ~ Concrete Slab
ROADWAY ~ 24'-0"
SKEW ~ None
LOADING ~ H-15
BUILT ~ 1932
DRAINAGE AREA ~ 3.75 square miles

PROPOSED STRUCTURE

TYPE: Single span reinforced concrete slab with reinforced concrete wall abutments
SPANS: 24'-0" face to face of abutments
ROADWAY: 36'-0" face to face of guard rails
LOAD FREQUENCY: CF = 130 (57)
SKEW: None
WEARING SURFACE: 1" monolithic concrete
APPROACH SLABS: AS-1-54 (25' long)
ALIGNMENT: Tangent

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

1/3

SITE PLAN

BRIDGE NO. HAN-69-0237
OVER CUMMINS DITCH
HANCOCK CO SR. 69

SEC.
STA. 125+09.75
125+36.25
SCALE 1" = 20'

PRESENT TOPOGRAPHY		PROPOSED WORK			
SURVEYED	DRAWN	DESIGNED	DRAWN	CHECKED	REVIEWED
AERIAL SURVEY	AERIAL SURVEY	D.H.S.	D.H.S.	R.E.J.	P.E.S.

BFG 3-1-67

01448

JUL 15 1986

125+09.75

Elev. 869.0

Elev. 869.0±

End Appr. Slab
Sta. 125+09.75

Begin Appr. Slab
Sta. 125+36.25

+07.23

+38.48

+07.23

+38.48

Elev. 869.0±

Transition slopes 2:1 to 4:1 at all four corners

Elev. 869.0±

Clears 5 year High Water Elevation 2.6'±

BRIDGE LIMITS = 26.50'

N 0°-12' E

CUMMINS DITCH

B.M. No. 2 Spike in ϕ 31' Lt.
Sta. 121+58 Elev. 880.05

B.M. No. 3 Spike in Twin Ash 36' Rt.
Sta. 129+24 Elev. 878.20

B.M. YELLOW PAINTED SQUARE N.E. HEADWALL

150' V.C.

1.04%

0.00%

0.00%

Limit channel excavation

Ftg. Elev. 866.00

Highest Known Hi Water Elev. 877.8
10 Yr. High Water Elev. 876.0
5 Yr. High Water Elev. 874.8

Excavate channel thru structure to elevation 869.0±

Pi. Sta. 122+50
Et. 879.00

122 123 124 125 126 127 128

879.54 879.35 879.20 879.09 879.02 879.00 879.00 879.00 879.00 879.00 879.00

880 870 860 850

879.47 878.29 877.95 877.83 877.78 877.71 877.70 877.60 877.54

877.92

877.0

874.2

874.3

873.7

874.6

873.5

874.7

875.6

875.2

876.6

877.4

878.9

876

878

874

FED. RD. DIVISION	STATE	PROJECT		
2	OHIO			

38
57

HANCOCK COUNTY
HAN-69 ~~(1.12)~~ (1.97) (2.31) (3.28) (4.23) (6.17)



NOTE: For section A-A & section B-B see sheet no. 39

GENERAL PLAN



ELEVATION

GENERAL NOTES

Reference shall be made to Standard Drawings SB-1-64 sheets 1 and 2 revised 11-8-65, and to Supplemental Specifications 808 dated 1-13-67 and 825 dated 1-1-67.

Design Data:
Design Loading - CF 130 (57)
Concrete Class C - Basic unit stress 1,333 p.s.i.
Concrete Class E - Basic unit stress 1,133 p.s.i.
Reinforcing Steel - ASTM A15, A16, A160, Deformed, Intermediate or Hard Grade.
Basic unit stress 20,000 p.s.i.

Removal of Existing Structure: When no longer needed to maintain traffic the existing structure shall be removed.

Footings shall extend to a minimum of 3" into undisturbed rock or to the elevation shown, whichever is lower.

Foundation Bearing Pressure: Abutment footings are designed for a maximum bearing pressure of 4.0 tons per sq. ft.

Slab Thickness is $15\frac{3}{4}$" which includes 1" for monolithic wearing surface.

For Two-deep beam railing see sheet 31

ESTIMATED QUANTITIES

Item	Total	Unit	Description	Super.	Abts.	Gen'l	As Built	
202	Lump	Sum	Existing structure removed			Lump		
503	49	Cu. Yds.	Unclassified excavation		49			
503	42	Cu. Yds.	Rock excavation		42			
503	Lump	Sum	Cofferdams, cribs and sheeting		Lump			
509	13,807	Lbs.	Reinforcing steel	9478	4329			
511	48	Cu. Yds.	Class C concrete, superstructure	48				
511	78	Cu. Yds.	Class E concrete, abutment walls		78			
511	55	Cu. Yds.	Class E concrete, abutment footings		55			
516	10	Sq. Ft.	½" Preformed expansion joint filler, AASHO M-153		10			
517	53.00	Lin. Ft.	Railing (Two deep beam rails with galvanized steel posts & bolts	53.00				
518	50	Cu. Yds.	Porous backfill		50		E-17	57
808	48	Units	Water-reducing, set-retarding admixture	48			E-1	—
825	115	Sq. Yds.	Concrete surface treatment	115				

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
DIVISION OF DESIGN AND CONSTRUCTION
BUREAU OF BRIDGES

2

GENERAL PLAN, ELEVATION, NOTES, AND ESTIMATED QUANTITIES
BRIDGE No. HAN-69-0237
OVER CUMMINS DITCH

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
E.S.T.	E.S.T.	E.P.M.	J.D.E. 2-9-67	B.F.G.	3-1-67	

REV. 4-16-70 GFJ

FED. RD. DIVISION	STATE	PROJECT	
2	OHIO		

39
51

HANCOCK COUNTY
HAN-69 - (1.14)(1.97)(2.31)(3.28)(4.23)(6.17)



PARTIAL ABUTMENT PLAN



PARTIAL ELEVATION

REINFORCING STEEL LIST

Mark	No.	Length	Weight	Shp
Superstructure				
A834	62	28'-2"	6,167	B
B601	56	35'-6"	2,986	S
C501	12	26'-0"	325	S
Abutments				
E601	52	8'-5"	657	B
D501	46	4'-4"	208	B
L501	32	33'-8"	1,124	S
L502	8	30'-8"	256	S
L503	8	27'-8"	231	S
L504	8	5'-7"	47	S
M501	46	8'-5"	404	S
N501	46	8'-0"	384	S

Bending Diagram



Mark	No.	Length	Weight	Shp
Abutments (Cont)				
P501	16	6'-2"	103	B
Q501	20	6'-0"	125	S
Q502	8	4'-6"	38	S
Q503	8	3'-0"	25	S
S501	20	9'-7"	200	S
S502	8	8'-1"	67	S
S503	8	6'-7"	55	S
R501	24	5'-5"	136	S
T501	36	7'-2"	269	B
Replacement Bars				
RE801	1	6'-6"	—	S
RE601	1	5'-11"	—	S
RE501	1	5'-7"	—	S



END VIEW



SECTION E-E

SECTION F-F



SECTION A-A



SECTION B-B

Note:
For additional superstructure details see Std. Dwg. SB-1-64, Sheet 1.
n.s denotes near side, f.s. denotes far side.

MICRO. FILMED
JUL 15 1986

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
DIVISION OF DESIGN AND CONSTRUCTION
BUREAU OF BRIDGES

PARTIAL ABUTMENT PLAN, ELEVATION, REINFORCING STEEL DETAIL AND LIST

BRIDGE No. HAN-69-0237
OVER CUMMINS DITCH

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
E.S.T.	E.S.T.		J.D.R.	BFG	3-1-67	

FED. RD. DIVISION	STATE	PROJECT	
2	OHIO		

40
51

HANCOCK COUNTY
HAN-69-(1.14)(1.97)(2.31)(3.28)(4.23)(6.17)
4.2± miles South of Mt. Cory.

RILEY CREEK

Elev. 855.0±

GATE

End Appr. Slab Sta. 177+29.99

Begin Appr. Slab Sta. 178+16.01

3.0' bench

Elev. 855.0±

N 0°-36 E

Transition slope 2:1 to 4:1 at all 4 corners

EARTHWORK limits shown are schematic. Actual slopes shall conform to plan cross-sections.

Clears 5year Highwater Elev. 2.4'

EXISTING STRUCTURE
SPAN — 2@ 25'-0" (Clear)
TYPE — Concrete Slab
ROADWAY — 24'-0"
SKEW — None
LOADING — H-15
BUILT 1932
CONDITION — Fair
DRAINAGE AREA — 13.2 Sq Mi.

1984 DESIGN TRAFFIC: 884 ADT

PROPOSED STRUCTURE

TYPE: Continuous reinforced concrete slab with capped pile substructure
SPANS: 26.0'-32.5'-26.0' c/c brgs.
ROADWAY: 36'-0" f/f guard rails
LOAD FREQUENCY: CF = 130 (57)
SKEW: 10° R.F.
WEARING SURFACE: 1" monolithic concrete
APPROACH SLABS: AS-1-54 (25' long)
ALIGNMENT: Tangent

B.M. Spike 24" Hickory 170' Lt. Sta. 175+87 Elev. 864.57

B.M. CHISELED SQUARE S.W. ABUTMENT ELEV. 865.70

BRIDGE LIMITS = 86.02'

Sta. 177+23.99

Sta. 178+16.01

Highest Known Highwater El. 865.3
10year Highwater El. 863.5
5year High water (Design) El. 862.5
Normal Water 855.8

Bench Elev. 862.9±

Bench Elev. 862.9±

150' V.C.

200' V.C.

+0.56%

0.00%

2:1 (Norm)

2:1 (Norm)

Excavate channel thru structure to Elev. 855.0±

All piles are 12 BP53 Steel piles
Estimated average pay length:
Abutments ~ 17 feet
Piers ~ 19 feet

Elev. 866.50

175 176 177 178 179

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

JUL 15 1988

SITE PLAN

BRIDGE NO. HAN-69-0336
OVER RILEY CREEK
HANCOCK CO SR 69
SEC.
STA. 177+29.99 178+16.01
SCALE 1" = 20'

PRESENT TOPOGRAPHY		PROPOSED WORK			
SURVEYED	DRAWN	DESIGNED	DRAWN	CHECKED	REVIEWED
AERIAL SURVEY	AERIAL SURVEY	D.H.S.	D.H.S.	N.J.B.	P.E.S.

BFG 2-20-67

01448

FED. RD. DIVISION	STATE	PROJECT	
2	OHIO		

41
51

HANCOCK COUNTY
HAN-69-~~(1.74)(1.97)(2.31)(3.28)(4.23)(6.17)~~



GENERAL PLAN



ELEVATION

ESTIMATED QUANTITIES

Item	Total	Unit	Description	Super.	Piers	Abuts.	Gen'l.	As Built	
202	Lump	Sum	Existing structures removed				Lump		
503	83	Cu. Yds.	Unclassified excavation			83			
505	Lump	Sum	First test pile				Lump		
507	510	Lin. Ft.	Steel piles (12 BP 53)		270	240			
509	39,565	Lbs.	Reinforcing steel	31,703	3,017	4845			
511	14.9	Cu. Yds.	Class C concrete, superstructure & pier caps	13.6	1.3				
511	4.4	Cu. Yds.	Class E concrete, abutments			4.4			
517	172.04	Lin. Ft.	Railing (Two deep beam rails with steel posts & bolts)	172.04					
518	14	Cu. Yds.	Porous backfill			14			
601	200	Sq. Yds.	Crushed aggregate slope protection			200			
808	14.9	Units	Water-reducing, set-retarding admixture	13.6	1.3				
825	370	Sq. Yds.	Concrete surface treatment	370					

GENERAL NOTES

REFERENCE shall be made to Std. Drwgs. CS-1-65 dated 6-1-65, P-1-54 revised 11-8-65, A-1-54 revised 11-8-65, and to Supplemental Specifications No. 808 dated 1-13-67 & 825 dated 1-1-67.

DESIGN LOADING = CF = 130(57)
Concrete class "C" basic unit stress 1,333 p.s.i.
Concrete class "E" basic unit stress 1,133 p.s.i.
Reinforcing Steel - ASTM A15, A16, A160, Deformed, Intermediate or Hard Grade, basic unit stress 20,000 p.s.i.

REMOVAL OF EXISTING STRUCTURE: When no longer needed to maintain traffic the existing structure shall be removed.

PILES shall be driven through the existing subsoils to firm contact with bedrock at both abutments and both piers. If the length of penetration is approximately equal to the depth to rock according to the bridge foundation investigation report, the firm contact shall be considered as attained when the capacity according to the formula in Sec. 507.05 is not less than the following value for a pile hammer of the indicated energy rating.
For the abutment piles:
40 tons per pile using a 7,000 ft. lb. hammer
35 tons per pile using an 11,000 ft. lb. hammer
30 tons per pile using a 15,000 ft. lb. or greater hammer.
For the pier piles:
50 tons per pile using a 7,000 ft. lb. hammer
45 tons per pile using an 11,000 ft. lb. hammer
40 tons per pile using a 15,000 ft. lb. hammer
If the energy rating of the hammer is between the ratings as shown above, the required formula capacity shall be determined by interpolation. The design load of the abutment piles is 23 tons per pile and the pier piles is 30-32 tons per pile.

PIER PILE ENCASEMENT as shown on Std. Drwg. P-1-54 is not required. The painting of the piles shall extend to low water elevation or, if the proposed surface of the ground is above low water, it shall extend to at least one foot below the proposed surface of the ground.

For Two deep beam railing see sheet 31

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
DIVISION OF DESIGN AND CONSTRUCTION
BUREAU OF BRIDGES

2

GENERAL PLAN, ELEVATION, NOTES, AND ESTIMATED QUANTITIES
BRIDGE No. HAN-69-0336
OVER RILEY CREEK

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
E.S.T.	E.S.T.		JHNES 2-9-67	BFG	2-20-67	



ABUTMENT PLAN



ABUTMENT ELEVATION

Note: All piles are 12 BP53 steel piles



PIER PLAN



PIER ELEVATION

REINFORCING STEEL LIST

Mark	No.	Length	Weight	Shp
Superstructure				
A825	108	30'-3"	8723	S
B825	34	22'-2"	2,013	B
C825	36	19'-3"	1,850	B
D825	17	20'-10"	945	S
E825	18	15'-8"	753	S
F925	70	24'-5"	5,812	S
G925	36	12'-5"	1,520	S
H925	32	9'-7"	1,042	S
JG01	36	16'-6"	892	S
KG01	18	12'-11"	349	S
MG01	87	36'-1"	4,715	S
NG01	57	36'-1"	3,089	S
Piers				
P1001	8	36'-1"	1,241	S
P901	8	33'-0"	898	S
P501	4	33'-0"	138	S
P502	52	9'-0"	488	B
P503	8	6'-4"	53	B
P401	56	5'-4"	199	B
Abutments				
R1001	16	19'-3"	1,323	S
R801	16	22'-5"	958	S
R501	16	21'-11"	366	S
R502	136	6'-7"	933	B
R503	8	16'-4"	153	S
R504	24	5'-4"	133	S
R505	28	7'-11"	231	B
R506	8	10'-8"	89	S
R507	16	4'-11"	82	S
R508	24	6'-8"	167	B
R509	24	8'-5"	211	B
R401	56	5'-4"	199	B
Replacement bars				
RE1001	1	7'-2"	—	S
RE901	1	6'-10"	—	S
RE601	1	6'-6"	—	S
RE601	1	5'-11"	—	S
RE501	1	5'-7"	—	S
RE401	1	5'-4"	—	B

Bending Diagram





SLAB REINFORCING DETAIL

Note: for more detail see standard drawing C S-1-65

MICROFILMED
JUL 15 1986

FED. RD. DIVISION	STATE	PROJECT	
2	OHIO		

42
51

HANCOCK COUNTY
HAN-69 - (1.14)(1.97)(2.31)(3.28)(4.23)(6.17)

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
DIVISION OF DESIGN AND CONSTRUCTION
BUREAU OF BRIDGES

3 3

ABUTMENT, PIER AND SLAB REIN. DETAIL AND STEEL LIST
BRIDGE No. HAN-69-0336 OVER RILEY CREEK

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
E.S.T.	E.S.T.		INNES	BFG	2-20-67	

FED. RD. DIVISION	STATE	PROJECT	
2	OHIO	67 S-	

43
51

HANCOCK COUNTY
HAN-69-(1.14)(1.97)(2.31)(3.28)(4.23)(6.17)
1.36 mi. South of Mt. Cory



1984 DESIGN TRAFFIC = 975 ADT

EXISTING STRUCTURE
SPAN — 22'-0"
TYPE ~ Concrete Slab
ROADWAY — 24'-0"
SKEW ~ None.
LOADING ~
BUILT ~ 1932
CONDITION ~ Fair

DRAINAGE AREA — 1681 Acres or 2.63 sq. miles

PROPOSED STRUCTURE

TYPE : Single span reinforced concrete slab with reinforced concr. wall abutments.
SPAN : 22'-0" c/c abutments
ROADWAY : 36'-0" c/c guardrails
LOAD FREQUENCY : CF = 130 (57)
SKEW : None
WEARING SURFACE : 1" Monolithic concr.
APPROACH SLABS : AS-1-54 (25' long)
ALIGNMENT : Tangent

MICROFILMED JUL 15 1986

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES
1/4

SITE PLAN

BRIDGE NO. HAN-69-0622
OVER MARSH RUN
HANCOCK CO SR 69
SEC.
STA. 328+40.25 328+64.75
SCALE 1" = 20'

PRESENT TOPOGRAPHY		PROPOSED WORK			
SURVEYED	DRAWN	DESIGNED	DRAWN	CHECKED	REVIEWED
AERIAL SURVEY	AERIAL SURVEY	D.G.M.	D.G.M. N.R.B.	D.H.S.	P.E.S.

01743
BFG 5-31-67

FED. RD. DIVISION	STATE	PROJECT	
2	OHIO		

44/51

~~HAN-69-(1.14)(1.97)(2.31)(3.28)(4.23)(6.17)~~



GENERAL PLAN



ELEVATION

GENERAL NOTES

REFERENCE shall be made to Standard Drawing SB-1-64 sheets 1 and 2 revised 11-8-65, and to Supplemental Specifications 808 dated 1-13-67 and 825 dated 1-1-67.

DESIGN DATA:

Design Loading - CF 130 (57)

Concrete Class C - basic unit stress 1,333 p.s.i.
Concrete Class E - basic unit stress 1,133 p.s.i.

Reinforcing Steel - ASTM A15, A16, A160, Deformed, Intermediate or Hard Grade. Basic unit stress 20,000 p.s.i.

FOUNDATION BEARING PRESSURE: Abutment footings are designed for a maximum bearing pressure of 2.5 tons per sq. ft.

FOOTING EXCAVATION shall extend for a distance 1' foot beyond the edge of the footings to elevation 812.8. The excavation shall than be backfilled to elevation 816.8, with a compacted granular material meeting the gradations of Item 310.

For Two deep beam railing see sheet 31

ESTIMATED QUANTITIES

Item	Total	Unit	Description	Super	Abuts		Gen'l	As Built	
202	Lump	Sum	Existing structure removed				Lump		
310	110	Cu.Yds	Sub base		110				
503	Lump	Sum	Cofferdams, cribs and sheeting				Lump		
503	250	Cu.Yds	Unclassified excavation		250				
509	12608	lbs.	Reinforcing steel	8511	4097				
511	43	Cu.Yds	Class C concrete, superstructure	43					
511	79	Cu.Yds	Class E concrete, abutment walls, wings & cut-off wall.		79				
511	43	Cu.Yds	Class E concrete, abutment footings		43				
516	10	Sq.ft.	½" Preformed expansion joint filler AASHO Spec. M-153	10					
517	49	Lin.ft.	Railing (Two deep beam rails with steel posts and bolts)	490					
518	36	Cu.Yds	Porous backfill		36				
808	43	Units	Water-reducing, set-retarding admixture	43					
825	105	Sq.Yds	Concrete surface treatment	105					

~~43~~



SECTION A-A

MICROFILMED
JUL 15 1986

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
DIVISION OF DESIGN AND CONSTRUCTION
BUREAU OF BRIDGES

2

GENERAL PLAN & ELEVATION NOTES & ESTIMATED QUANTITIES

BRIDGE NO. HAN-69-0622 OVER MARSH RUN HANCOCK CO.

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
JEM	JEM	JEM	FPK	BFG	5-31-67	

Rev. 9-16-70 (GFJ)

FED. RD. DIVISION	STATE	PROJECT	
2	OHIO		

45
51



PLAN (Rear Abutment shown
Fwd. Abutment opposite hand)



SECTION A-A



ELEVATION
(Rear Abutment shown
Fwd. Abutment opposite hand)



SECTION B-B



ELEVATION
(Cut-off wall)



SECTION D-D



SECTION C-C

MICROFILM
JUL 15 1986

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
DIVISION OF DESIGN AND CONSTRUCTION
BUREAU OF BRIDGES

3

ABUTMENT DETAILS

BRIDGE NO. HAN-69-0622
OVER MARSH RUN
HANCOCK CO.

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
JEM	JEM		FPK	BFG	5-31-67	