


SHEET NUM.					PART.		ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
6	7	9	10	11	01/STR/PV							
ROADWAY												
2					2	SPECIAL	69050100	2	EACH	MAILBOX SUPPORT SYSTEM, SINGLE	6	
2					2	SPECIAL	69050200	2	EACH	MAILBOX SUPPORT SYSTEM, DOUBLE	6	
EROSION CONTROL												
					1,000		832	30000	1,000	EACH	EROSION CONTROL	
PAVEMENT												
		602			602	251	01030	602	CY	PARTIAL DEPTH PAVEMENT REPAIR (442) (LONGITUDINAL)	5	
		150			150	251	01030	150	CY	PARTIAL DEPTH PAVEMENT REPAIR (442) (TRANSVERSE)		
		44			44	253	02000	44	CY	PAVEMENT REPAIR (LONGITUDINAL)		
		13			13	253	02000	13	CY	PAVEMENT REPAIR (TRANSVERSE)		
		241,155			241,155	421	10011	241,155	SY	MICROSURFACING, SURFACE COURSE, AS PER PLAN	5	
		7,953			7,953	897	01010	7,953	SY	PAVEMENT PLANING, ASPHALT CONCRETE, CLASS A (0.0" - 0.5")		
		40			40	897	02000	40	SY	PATCHING PLANED SURFACE		
TRAFFIC CONTROL												
		1,099			1,099	621	00100	1,099	EACH	RPM		
		1,099			1,099	621	54000	1,099	EACH	RAISED PAVEMENT MARKER REMOVED		
		28.92			28.92	642	00104	28.92	MILE	EDGE LINE, 6", TYPE 1 (WHITE)		
		15.13			15.13	642	00300	15.13	MILE	CENTER LINE, TYPE 1		
		127			127	643	30000	127	FT	REMOVAL OF PAVEMENT MARKING (CROSSWALK LINES)		
		352			352	643	30000	352	FT	REMOVAL OF PAVEMENT MARKING (STOP LINES)		
		15.13			15.13	643	30030	15.13	MILE	REMOVAL OF PAVEMENT MARKING (CENTER LINE)		
		28.92			28.92	643	30030	28.92	MILE	REMOVAL OF PAVEMENT MARKING (EDGE LINE, 6")		
		506			506	644	00500	506	FT	STOP LINE		
		127			127	644	00600	127	FT	CROSSWALK LINE		
		27			27	644	30000	27	FT	REMOVAL OF PAVEMENT MARKING		
MAINTENANCE OF TRAFFIC												
	40				40	614	11110	40	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE		
	200				200	614	12460	200	EACH	WORK ZONE MARKING SIGN		
		30.26			30.26	614	21550	30.26	MILE	WORK ZONE CENTER LINE, CLASS III, 642 PAINT		
		1,012			1,012	614	26610	1,012	FT	WORK ZONE STOP LINE, CLASS III, 642 PAINT		
INCIDENTALS												
					LS	614	11000	LS		MAINTAINING TRAFFIC		
					LS	623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING		
					LS	624	10000	LS		MOBILIZATION		

GENERAL SUMMARY

DESIGN AGENCY
DISTRICT 3



ENGINEERING
TEAM FOUR

DESIGNER
JNC

REVIEWER
KCK 02/28/20

PROJECT ID
101438

SHEET TOTAL
8 11

