


SHEET NUM.								PART.						ALT	ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE SHEET NO.
5	7	8	18	19	21	28		01/NHS/05	02/SSK/05	03/SSK/05	04/SSK/05	05/NHS/05	06/SAE/44	(X)		EXT	TOTAL			
		1,447						114	593		740				251	01030	1,447	CY	PAVEMENT	
		365						29	149		187				251	01030	365	CY	PARTIAL DEPTH PAVEMENT REPAIR (442) (LONGITUDINAL)	
						4					4				253	01000	4	SY	PARTIAL DEPTH PAVEMENT REPAIR (442) (TRANSVERSE)	
		144						12	60		72				253	02000	144	CY	PAVEMENT REPAIR	
		35						3	16		16				253	02000	35	CY	PAVEMENT REPAIR (FULL DEPTH FLEXIBLE) (LONGITUDINAL)	
			37,337					3,010	9	30,254					254	01000	37,337	SY	PAVEMENT REPAIR (FULL DEPTH FLEXIBLE) (TRANSVERSE)	
																			PAVEMENT PLANING, ASPHALT CONCRETE (1.50")	
			117,127					11,925	50,392	43,566					254	01000	117,127	SY	PAVEMENT PLANING, ASPHALT CONCRETE (3.00")	
			721					71	234	343					254	01600	721	SY	PATCHING PLANED SURFACE	
			7,044					719	3,029	2,619					407	20000	7,044	GAL	NON-TRACKING TACK COAT (0.06 GAL/SY)	
			17,817					1,349	5,788	8,612					407	20000	17,817	GAL	NON-TRACKING TACK COAT (0.09 GAL/SY)	
			5,680					451	2,471	2,325					408	10001	5,680	GAL	PRIME COAT, AS PER PLAN	9
			6,021					501	2,107	2,942					442	00201	6,021	CY	ASPHALT CONCRETE SURFACE COURSE, 9.5 MM, TYPE A (446), AS PER PLAN (PG64-22)	10
			440					126		144					442	10001	440	CY	ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (446), AS PER PLAN (PG88-22M)	10
			4,898					500	2,106	1,821					442	10081	4,898	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, 12.5 MM, TYPE A (446), AS PER PLAN	10
			127					10	61	45					442	22001	127	CY	ASPHALT CONCRETE SURFACE COURSE, 9.5 MM, TYPE A (449), AS PER PLAN (SAFETY EDGE)	10
						20									452	12010	20	SY	8" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC 1P	
26			806					65	348	356					617	10100	832	CY	COMPACTED AGGREGATE	
	17					3				17	3				638	10800	20	EACH	WATER WORK	
								44	226	198					621	00100	508	EACH	TRAFFIC CONTROL	
								44	226	198					621	54000	508	EACH	RPM	
					28			8	13	5	2				626	00110	28	EACH	RAISED PAVEMENT MARKER REMOVED	
						2					2				630	79500	2	EACH	BARRIER REFLECTOR, TYPE 2, 1 WAY	
						2					2				630	80100	2	SF	SIGN SUPPORT ASSEMBLY, POLE MOUNTED	
						2					2				630	85100	2	EACH	SIGN, FLAT SHEET	
						2					2				630	87500	2	EACH	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	
						2					2				630	87500	2	EACH	REMOVAL OF POLE MOUNTED SIGN AND DISPOSAL	
						8					8				630	87520	8	EACH	REMOVAL OF POLE MOUNTED SIGN AND REERECTION	
			433					342		91					642	30000	433	FT	REMOVAL OF PAVEMENT MARKING (CROSSWALK LINE)	

GENERAL SUMMARY

DESIGN AGENCY
DISTRICT 3



ENGINEERING
TEAM FOUR

DESIGNER
JLB

REVIEWER
NRF 01/24/24

PROJECT ID
107491

SHEET TOTAL
P.15 | 59