SHEET NUM. P.4	P.5	P.7	P.8	P.11	P.13	P.14	PART. 01/STR/05	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
												ROADWAY	
	37						37	202	98100	37	EACH	REMOVAL MISC.: BARRIER REFLECTORS	P.4
17							17	203	10000	17	CY	EXCAVATION (FOR PAVEMENT REPAIR)	
	305						305	209	60200	305	STA	LINEAR GRADING	
				447			447	209	72000	447	STA	PREPARING SUBGRADE FOR SHOULDER PAVING	
	5						5	623	39501	5	EACH	MONUMENT ASSEMBLY ADJUSTED TO GRADE, AS PER PLAN	P.4
	LS						LS	SPECIAL	69091000	LS		AS-BUILT CONSTRUCTION PLANS	P.5
												EROSION CONTROL	
							3,000	832	30000	3,000	EACH	EROSION CONTROL	
												DRAINAGE	
	1						1	611	98630	1	EACH	CATCH BASIN ADJUSTED TO GRADE	
	2						2	611	99660	2	EACH	MANHOLE RECONSTRUCTED TO GRADE	
	1,200						1,200	SPECIAL	61199820	1,200	LB	MISCELLANEOUS METAL	P.4
												PAVEMENT	
2,000							2,000	251	01000	2,000	SY	PARTIAL DEPTH PAVEMENT REPAIR (441), (LONGITUDINAL)	
500							500	251	01000	500	SY	PARTIAL DEPTH PAVEMENT REPAIR (441), (TRANSVERSE)	
675							675	252	01500	675	FT	FULL DEPTH PAVEMENT SAWING	
300							300	253	01000	300	SY	PAVEMENT REPAIR	
				73,109			73,108	254	01000	73,109	SY	PAVEMENT PLANING, ASPHALT CONCRETE (T=1.75")	
				4,049			4,049	254	01001	4,049	SY	PAVEMENT PLANING, ASPHALT CONCRETE, AS PER PLAN, (T=1.75")	P.11
17							17	304	20000	17	CY	AGGREGATE BASE (FOR PAVEMENT REPAIR)	
				7,039			7,039	407	20000	7,039	GAL	NON-TRACKING TACK COAT	
				3,971			3,971	408	10001	3,971	GAL	PRIME COAT, AS PER PLAN	P.11
				10			10	411	10000	10	CY	STABILIZED CRUSHED AGGREGATE, (FIELD DRIVES)	
				99,103			99,103	422	11000	99,103	SY	AGGREGATE, SINGLE CHIP SEAL, TYPE A	
				39,845			39,844	422	25000	39,845	GAL	EMULSION, CHIP SEAL	
				3,239			3,238	441	50100	3,239	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG70-22M, (T=1.5")	
				276			276	617	10101	276	CY	COMPACTED AGGREGATE, AS PER PLAN (T=1.0" AVG.)	P.11
	6.22						6.22	618	41000	6.22	MILE	RUMBLE STRIPES, EDGE LINE (ASPHALT CONCRETE)	
	4.11						4.11	618	43000	4.11	MILE	RUMBLE STRIPES, CENTER LINE (ASPHALT CONCRETE)	
				21,912			21,912	874	20000	21,912	FT	LONGITUDINAL JOINT PREPARATION	
												TRAFFIC CONTROL	
					419		419	621	00100	419	EACH	RPM	
					335		336	621	54000	335	EACH	RAISED PAVEMENT MARKER REMOVED	
	46						46	626	00110	46	EACH	BARRIER REFLECTOR, TYPE 2, ONE-WAY	
	90						90	630	02100	90	FT	GROUND MOUNTED SUPPORT, NO. 2 POST	
	12						12	630	80100	12	SF	SIGN, FLAT SHEET, 730.20	
	12						12	630	84900	12	EACH	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL	
	12						12	630	86002	12	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	
						11.65	11.65	646	10010	11.65	MILE	EDGE LINE, 6"	
						5.66	5.66	646	10200	5.66	MILE	CENTER LINE	
						42	42	646	10400	42	FT	STOP LINE	
				6			6	646	50300	6	MILE	REMOVAL OF PAVEMENT MARKING	
												STRUCTURE REPAIRS	
												FOR ATB-6-1.887 ESTIMATED QUANTITIES	16
												FOR ATB-6-5.638 ESTIMATED QUANTITIES	16
												MAINTENANCE OF TRAFFIC	
			100				100	614	11110	100	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	
		8					8	614	12460	8	EACH	WORK ZONE MARKING SIGN (ALL PHASES)	
		10					10	614	13000	10	CY	ASPHALT CONCRETE FOR MAINTAINING TRAFFIC	
			6				6	614	18601	6	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	P.8
		9.79					9.79	614	21000	9.79	MILE	WORK ZONE CENTER LINE, CLASS I	
		5.67					5.67	614	21550	5.67	MILE	WORK ZONE CENTER LINE, CLASS III, 642 PAINT	
		11.49					11.49	614	22360	11.49	MILE	WORK ZONE EDGE LINE, CLASS III, 6", 642 PAINT	
		80					80	614	26000	80	FT	WORK ZONE STOP LINE, CLASS I	
		40					40	614	26610	40	FT	WORK ZONE STOP LINE, CLASS III, 642 PAINT	

Adjusted quantity

GENERAL SUMMARY

DESIGN AGENCY

DESIGNER NKF

REVIEWER MJA 03-13-24

PROJECT ID 116821

SHEET P.9 TOTAL 17

ATB-6-0.00

MODEL: Sheet_SurvFt PAPERSIZE: 34x22 (in.) DATE: 10/29/2024 TIME: 7:53:23 AM USER: mandrasi
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 04\Ashtabula\116821\400-Engineering\Roadway\Sheets\116821_GG001.dgn