


SHEET NUM.										PART.		ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE SHEET NO.
2	5	12								01/NFP/06		EXT	TOTAL				
ROADWAY																	
LS										LS	201	11000	LS			CLEARING AND GRUBBING	
	2,016									203	10000	2,016	2,016			EXCAVATION	
	378									203	20000	378	378			EMBANKMENT	
ITEM DELETED																	
EROSION CONTROL																	
	831									831	659	10000	831	SY		SEEDING AND MULCHING	
	0.08									0.08	659	20000	0.08	TON		COMMERCIAL FERTILIZER	
	0.2									0.2	659	31000	0.2	ACRE		LIME	
	4.5									4.5	659	35000	4.5	MGAL		WATER	
										3,000	832	30000	3,000	EACH		EROSION CONTROL	
DRAINAGE																	
	888									888	601	25001	888	CY		DUMPED ROCK FILL, TYPE A, AS PER PLAN	2
RETAINING WALLS																	
		1,050								1,050	507	00400	1,050	FT		STEEL PILES, MISC.:W24x76, FURNISHED, AS PER PLAN	2
		1,225								1,225	524	94703	1,225	FT		DRILLED SHAFTS, 36" DIAMETER, ABOVE BEDROCK, AS PER PLAN	2
		190								190	524	94705	190	FT		DRILLED SHAFTS, 36" DIAMETER, INTO BEDROCK, AS PER PLAN	2
		1,225								1,225	524	95000	1,225	FT		DRILLED SHAFTS, MISC.:PERMANENT CASING	2
INCIDENTALS																	
										LS	623	10000	LS			CONSTRUCTION LAYOUT STAKES AND SURVEYING	
										LS	624	10000	LS			MOBILIZATION	

GENERAL SUMMARY

DESIGN AGENCY

 DESIGNER
 ARM
 REVIEWER
 XXX MM-DD-YY
 PROJECT ID
 117573
 SHEET TOTAL
 P.4 14