

SHEET NUM.									PART.			ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
8	9	15	16	17	18	19	20		01/NFA	02/NHS	03/S5K						
	15					45				60		203	10000	60	CY	ROADWAY	
	0.08					0.14				0.22		209	60500	0.22	MILE	EXCAVATION	
		18.12								18.12		209	72050	18.12	MILE	LINEAR GRADING	
	262.5					356.25				618.75		606	16500	618.75	FT	PREPARING SUBGRADE FOR SHOULDER PAVING	
		250								250		606	17000	250	FT	GUARDRAIL REBUILT, TYPE 5	
																RAISING TYPE 5 GUARDRAIL	
		40								40		606	17700	40	EACH		
	1									1		606	27840	1	EACH	REPLACE EXISTING GUARDRAIL BLOCKOUT	
						1				1		606	27850	1	EACH	ANCHOR ASSEMBLY REBUILT, TYPE B	
		1								1		606	27900	1	EACH	ANCHOR ASSEMBLY REBUILT, TYPE E	
	1					2				3		606	35010	3	EACH	ANCHOR ASSEMBLY REBUILT, TYPE T	
																BRIDGE TERMINAL ASSEMBLY REBUILT, TYPE 1	
																EROSION CONTROL	
	142					245				387		659	10001	387	SY	SEEDING AND MULCHING, AS PER PLAN	8
										1,162		832	30000	1,162	EACH	EROSION CONTROL	
						1				1		611	99150	1	EACH	DRAINAGE	
																INLET ADJUSTED TO GRADE	
																PAVEMENT	
1,838									50	1,778	10	253	02000	1,838	CY	PAVEMENT REPAIR	
	773									773		253	02001	773	CY	PAVEMENT REPAIR, AS PER PLAN	9
			10,308						6,219		4,089	254	01000	10,308	SY	PAVEMENT PLANING, ASPHALT CONCRETE, 1.5"	
		504,157	2,121						2,121	504,157		254	01000	506,278	SY	PAVEMENT PLANING, ASPHALT CONCRETE, 1.75"	
						5,389				5,389		254	01000	5,389	SY	PAVEMENT PLANING, ASPHALT CONCRETE, 3.75"	
	960									960		254	01000	960	SY	PAVEMENT PLANING, ASPHALT CONCRETE, 4"	
5,000							1,984			6,984		254	01001	6,984	SY	PAVEMENT PLANING, ASPHALT CONCRETE, AS PER PLAN, VARIABLE	8
		2,344								2,344		254	01010	2,344	SY	PAVEMENT PLANING, PORTLAND CEMENT CONCRETE, 1.5"	
	2,200									2,200		255	11000	2,200	SY	FULL DEPTH PAVEMENT REMOVAL AND RIGID REPLACEMENT, TYPE 1, CLASS QC1	
	7,260									7,260		255	20000	7,260	FT	FULL DEPTH PAVEMENT SAWING	
LS										LS		SPECIAL	40010000	LS		PAVER MOUNTED THERMAL PROFILING	8
		51,403	994						668	51,403	326	407	20000	52,397	GAL	NON-TRACKING TACK COAT	
		8,504								8,504		408	10000	8,504	GAL	PRIME COAT	
	3					19				22		441	70800	22	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (449), (UNDER GUARDRAIL)	
		20,585	76						76	20,585		442	00100	20,661	CY	ANTI-SEGREGATION EQUIPMENT	
		8,825								8,825		442	10080	8,825	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, 12.5 MM, TYPE A (446)	
		23,284	103						103	23,284		442	10301	23,387	CY	ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (447), AS PER PLAN	8
			431						260		171	442	20000	431	CY	ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (448)	
347							3			350		442	22400	350	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, 19 MM, TYPE A (449)	
		886								886		617	10100	886	CY	COMPACTED AGGREGATE	
			44.4							44.4		618	40600	44.4	MILE	RUMBLE STRIPS, SHOULDER (ASPHALT CONCRETE)	
LS										LS		SPECIAL	69098400	LS		INTELLIGENT COMPACTION	8
																TRAFFIC CONTROL	
				1,535	84				79	1,500	40	621	00100	1,619	EACH	RPM	
				1,535	84				79	1,500	40	621	54000	1,619	EACH	RAISED PAVEMENT MARKER REMOVED	
					1.17				0.73		0.44	644	00104	1.17	MILE	EDGE LINE, 6"	
					0.54				0.37		0.17	644	00300	0.54	MILE	CENTER LINE	
					105						105	644	00400	105	FT	CHANNELIZING LINE, 8"	
					203	33			56	147	33	644	00500	236	FT	STOP LINE	
						180					180	644	00700	180	FT	TRANSVERSE/DIAGONAL LINE	
					775				90	685		644	00720	775	FT	CHEVRON MARKING	
						67					67	644	00900	67	SF	ISLAND MARKING	
						1			1			644	01110	1	EACH	SCHOOL SYMBOL MARKING, 96"	
						2					2	644	01300	2	EACH	LANE ARROW	
						102					102	644	01510	102	FT	DOTTED LINE, 6"	
				15	28					15	28	644	20800	43	FT	YIELD LINE	
					0.43				0.28	0.15		807	12010	0.43	MILE	WET REFLECTIVE EPOXY PAVEMENT MARKING, EDGE LINE, 6"	
					47.6				0.08	47.52		807	14010	47.6	MILE	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, EDGE LINE, 6"	
					22.2					22.2		807	14110	22.2	MILE	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, LANE LINE, 6"	
					9,898				511	9,387		807	14310	9,898	FT	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, CHANNELIZING LINE, 12"	
					10,465				575	9,890		807	14410	10,465	FT	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, DOTTED LINE, 6"	
						69.8			0.08	69.72		850	10010	69.8	MILE	GROOVING FOR 6" RECESSED PAVEMENT MARKING, (ASPHALT)	
					10,465				575	9,890		850	10110	10,465	FT	GROOVING FOR 6" RECESSED PAVEMENT MARKING, (ASPHALT)	
					9,898				511	9,387		850	10130	9,898	FT	GROOVING FOR 12" RECESSED PAVEMENT MARKING, (ASPHALT)	
					0.43				0.28	0.15		850	20010	0.43	MILE	GROOVING FOR 6" RECESSED PAVEMENT MARKING, (CONCRETE)	

GENERAL SUMMARY

DESIGN AGENCY



DESIGNER

WBC

REVIEWER

KWK 07/09/25

PROJECT ID

91705

SHEET

11

TOTAL

33