

I:\ProjectData\07327\Design\Roadway\Sheets\07327\_G0002.dgn\_Sheet 18-NOV-2020 2:22PM dno:fmf

SHEET NUM.										PART.	ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE SHEET NO.
5	6	7	10	16	38	39				01/STR/OT		EXT	TOTAL			
<b>TRAFFIC CONTROL</b>																
			27							27	621	00100	27	EACH	RPM	
			27							27	621	54000	27	EACH	RAISED PAVEMENT MARKER REMOVED	
				12						12	626	00110	12	EACH	BARRIER REFLECTOR, TYPE 2 (BI-DIRECTIONAL)	
				13						13	630	02100	13	FT	GROUND MOUNTED SUPPORT, NO. 2 POST	
				1						1	630	85100	1	EACH	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	
			0.4							0.4	646	10010	0.4	MILE	EDGE LINE, 6"	
			0.2							0.2	646	10200	0.2	MILE	CENTER LINE	
<b>RETAINING WALLS</b>																
1,417										1,417	503	21101	1,417	CY	UNCLASSIFIED EXCAVATION, AS PER PLAN	5
					2,495					2,495	507	00200	2,495	FT	STEEL PILES HP12X53, FURNISHED	
					3,395					3,395	507	00400	3,395	FT	STEEL PILES, MISC.: W18X76, FURNISHED	5
			97							97	511	46511	97	CY	CLASS QCI CONCRETE, FOOTING, AS PER PLAN	5
			496							496	511	81300	496	EACH	CONCRETE, MISC.: 8" x 24" x 57" PRECAST CONCRETE LAGGING	5
			320							320	518	21200	320	CY	POROUS BACKFILL WITH GEOTEXTILE FABRIC	
				655						655	518	40000	655	FT	6" PERFORATED CORRUGATED PLASTIC PIPE	
				4						4	518	40010	4	FT	6" NON-PERFORATED CORRUGATED PLASTIC PIPE, INCLUDING SPECIALS	
					1,040					1,040	524	94503	1,040	FT	DRILLED SHAFTS, 24" DIAMETER, ABOVE BEDROCK, AS PER PLAN	5
					800					800	524	94505	800	FT	DRILLED SHAFTS, 24" DIAMETER, INTO BEDROCK, AS PER PLAN	5
					1,900					1,900	524	94603	1,900	FT	DRILLED SHAFTS, 30" DIAMETER, ABOVE BEDROCK, AS PER PLAN	5
					1,100					1,100	524	94605	1,100	FT	DRILLED SHAFTS, 30" DIAMETER INTO BEDROCK, AS PER PLAN	5
						1,125				1,125	524	95000	1,125	FT	DRILLED SHAFTS, MISC.: PLUG PILE, 30" DIAMETER, UNREINFORCED	5
<b>MAINTENANCE OF TRAFFIC</b>																
		LS								LS	614	12420	LS		DETOUR SIGNING	
	115									115	614	13000	115	CY	ASPHALT CONCRETE FOR MAINTAINING TRAFFIC	
	0.2									0.2	614	21550	0.2	MILE	WORK ZONE CENTER LINE, CLASS III, 642 PAINT	
		10								10	616	10000	10	MGAL	WATER	
		115								115	617	10100	115	CY	COMPACTED AGGREGATE	
<b>INCIDENTALS</b>																
		LS								LS	614	11000	LS		MAINTAINING TRAFFIC	
										4	619	16010	4	MNTH	FIELD OFFICE, TYPE B	
										LS	623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
										LS	624	10000	LS		MOBILIZATION	

**GENERAL SUMMARY**

**BEL - 9 - 0.01**