

G:\22085 belmont_county_courthouse_cds\Drawings\plan_sets\22085-3-GENERAL SUMMARY.dwg 11-Feb-25 8:39 AM

SHEET NUM.										PART.			ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.	
													INCIDENTALS						
										614	11001	LS		MAINTAINING TRAFFIC, AS PER PLAN, TEMPORARY ACCESS CONTROLS, BARRICADES AND SIGNAGE					
										624	10000	LS		MOBILIZATION					
										ITEMS OF WORK									
										202	11005	2	EACH	STRUCTURE REMOVED, AS PER PLAN, TRENCH DRAIN				P.8-11	
										202	23001	1,015	SY	PAVEMENT REMOVED, AS PER PLAN, ASPHALT CONCRETE				P.8-11	
										202	23001	540	SY	PAVEMENT REMOVED, AS PER PLAN, BRICK PAVER				P.8-11	
										202	30001	1,240	SF	WALK REMOVED, AS PER PLAN, 2" CONCRETE OVERLAY REMOVAL @ COURTHOUSE MAIN ENTRANCE				P.8-11	
										202	30001	3,100	SF	WALK REMOVED, AS PER PLAN, CONCRETE (HEAVY DUTY)				P.8-11	
										202	30001	7,000	SF	WALK REMOVED, AS PER PLAN, CONCRETE (REGULAR DUTY)				P.8-11	
										202	32001	1,000	FT	CURB REMOVED, AS PER PLAN				P.8-11	
										202	75611	2	EACH	VALVE BOX REMOVED, AS PER PLAN				P.8-11	
										202	98000	LS		REMOVAL MISC.: BENCH				P.8-11	
										202	98000	LS		REMOVAL MISC.: BOLLARD				P.8-11	
										202	98000	LS		REMOVAL MISC.: BUILDING-MOUNTED HANDRAIL				P.8-11	
										202	98000	LS		REMOVAL MISC.: CONCRETE PLANTER POTS				P.8-11	
										202	98000	LS		REMOVAL MISC.: DRAIN GRATE				P.8-11	
										202	98000	LS		REMOVAL MISC.: DUMPSTERS RELOCATED				P.8-11	
										202	98000	LS		REMOVAL MISC.: FLAGPOLE				P.8-11	
										202	98000	LS		REMOVAL MISC.: FLOOD LIGHT				P.8-11	
										202	98000	LS		REMOVAL MISC.: HISTORICAL MARKER SIGN				P.8-11	
										202	98000	LS		REMOVAL MISC.: MAILBOX				P.8-11	
										202	98000	LS		REMOVAL MISC.: PARKING TICKET BOX				P.8-11	
										202	98000	LS		REMOVAL MISC.: SURFACE MOUNTED HANDRAIL				P.8-11	
										202	98000	LS		REMOVAL MISC.: TABLE AND CHAIRS				P.8-11	
										202	98000	LS		REMOVAL MISC.: TRASH RECEPTACLE				P.8-11	
										202	98000	LS		REMOVAL MISC.: WOOD FENCE AND GATE				P.8-11	
										202	98000	LS		REMOVAL MISC.: X-MAS TREE PIT MANHOLE				P.8-11	
										630	85101	9	EACH	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION, AS PER PLAN				P.8-11	
										630	85200	4	EACH	REMOVAL OF GROUND MOUNTED SIGN AND DELIVERY, BUILDING MONUMENT SIGN (4)				P.8-11	
										630	85201	8	EACH	REMOVAL OF GROUND MOUNTED SIGN AND DELIVERY, AS PER PLAN				P.8-11	
										645	30011	5	EACH	REMOVAL OF PAVEMENT MARKINGS, AS PER PLAN				P.8-11	
										PAVEMENT									
										304	20001	20	CY	AGGREGATE BASE, AS PER PLAN				P.45-46	
										407	10001	5	GAL	TACK COAT, AS PER PLAN				P.45-46	
										442	22001	1	CY	ASPHALT CONCRETE SURFACE COURSE, 9.5 MM, TYPE A (449), AS PER PLAN				P.45-46	
										442	22201	0.5	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, 9.5 MM, TYPE A (449), AS PER PLAN				P.45-46	
										451	10011	320	SY	6" REINFORCED CONCRETE PAVEMENT, CLASS QC 1P, AS PER PLAN, HEAVY DUTY				P.45-46	
										SPECIAL	53000200	LS		STRUCTURES, CAST IRON RAILING RESTORATION				P.40	
										608	10001	6,500	SF	4" CONCRETE WALK, AS PER PLAN				P.45	
										608	10001	160	SF	4" CONCRETE WALK, AS PER PLAN, COURTHOUSE STAMPED OUTLINE				P.45	
										608	13001	9,200	SF	6" CONCRETE WALK, AS PER PLAN, 7 INCH				P.45	
										608	13001	3,750	SF	6" CONCRETE WALK, AS PER PLAN, BRICK PAVEMENT				P.45	
										608	40001	430	FT	CONCRETE STEPS, TYPE A, AS PER PLAN, S 01				P.37	
										608	40001	540	FT	CONCRETE STEPS, TYPE A, AS PER PLAN, S 02				P.37	
										608	40001	45	FT	CONCRETE STEPS, TYPE A, AS PER PLAN, S 03				P.37	
										608	40001	105	FT	CONCRETE STEPS, TYPE A, AS PER PLAN, S 04				P.37	
										608	40001	110	FT	CONCRETE STEPS, TYPE A, AS PER PLAN, S 05				P.37	
										608	40001	85	FT	CONCRETE STEPS, TYPE A, AS PER PLAN, S 06				P.37	
										608	40001	65	FT	CONCRETE STEPS, TYPE A, AS PER PLAN, S 07				P.37	
										608	40001	6	FT	CONCRETE STEPS, TYPE A, AS PER PLAN, S 08				P.37	
										608	40001	40	FT	CONCRETE STEPS, TYPE A, AS PER PLAN, S 09				P.37	
										608	40001	25	FT	CONCRETE STEPS, TYPE A, AS PER PLAN, S 10				P.37	
										608	40001	20	FT	CONCRETE STEPS, TYPE A, AS PER PLAN, S 11				P.37	
										608	40001	40	FT	CONCRETE STEPS, TYPE A, AS PER PLAN, S 12				P.37	
										608	40001	20	FT	CONCRETE STEPS, TYPE A, AS PER PLAN, S 13				P.37	
										608	40001	20	FT	CONCRETE STEPS, TYPE A, AS PER PLAN, S 14				P.37	
										608	53021	225	SF	DETECTABLE WARNING, AS PER PLAN				P.47	
										609	00501	48	FT	SANDSTONE CURB, AS PER PLAN, LIMESTONE				P.46	
										609	26001	215	FT	CURB, TYPE 6, AS PER PLAN, PLANTER CURB				P.45	
										609	26001	1,020	FT	CURB, TYPE 6, AS PER PLAN, WITH REINFORCEMENT				P.45	
										609	33201	180	FT	CURB, TYPE 10-B, AS PER PLAN, WITH REINFORCEMENT				P.46	
										642	13000		CY	ASPHALT CONCRETE FOR MAINTAINING TRAFFIC					
										642	00511	78	FT	STOP LINE, TYPE 1A, AS PER PLAN					
										642	00650	200	FT	CROSSWALK LINE, 24", TYPE 1A					
										642	00711	600	FT	TRANSVERSE/DIAGONAL LINE, TYPE 1A, AS PER PLAN				P.46	
										642	01210	500	FT	PARKING LOT STALL MARKING, TYPE 1A					
										642	50010	16	EACH	PAVEMENT MARKING, MISC.: "RESERVED" & "VAN"					
										642	01710	11	EACH	HANDICAP SYMBOL MARKING, TYPE 1A					

R1

GENERAL SUMMARY

BELMONT COUNTY
COURTHOUSE

CALCULATED
RAN
CHECKED
JUA

P.4
P.67