

SHEET NUM.													PART.	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
P.4		P.5		P.8		P.20					R/W PLANS	OFFICE CALCS	01/STR/04						
LS													LS	201	11000	LS		ROADWAY	
				1,804									1,804	202	23000	1,804	SY	CLEARING AND GRUBBING	
				599									599	202	38000	599	FT	PAVEMENT REMOVED	
48													48	SPECIAL	20270000	48	FT	GUARDRAIL REMOVED	P.4
																		FILL AND PLUG EXISTING CONDUIT (5'-0" SPAN X 7'-6" RISE BOX CULVERT)	
						531							531	203	10000	531	CY	EXCAVATION	
						9,700							9,700	203	20000	9,700	CY	EMBANKMENT	
												2,888	2,888	204	10000	2,888	SY	SUBGRADE COMPACTION	
2													2	204	45000	2	HOUR	PROOF ROLLING	
										4			4	623	40500	4	EACH	REFERENCE MONUMENT, TYPE A	
																		EROSION CONTROL	
				51									51	601	32004	51	CY	ROCK CHANNEL PROTECTION, TYPE A WITH GEOTEXTILE FABRIC	
627				149									776	659	00300	776	CY	TOPSOIL	
5,646													5,646	659	10000	5,646	SY	SEEDING AND MULCHING	
0.76													0.76	659	20000	0.76	TON	COMMERCIAL FERTILIZER	
1.17													1.17	659	31000	1.17	ACRE	LIME	
30													30	659	35000	30	MGAL	WATER	
				1,343									1,343	670	00500	1,343	SY	SLOPE EROSION PROTECTION	
													LS	832	15000	LS		STORM WATER POLLUTION PREVENTION PLAN	
													LS	832	15002	LS		STORM WATER POLLUTION PREVENTION INSPECTIONS	
													LS	832	15010	LS		STORM WATER POLLUTION PREVENTION INSPECTION SOFTWARE	
													33,250	832	30000	33,250	EACH	EROSION CONTROL	
																		DRAINAGE	
				LS									LS	503	11100	LS		COFFERDAMS AND EXCAVATION BRACING	
				15									15	503	21100	15	CY	UNCLASSIFIED EXCAVATION	
				8.1									8.1	602	20000	8.1	CY	CONCRETE MASONRY	
345													345	605	31100	345	FT	AGGREGATE DRAINS	
													50	611	01400	50	FT	6" CONDUIT, TYPE E	
50													50	611	01500	50	FT	6" CONDUIT, TYPE F	
50													159	611	28000	159	FT	84" CONDUIT, TYPE A (FOR PIPE ALLOWABLE MATERIALS, SEE CULVERT PLAN AND PROFILE)	
				159															
																		PAVEMENT	
												691	691	301	56000	691	CY	ASPHALT CONCRETE BASE, PG64-22, (449)	
												478	478	304	20000	478	CY	AGGREGATE BASE	
			50									486	536	407	10000	536	GAL	TACK COAT	
			25									94	119	441	70100	119	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (449), PG70-22M	
												131	131	441	70300	131	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (449)	
			25										25	617	10100	25	CY	COMPACTED AGGREGATE	
																		TRAFFIC CONTROL	
				9									9	621	00100	9	EACH	RPM	
				9									9	621	54000	9	EACH	RAISED PAVEMENT MARKER REMOVED	
				0.24									0.24	644	00104	0.24	MILE	EDGE LINE, 6"	
				0.12									0.12	644	00300	0.12	MILE	CENTER LINE	
																		MAINTENANCE OF TRAFFIC	
			100										100	253	02000	100	CY	PAVEMENT REPAIR	
			LS										LS	614	12420	LS		DETOUR SIGNING	
			100										100	614	13000	100	CY	ASPHALT CONCRETE FOR MAINTAINING TRAFFIC	
			31										31	616	10000	31	MGAL	WATER	
																		INCIDENTALS	
													LS	614	11000	LS		MAINTAINING TRAFFIC	
													LS	623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
													LS	623	50000	LS		PRECONSTRUCTION SURVEY MONUMENT VERIFICATION AND REPORT	
													LS	623	51000	LS		POST CONSTRUCTION SURVEY MONUMENT VERIFICATION AND REPORT	
													LS	624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

DESIGN AGENCY

BG

www.bgeengr.com

5560 WILCOX PLACE, SUITE C
DUBLIN, OHIO 43016

DESIGNER

JEP

REVIEWER

RG 05/28/25

PROJECT ID

114435

SHEET

P.7

TOTAL

29