SHEET NUMBER											PART.			ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
3	4	5	6	8	9	10					01/NHS								
																		EROSION CONTROL	
											1,000			832	30000	1,000	EACH	EROSION CONTROL	
																		PAVEMENT	
2,000											2,000			251	01001	2,000	SY	PARTIAL DEPTH PAVEMENT REPAIR (441), AS PER PLAN	3
				209,970							209,970			421	10010	209,970	SY	MICROSURFACING, SURFACE COURSE	
				209,970							209,970			421	10020	209,970	SY	MICROSURFACING, LEVELING COURSE	
				18.15							18.15			618	40600	18.15	MILE	RUMBLE STRIPS, SHOULDER (ASPHALT CONCRETE)	
				3,854							3,854			897	01011	3,854	SY	PAVEMENT PLANING, ASPHALT CONCRETE, CLASS A, AS PER PLAN	3
																		TRAFFIC CONTROL	
						630					630			621	00100	630	EACH	RPM	
						630					630			621	54000	630	EACH	RAISED PAVEMENT MARKER REMOVED	
					0.03						0.03			644	00300	0.03	MILE	CENTER LINE	
					390						390			644	00500	390	FT	STOP LINE	
					308						308			644	00720	308	FT	CHEVRON MARKING	
					750						750			644	00900	750	SF	ISLAND MARKING	
					12						12			644	01300	12	EACH	LANE ARROW	
					3,445						3,445			644	01510	3,445	FT	DOTTED LINE, 6"	
					5,893						5,893			644	30000	5,893	FT	REMOVAL OF PAVEMENT MARKING	
					750						750			644	30010	750	SF	REMOVAL OF PAVEMENT MARKING	
					12						12			644	30020	12	EACH	REMOVAL OF PAVEMENT MARKING	
					27.23						27.23			644	30030	27.23	MILE	REMOVAL OF PAVEMENT MARKING	
					1,750						1,750			807	14310	1,750	FT	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, CHANNELIZING LINE, 12"	
					18.15						18.15			807	14010	18.15	MILE	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, EDGE LINE, 6"	
					9.08						9.08			807	14110	9.08	MILE	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, LANE LINE, 6"	
					27.23						27.23			850	10010	27.23	MILE	GROOVING FOR 6" RECESSED PAVEMENT MARKING, (ASPHALT)	
					1,750						1,750			850	10130	1,750	FT	GROOVING FOR 12" RECESSED PAVEMENT MARKING, (ASPHALT)	
																		MAINTENANCE OF TRAFFIC	
			80								80			614	11110	80	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	
	28										28			614	12460	28	EACH	WORK ZONE MARKING SIGN	
		8									8			614	12484	8	EACH	WORK ZONE INCREASED PENALTIES SIGN	
			50								50			614	12600	50	EACH	REPLACEMENT DRUM	
	27.24										27.24			614	20580	27.24	MILE	WORK ZONE LANE LINE, CLASS III, 6", 642 PAINT	
	0.43										0.43			614	22210	0.43	MILE	WORK ZONE EDGE LINE, CLASS I, 6", 740.06, TYPE I	
	54.45										54.45			614	22360	54.45	MILE	WORK ZONE EDGE LINE, CLASS III, 6", 642 PAINT	
	4,050										4,050			614	23690	4,050	FT	WORK ZONE CHANNELIZING LINE, CLASS III, 12", 642 PAINT	
	924										924			614	26610	924	FT	WORK ZONE STOP LINE, CLASS III, 642 PAINT	
	2,280										2,280			614	24402	2,280	FT	WORK ZONE DOTTED LINE, CLASS I, 6", 740.06, TYPE I	
		12									12			808	18700	12	SNMT	DIGITAL SPEED LIMIT (DSL) SIGN ASSEMBLY	
																		INCIDENTALS	
											100			614	11000		LS	MAINTAINING TRAFFIC	
											100			623	10000		LS	CONSTRUCTION LAYOUT STAKES AND SURVEYING	
											100			624	10000		LS	MOBILIZATION	

GENERAL SUMMARY

DESIGN AGENCY

DESIGNER JBS

REVIEWER MCM 02-05-26

PROJECT ID 118856

SHEET P.7 TOTAL 13

BRO-32-15.29

MODEL: Sheet_SurvFt PAPERSIZE: 34x22 (in.) DATE: 6/18/2026 TIME: 7:54:18 AM PLTDRV: OHDOT_PDF.pltcfg PENTBL: OHDOT_Pen.tbl USER: Joshua.Starlin@dot.ohio.gov WORKSPACE: OHDOTCEv02 WORKSET: 118856 PRODUCT: OpenRoadsDesigner 24.00.00.205
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 09\Brown\118856\400-Engineering\Roadway\Sheets\118856_GG001.dgn