ITEM 614. MAINTAINING TRAFFIC

MAINTAIN ALL EXISTING LANES OF TRAFFIC IN EACH DIRECTION AT ALL TIMES, EXCEPT ACCORDING TO THE PERMITTED LANE CLOSURE TIMES NOTE OR AS SHOWN IN THE PLANS, BY USE OF THE EXISTING PAVEMENT AND THE COMPLETED PAVEMENT.

NO WORK SHALL BE PERFORMED AND ALL EXISTING LANES SHALL BE OPEN TO TRAFFIC DURING THE FOLLOWING DESIGNATED HOLIDAYS OR EVENTS:

CHRISTMAS	FOURTH OF JULY
NEW YEARS	LABOR DAY
MEMORIAL DAY	THANKSGIVING
US JR TRIATHLON -	- (JULY 31, AUG 1 & 2)
VOA METRO PARKS	SOCCER TOURNAMENT

THE PERIOD OF TIME THAT THE LANES ARE TO BE OPEN DEPENDS ON THE DAY OF THE WEEK ON WHICH THE HOLIDAY OR EVENT FALLS. THE FOLLOWING SCHEDULE SHALL BE USED TO DETERMINE THIS PERIOD:

TIME ALL LANES MUST BE OPEN TO TRAFFIC
12:00N FRIDAY THROUGH 6:00 AM MONDAY
12:00N FRIDAY THROUGH 6:00 AM TUESDAY
12:00N MONDAY THROUGH 6:00 AM WEDNESDAY
12:00N TUESDAY THROUGH 6:00 AM THURSDAY
12:00N WEDNESDAY THROUGH 6:00 AM FRIDAY
6:00 AM WEDNESDAY THROUGH 6:00 AM MONDAY
12:00N THURSDAY THROUGH 6:00 AM MONDAY
12:00N FRIDAY THROUGH 6:00 AM MONDAY

*THANKSGIVING ONLY

SHOULD THE CONTRACTOR FAIL TO MEET ANY OF THESE REQUIREMENTS. THE CONTRACTOR SHALL BE ASSESSED A DISINCENTIVE ACCORDING TO THE PERMITTED LANE CLOSURE TIMES & UNAUTHORIZED LANE USE TABLE FOR THE ABOVE DESCRIBED LANE CLOSURE RESTRICTIONS ARE VIOLATED.

LENGTH AND DURATION OF LANE CLOSURES AND RESTRICTIONS SHALL BE AT THE APPROVAL OF THE ENGINEER. IT IS THE INTENT TO MINIMIZE THE IMPACT TO THE TRAVELING PUBLIC. LANE CLOSURES OR RESTRICTIONS OVER SEGMENTS OF THE PROJECT IN WHICH NO WORK IS ANTICIPATED WITHIN A REASONABLE TIME FRAME. AS DETERMINED BY THE ENGINEER. SHALL NOT BE PERMITTED. THE LEVEL OF UTILIZATION OF MAINTENANCE OF TRAFFIC DEVICES SHALL BE COMMENSURATE WITH THE WORK IN PROGRESS.

NOTICE OF CLOSURE SIGNS (W20-H13) SHALL BE ERECTED BY THE CONTRACTOR PRIOR TO THE SCHEDULED ROAD OR RAMP CLOSURE IN ACCORDANCE WITH THE NOTICE OF CLOSURE TIME TABLE BELOW. LAT THE APPROVAL OF THE ENGINEER. PORTABLE CHANGEABLE MESSAGE SIGNS MAY BE USED IN LIEU OF THE STANDARD FLATSHEET SIGN FOR CLOSURE DURATION'S OF LESS THAN 1 WEEK.]

THE SIGNS SHALL BE ERECTED ON THE RIGHT-HAND SIDE OF THE ROAD/RAMP FACING TRAFFIC. THEY SHALL BE PLACED SO AS NOT TO INTERFERE WITH THE VISIBILITY OF ANY OTHER TRAFFIC CONTROL SIGNS. ON ROADWAYS, THEY SHOULD BE ERECTED AT OR NEAR THE POINT OF CLOSURE. THE SIGNS MAY BE ERECTED ANYWHERE ON RAMPS AS LONG AS THEY ARE VISIBLE TO THE MOTORISTS USING THE RAMP. ON ENTRANCE RAMPS, THE SIGN SHALL BE ERECTED WELL IN ADVANCE OF THE MERGE AREA TO AVOID DISTRACTING *MOTORISTS.*

ITEM 614. MAINTAINING TRAFFIC (CONTINUED)

THE SIGN SHALL DISPLAY THE DATE OF THE CLOSURE IN MMM-DD THROUGHOUT THE DURATION OF THE PROJECT. THE CONTRACTOR FORMAT AND THE NUMBER OF DAYS OF THE CLOSURE. THE LAST SHALL NOTIFY THE PROJECT ENGINEER IN WRITING OF ALL LINE OF THE W20-H13 SIGN LISTS A PHONE NUMBER WHICH A TRAFFIC RESTRICTIONS AND UPCOMING MAINTENANCE OF TRAFFIC MOTORIST MAY CALL FOR ADDITIONAL INFORMATION. THIS IS TO CHANGES. THE CONTRACTOR SHALL ENSURE THE WRITTEN BE A SPECIFIC OFFICE WITHIN THE DISTRICT RATHER THAN THE NOTIFICATION IS SUBMITTED IN A TIMELY MANNER TO ALLOW THE GENERAL SWITCHBOARD NUMBER. PROJECT ENGINEER TO MEET THE REQUIRED TIME FRAMES SET FORTH IN THE TABLE BELOW TO INFORM THE SPECIAL HAULING PERMITS SECTION (HAULING.PERMITS@DOT.OHIO.GOV) AND THE NOTICE OF CLOSURE SIGN TIME TABLE ITEM DURATION OF CLOSURE SIGN DISPLAYED TO PUBLIC DISTRICT PUBLIC INFORMATION OFFICE (PIO). THIS NOTIFICATION RAMP & >= 2 WEEKS 14 CALENDAR DAYS PRIOR TO CLOSURE SHALL BE RECEIVED BY THE PROJECT ENGINEER PRIOR TO THE ROAD > 12 HOURS & < 2 WEEKS 7 CALENDAR DAYS PRIOR TO CLOSURE PHYSICAL SETUP OF ANY APPLICABLE SIGNS OR MESSAGE CLOSURES < 12 HOURS 2 BUSINESS DAYS PRIOR TO CLOSURE BOARDS.

THE CONTRACTOR SHALL PROVIDE, ERECT AND MAINTAIN STANDARD 48 X 30 INCH ROAD CLOSED SIGNS, SIGN SUPPORTS, BARRICADES AND LIGHTS, AS DETAILED IN SCD MT-101.60 AT THE FOLLOWING LOCATIONS DURING PERIODS IN WHICH THE AFFECTED ROADS ARE CLOSED TO TRAFFIC.

TYLERSVILLE ROAD. EAST OF THE SOUTHBOUND RAMPS

TYLERSVILLE ROAD, WEST OF THE NORTHBOUND RAMPS

ALL WORK AND TRAFFIC CONTROL DEVICES SHALL BE IN ACCORDANCE WITH C&MS 614 AND OTHER APPLICABLE PORTIONS OF THE SPECIFICATIONS, AS WELL AS THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES. PAYMENT FOR ALL LABOR. EQUIPMENT AND MATERIALS SHALL BE INCLUDED IN THE LUMP SUM CONTRACT PRICE FOR ITEM 614, MAINTAINING TRAFFIC, UNLESS SEPARATELY ITEMIZED IN THE PLAN.

DUST CONTROL

THE CONTRACTOR SHALL FURNISH AND APPLY WATER FOR DUST CONTROL AS DIRECTED BY THE ENGINEER. THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN INCLUDED FOR DUST CONTROL PURPOSES:

ITEM 616, WATER 5 M. GAL

MAINTENANCE OF TRAFFIC PAVEMENT MARKINGS

THE NATURE OF THE WORK TO BE CONDUCTED REQUIRES TEMPORARY PAVEMENT MARKINGS TO BE PLACED AFTER PAVEMENT PLANING AND ASPHALT COURSES ARE PLACED. THE FOLLOWING QUANTITIES HAVE BEEN CARRIED TO THE GENERAL SUMMARY FOR THIS WORK:

614, WORK ZONE LANE LINE, CLASS III, 642 PAINT 0.308 MILES 614, WORK ZONE CENTER LINE, CLASS III, 642 PAINT 0.102 MILES 614. WORK ZONE EDGE LINE. CLASS III. 642 PAINT 0.205 MILES 614, WORK ZONE CHANNELIZING LINE, CLASS III, 642 PAINT 948 FEET 614, WORK ZONE STOP LINE, CLASS III, 642 PAINT 94 FEET

LOCATION DIF	DIRECTION	EX. NO. OF THRU LANES	1 LANE CLOSED		2 LANES CLOSED		3 LANES CLOSED		15 MINUTE SHORT DURATION COMPLETE CLOSURES	COMPLETE CLOSURE	TIME UNIT	DISINCENTIVE PER
	+		WEEKDAY	WEEKEND	WEEKDAY	WEEKEND	WEEKDAY	WEEKEND	ANY DAY	ANY DAY		
I-75*	вотн	4	8 PM - 6 AM	9 PM - 9 AM	10 PM - 5 AM	11 PM TO 7 AM	12 AM - 5 AM	12 AM - 6 AM	12 AM - 4 AM	NONE	1 MINUTE	\$285
	NB -	1	NONE	NONE	NONE	NONE			— 12 AM - 4 AM	NONE	1 MINUTE	\$285
NB EXIT RAMP		2 OR MORE	9 PM - 6 AM	9 PM - 6 AM	9 PM - 6 AM	9 PM - 6 AM				INUINE		
	CD.	1	NONE	NONE	NONE	NONE			- 12 AM - 4 AM	NONE	1 MINUTE	\$285
SB EXIT RAMP	9 SB -	2 OR MORE	9 PM - 6 AM	9 PM - 6 AM	9 PM - 6 AM	9 PM - 6 AM				NONE		
TYLERSVILLE ROAD	EB	2		9 PM - 6 AM	NONE	NONE }	\		- 12 AM - 4 AM	1 OCCURANCE FROM 8 PM SUNDAY TO 6 AM FRIDAY	1 MINUTE	\$90
	WB	VARIES	9 PM - 6 AM		9 PM - 6 AM	9 PM - 6 AM	2	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~				

 \bigcirc

 \bigcirc

 \bigcirc

NOTIFICATION OF TRAFFIC RESTRICTIONS

INFORMATION SHOULD INCLUDE, BUT IS NOT LIMITED TO, ALL CONSTRUCTION ACTIVITIES THAT IMPACT OR INTERFERE WITH TRAFFIC AND SHALL LIST THE SPECIFIC LOCATION. TYPE OF WORK. ROAD STATUS. DATE AND TIME OF RESTRICTION. DURATION OF RESTRICTION, NUMBER OF LANES MAINTAINED, NUMBER OF LANES CLOSED. MINIMUM VERTICAL CLEARANCE. MINIMUM WIDTH OF DRIVABLE PAVEMENT. DETOUR ROUTES. IF APPLICABLE, AND ANY OTHER INFORMATION REQUESTED BY THE PROJECT ENGINEER.

ITEM	DURATION OF CLOSURE	NOTICE DU
RAMP & ROAD CLOSURES	<i>>= 2 WEEKS > 12 HOURS & < 2 WEEKS < 12 HOURS</i>	21 CALENDA 14 CALENDA 4 BUSINES
LANE CLOSURES & RESTRICTIONS	>= 2 WEEKS < 2 WEEKS	14 CALEND 2 BUSINES
START OF CONSTRUCTION & TRAFFIC PATTERN CHANGES	N/A	14 CALENDA

ANY UNFORESEEN CONDITIONS NOT SPECIFIED IN THE PLANS REQUIRING TRAFFIC RESTRICTIONS SHALL ALSO BE REPORTED TO THE PROJECT ENGINEER USING THE NOTIFICATION TIME TABLE.

DISTRICT PUBLIC INFORMATION OFFICER BY EMAIL AT SHORT TERM LANE CLOSURES ARE THOSE WHICH ARE PERMITTED BY THE PERMITTED LANE CLOSURE NOTE. THESE TIMES SHALL DOT.DO8.PIO@DOT.OHIO.GOV DISTRICT PERMIT SECTION BY EMAIL AT DO8.PERMITS@DOT.OHIO.GOV NOT BE REVISED WITHOUT PRIOR APPROVAL FROM THE CENTRAL OFFICE SPECIAL HAUL PERMITS SECTION BY EMAIL AT DISTRICT 8 WORK ZONE TRAFFIC CONTROL MANAGER. SHORT HAULING.PERMITS@DOT.OHIO.GOV TERM LANE CLOSURES SHALL ONLY BE IMPLEMENTED WHEN WORK DISTRICT TRAFFIC. DETOUR SECTION BY EMAIL AT IS BEING CONTINUOUSLY PERFORMED IN THE LANE. THE CLOSURE DOT.DO8.DETOURS@DOT.OHIO.GOV SHALL BE REMOVED AS SOON AS POSSIBLE AFTER WORK HAS STOPPED. PERMITTED LANE CLOSURES SHALL ONLY BE ALLOWED BUTLER COUNTY BY PHONE AT (513) 867-5744 DURING THE TIMES SPECIFIED IN THE PERMITTED LANE CLOSURE TIMES AND UNAUTHORIZED LANE USE TABLE INCLUDED IN THESE PLANS. NO LANE OR SHOULDER CLOSURE SHALL BE IN PLACE WHEN NO WORK IS BEING PERFORMED.

TEMPORARY PAVEMENT WEDGE

TEMPORARY PAVEMENT WEDGES SHALL BE PROVIDED AT ALL TIMES WHERE TRAFFIC IS REQUIRED TO TRAVEL FROM OR ONTO A PAVEMENT SURFACE OF A DIFFERENT ELEVATION, AROUND MANHOLES, AT CATCH BASINS, ETC. THE MINIMUM SLOPE OF THE TEMPORARY PAVEMENT WEDGE SHALL BE 3:1 ALONG LONGITUDINAL JOINTS AND 120:1 AT TRANSVERSE JOINTS. THESE WEDGES SHALL BE REMOVED PRIOR TO PLACING THE SPECIFIED PAVEMENT COURSE. PAYMENT FOR ALL WORK, MATERIALS, ETC. ASSOCIATED WITH THIS ITEM SHALL BE PAID FOR UNDER ITEM 614 MAINTAINING TRAFFIC LUMP SUM.

EXISTING AND TEMPORARY PAVEMENT MARKINGS

THE CONTRACTOR SHALL REMOVE ALL PAVEMENT MARKINGS FROM STA. 11+50 TO STA. 17+00. FOR ALL OTHER AREAS. THE CONTRACTOR SHALL USE WATER BLASTING OR USE AND MAINTAIN BLACK-OUT TAPE TO REMOVE EXISTING PAVEMENT MARKINGS IN CONFLICT WITH THE MOT PLANS. THE CONTRACTOR SHALL USE AND MAINTAIN 740.06 WORK ZONE PAVEMENT MARKINGS, TYPE I PER ODOT CMS.

UE TO OFFICE OF COMMUNICATIONS DAR DAYS PRIOR TO CLOSURE DAR DAYS PRIOR TO CLOSURE SS DAYS PRIOR TO CLOSURE

DAR DAYS PRIOR TO CLOSURE SS DAYS PRIOR TO CLOSURE

DAR DAYS PRIOR TO IMPLEMENTATION

PERMITTED LANE CLOSURE TIMES

S

3

S

S

ſ

m

5

50