


LOCATION MAP

LATITUDE: 39°20'56" LONGITUDE: -84°36'39"



PORTION TO BE IMPROVED	—————
INTERSTATE HIGHWAY	=====
FEDERAL ROUTES	=====
STATE ROUTES	=====
COUNTY & TOWNSHIP ROADS	=====
OTHER ROADS	—————

DESIGN DESIGNATION

	BUT-126 11.1-13.22		BUT-128 12.1-12.23		BUT-128 0.0-0.69		BUT-128 1.56-2.77		BUT-128 2.77-7.78		BUT-128 8.33-8.54		HAM-128 11.0-13.22	
CURRENT ADT (2024)	11,000	16,500	16,500	8,000	11,000	8,800	12,500	6,900						
DESIGN YEAR ADT (2024)	11,000	16,500	8,000	11,000	8,800	13,000	7,000							
DESIGN HOURLY VOLUME (2036)	1,400	2,100	1,000	1,400	1,100	1,700	900							
DIRECTIONAL DISTRIBUTION	61%	61%	70%	70%	70%	70%	70%							
TRUCKS (24 HOUR B&C)	11%	9%	13%	9%	13%	9%	9%							
DESIGN SPEED	40	40	60	40	60	55	60							
LEGAL SPEED	35	35	55	35	55	50	55							
DESIGN FUNCTIONAL CLASSIFICATION:														
05 MAJOR COLLECTOR	(URBAN)	(URBAN)	(RURAL)	(RURAL)	(RURAL)	(URBAN)	(RURAL)							
NHS PROJECT	NO	NO	NO	NO	NO	NO	NO							

DESIGN EXCEPTIONS

NONE

ADA DESIGN WAIVERS

REQUIRED SEE SHEET P.3

UNDERGROUND UTILITIES
 Contact Two Working Days
 Before You Dig

OHIO811.org
 Before You Dig

OHIO811, 8-1-1, or 1-800-362-2764
 (Non members must be called directly)

PLAN PREPARED BY:
 ODOT DISTRICT 8 ENGINEERING
 505 S. SR. 741
 LEBANON, OH 45036

STATE OF OHIO

DEPARTMENT OF TRANSPORTATION

HAM/BUT-SR 128-10.75/0.00

PART 1

CITY OF HAMILTON

SAINT CLAIR TOWNSHIP, FAIRFEILD TOWNSHIP, ROSS TOWNSHIP, AND CROSBY TOWNSHIP

HAMILTON AND BUTLER COUNTY

FOR PART 2, SEE BUT-128-6.62

INDEX OF SHEETS:

TITLE SHEET	1
TYPICAL SECTIONS	2
GENERAL NOTES	3
MAINTENANCE OF TRAFFIC	4-5
PLAN INSERT SHEETS	6-11
BRIDGE NOTES & QUANTITIES	12-13
GENERAL SUMMARY	14-15
SUBSUMMARIES	16-23
PAVEMENT MARKING & SIGNING PLAN	24
CURB RAMP DETAILS	25-27

STANDARD CONSTRUCTION DRAWINGS						SUPPLEMENTAL SPECIFICATIONS	SPECIAL PROVISIONS		
BP-3.1	1/21/22	DM-1.1	7/17/20	MT-99.20	4/19/19	MGS-5.3	7/15/16	800-2023	10/20/23
BP-3.2	1/18/19	DM-1.2	7/16/21	MT-101.70	4/21/28	MGS-6.1	1/19/18	832	7/21/23
BP-4.1	7/19/13			MT-101.75	7/21/23			846	4/17/15
BP-5.1	7/15/22	RM-4.2	4/17/20	MT-105.10	1/17/20			874	4/17/20
BP-7.1	1/20/23			MT-110.10	7/19/13			878	1/21/22
BP-9.1	1/18/19	HW-2.2	7/20/18					902	7/19/19
				TC-41.20	10/18/13			961	4/17/20
MGS-1.1	7/16/21	MT-95.31	7/19/19	TC-42.20	10/18/13				
MGS-2.1	1/19/18	MT-95.32	4/19/19	TC-52.10	10/18/13				
MGS-2.3	1/20/23	MT-95.50	7/21/17	TC-52.20	1/15/21				
MGS-4.2	7/19/13	MT-95.60	4/19/19	TC-61.30	7/19/19				
MGS-4.3	1/18/13	MT-96.11	7/21/23	TC-64.10	7/21/23				
		MT-96.20	7/21/23	TC-65.10	1/17/14				
AS-1-15	1/20/23	MT-96.26	1/18/19	TC-65.11	7/15/22				
DBR-3-11	7/15/11	MT-97.10	4/19/19	TC-71.10	4/26/23				
		MT-97.12	1/20/17	TC-74.10	1/20/23				

FEDERAL PROJECT NUMBER

E161(461)

RAILROAD INVOLVEMENT

NONE

PROJECT DESCRIPTION

RESURFACING OF A PORTION OF SR 128 IN BUTLER AND HAMILTON COUNTIES.

EARTH DISTURBED AREAS

PROJECT EARTH DISTURBED AREA:	2.7 ACRES
ESTIMATED CONTRACTOR EARTH DISTURBED AREA:	N/A ACRES
NOTICE OF INTENT EARTH DISTURBED AREA:	N/A (NOI NOT REQUIRED)*

*ROUTINE MAINTENANCE PROJECT

2023 SPECIFICATIONS

THE STANDARD SPECIFICATIONS OF THE STATE OF OHIO, DEPARTMENT OF TRANSPORTATION, INCLUDING SUPPLEMENTAL SPECIFICATIONS LISTED IN THE PLANS, CHANGES LISTED IN THE PROPOSAL, AND THE SUPPLEMENTAL SPECIFICATION 800 VERSION INDICATED ON THE TITLE SHEET SHALL GOVERN THIS IMPROVEMENT.

I HEREBY APPROVE THESE PLANS AND DECLARE THAT THE MAKING OF THIS IMPROVEMENT WILL NOT REQUIRE THE CLOSING TO TRAFFIC OF THE HIGHWAY AND THAT PROVISIONS FOR THE MAINTENANCE AND SAFETY OF TRAFFIC WILL BE AS SET FORTH ON THE PLANS AND ESTIMATES.

DISTRICT DEPUTY DIRECTOR

Terry K Campbell

DIRECTOR, DEPARTMENT OF TRANSPORTATION

Jack Markant

ENGINEER'S SEAL



DESIGN AGENCY	
DESIGNER	GAT
REVIEWER	KSD 07-07-23
PROJECT ID	102544
SHEET	P.1
TOTAL	27

