

MODEL: Sheet PAPER:SIZE: 34x22 (in.) DATE: 1/14/2026 TIME: 7:40:11 AM PLTDRV: OHDOT_PDF.plt PENTBL: OHDOT_Pen.tbl USER: Camron.Pollie@dolOhio.gov WORKSPACE: OHDOTCEV02 WORKSET: 111949 PRODUCT: OpenRoadsDesigner 24.00.00.205 pwc:\ohdot\oh-pw.bentley.com\ohdot-pw-02\Documents\01 Active Projects\District 07\Champaign\111949\400-Engineering\Roadway\Sheets\111949_GG001.dgn

SHEET NUMBER													PART.	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
							3	4	6	7	8		01/5<2						
																		ROADWAY	
							3						3	623	39500	3	EACH	MONUMENT ASSEMBLY ADJUSTED TO GRADE	
																		DRAINAGE	
							2						2	611	99654	2	EACH	MANHOLE ADJUSTED TO GRADE	10
																		PAVEMENT	
							500						500	251	01001	500	SY	PARTIAL DEPTH PAVEMENT REPAIR (441), AS PER PLAN	3
									27,433				27,433	254	01000	27,433	SY	PAVEMENT PLANING, ASPHALT CONCRETE, 1 ½" DEPTH	
							300						300	254	01601	300	SY	PATCHING PLANED SURFACE, AS PER PLAN	3
									2,332				2,332	407	20000	2,332	GAL	NON-TRACKING TACK COAT, 0.085 GAL/SY	
									1,143				1,143	441	50100	1,143	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG70-22M, 1 ½" THICKNESS	
									94				94	617	10100	94	CY	COMPACTED AGGREGATE, 1" AVERAGE THICKNESS	
																		WATER WORK	
							4						4	638	10800	4	EACH	VALVE BOX ADJUSTED TO GRADE	3
																		TRAFFIC CONTROL	
											50		50	621	00100	50	EACH	RPM	
											50		50	621	54000	50	EACH	RAISED PAVEMENT MARKER REMOVED	
										2.50			2.50	644	00100	2.50	MILE	EDGE LINE, 4"	
							0.40						0.40	644	00104	0.40	MILE	EDGE LINE, 6"	
							1.62						1.62	644	00300	1.62	MILE	CENTER LINE	
							192						192	644	00400	192	FT	CHANNELIZING LINE, 8"	
							52						52	644	00500	52	FT	STOP LINE	
										64			64	644	00620	64	FT	CROSSWALK LINE, 12"	
										60			60	644	00630	60	FT	CROSSWALK LINE, 24"	
										2			2	644	01300	2	EACH	LANE ARROW, LEFT	
										2			2	644	01300	2	EACH	LANE ARROW, RIGHT	
										15			15	644	20800	15	FT	YIELD LINE	
																		TRAFFIC SIGNALS	
							2						2	632	26501	2	EACH	DETECTOR LOOP, AS PER PLAN	3
							2						2	632	27201	2	EACH	LOOP DETECTOR TIE IN, AS PER PLAN	3
																		MAINTENANCE OF TRAFFIC	
								20					20	614	11110	20	hour	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	
							3.24						3.24	614	21100	3.24	MILE	WORK ZONE CENTER LINE, CLASS I, 642 PAINT	
							5.00						5.00	614	22100	5.00	MILE	WORK ZONE EDGE LINE, CLASS I, 4", 642 PAINT	
							0.80						0.80	614	22110	0.80	MILE	WORK ZONE EDGE LINE, CLASS I, 6", 642 PAINT	
							384						384	614	23200	384	FT	WORK ZONE CHANNELIZING LINE, CLASS I, 8", 642 PAINT	
										104			104	614	26200	104	FT	WORK ZONE STOP LINE, CLASS I, 642 PAINT	
							4						4	614	30200	4	EACH	WORK ZONE ARROW, CLASS I, 642 PAINT, LEFT	
							4						4	614	30200	4	EACH	WORK ZONE ARROW, CLASS I, 642 PAINT, RIGHT	
													LS	614	11000	LS		INCIDENTALS	
													LS	624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

DESIGN AGENCY



DESIGNER

CJP

REVIEWER

BJA MM-DD-YY

PROJECT ID

111949

SHEET

P.5

TOTAL

11

PAVEMENT MARKING SUBSUMMARY	
DESIGN AGENCY	
	
DESIGNER	
CJP	
REVIEWER	
BJA MM-DD-YY	
PROJECT ID	
111949	
SHEET	TOTAL
P.7	11