

STATE OF OHIO DEPARTMENT OF TRANSPORTATION

CLE-SR 133-22.00

JACKSON TOWNSHIP, WAYNE TOWNSHIP,
WILLIAMSBURG TOWNSHIP,
CLERMONT COUNTY

FEDERAL PROJECT NUMBER

E230(715)

RAILROAD INVOLVEMENT

NONE

PROJECT DESCRIPTION

RESURFACING SR 133 IN CLERMONT COUNTY BETWEEN SLM 22.00 TO 31.16. PAVEMENT EDGE REPLACEMENT BETWEEN SLM 28.01 TO 31.16. RESURFACING THE RAMPS AT THE SR 133 AND SR 32 INTERCHANGE

EARTH DISTURBED AREAS

PROJECT EARTH DISTURBED AREA: 4.84 ACRES
ESTIMATED CONTRACTOR EARTH DISTURBED AREA: N/A
NOTICE OF INTENT EARTH DISTURBED AREA: N/A (NOI NOT REQUIRED) *
*ROUTINE MAINTENANCE PROJECT

2023 SPECIFICATIONS

THE STANDARD SPECIFICATIONS OF THE STATE OF OHIO, DEPARTMENT OF TRANSPORTATION, INCLUDING SUPPLEMENTAL SPECIFICATIONS LISTED IN THE PLANS, CHANGES LISTED IN THE PROPOSAL, AND THE SUPPLEMENTAL SPECIFICATION 800 VERSION INDICATED ON THE PROPOSAL SHALL GOVERN THIS IMPROVEMENT.

I HEARBY APPROVE THESE PLANS AND DECLARE THAT THE MAKING OF THIS IMPROVEMENT WILL REQUIRE THE PART TIME CLOSING TO TRAFFIC OF THE HIGHWAY AS NOTED ON SHEET 6. DURING WHICH TIME DETOURS WILL BE PROVIDED AS SHOWN HEREIN. PROVISIONS FOR MAINTENANCE AND SAFETY OF TRAFFIC WILL BE AS SET FORTH ON THE PLANS AND ESTIMATES.

Terry K Campbell

District Deputy Director

Jack Marchbanks

Jack Marchbanks, PhD
Director, Department of Transportation

INDEX OF SHEETS:

TITLE SHEET	1
PROJECT LOCATION	2-4
GENERAL NOTES	5
MAINTENANCE OF TRAFFIC	6,7
SR 133 DETOUR	8,9
GENERAL SUMMARY	10
PAVEMENT CALCULATIONS	11
PAVEMENT MARKINGS	12

SEE SHEETS 2-4

LOCATION MAP

LATITUDE: 39°13'53" LONGITUDE: -84°07'00"

DESIGN DESIGNATION	CLE-SR 133 22.18-25.49	CLE-SR 133 25.49-28.00	CLE-SR 133 28.00-31.16	CLE-SR 133 TO SR 32W	CLE-SR 32W TO SR 133	CLE-SR 32E TO SR 133	CLE-SR 133 TO SR 32E
CURRENT ADT (2023)	2,100	950	2,300	2,300	2,300	2,300	2,300
DESIGN YEAR ADT (2035)	2,200	950	2,300	2,300	2,300	2,300	2,300
DESIGN HOURLY VOLUME (2035)	300	100	300	300	300	300	300
DIRECTIONAL DISTRIBUTION	55.5%	54.7%	55.5%	55.5%	55.5%	55.5%	55.5%
TRUCKS (24 HOUR B&C)	4%	5%	3%	3%	3%	3%	3%
DESIGN SPEED							
LEGAL SPEED							
DESIGN FUNCTIONAL CLASSIFICATION: 03 PRINCIPAL ATRERIAL CLE-32 RAMPS (URBAN). 05 MAJOR COLLECTOR CLE-133 22.18-27.99 (RURAL) 05 MAJOR COLLECTOR CLE-133 28.01-31.16 (RURAL)							
NHS PROJECT	NO						

DESIGN EXCEPTIONS

NONE

ADA DESIGN WAIVERS

NONE

UNDERGROUND UTILITIES
Contact Two Working Days
Before You Dig


OHIO811.org
Before You Dig

OHIO811, 8-1-1, or 1-800-362-2764
(Non members must be called directly)

PLAN PREPARED BY:
ODOT DISTRICT 8 ENGINEERING
505 S. STATE ROUTE 741
LEBANON, OHIO 45036

STANDARD CONSTRUCTION DRAWINGS				SUPPLEMENTAL SPECIFICATIONS	SPECIAL PROVISIONS
BP-3.1	1/21/22	MT-98.30	7/16/21	800-2023	7/21/23
BP-3.2	1/18/19	MT-99.20	4/19/19	807	1/31/22
BP-4.1	7/19/13	MT-101.60	4/26/23	821	4/20/12
		MT-101.90	7/17/20	832	7/15/22
MGS-1.1	7/16/21	MT-105.10	1/17/20	850	4/15/22
MGS-2.1	1/19/18			878	1/21/22
MGS-4.3	1/18/13	TC-61.30	7/19/19		
MGS-5.3	7/15/16	TC-65.10	1/17/14		
		TC-65.11	7/15/22		
MT-97.10	4/19/19	TC-73.20	1/17/20		
MT-97.12	1/20/17				
MT-98.10	1/17/20				
MT-98.11	1/17/20				
MT-98.20	4/19/19				
MT-98.22	1/17/20				
MT-98.29	1/17/20				

ENGINEER'S SEAL

ROADWAY



TITLE SHEET

DESIGN AGENCY



DESIGNER

JED

REVIEWER

JDO 5/12/2023

PROJECT ID

113982

SHEET TOTAL

P.1 12

CLE-SR 133-22.00

MODEL: Sheet PAPER: 17x11 (in.) DATE: 9/21/2023 TIME: 8:51:12 AM USER: jday64 pwc\ohiodot-pw-bentley.com\shahid-pw-02\Documents\01 Active Projects\District 08\Clermont\113982\40-Engineering\Roadway\Sheets\113982_GT001.dgn