

ESTIMATED QUANTITIES - STRUCTURE No.: CLI-133-0211 (01/STR FUNDING SPLIT)									
ITEM	EXTENSION	TOTAL	UNIT	DESCRIPTION	ABUT.	PIERS	SUPER.	GEN.	SEE SHEET
202	11203	LS	LS	PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN	LUMP	LUMP	LUMP		
202	22900	140	SY	APPROACH SLAB REMOVED				140	
503	11101	LS	LS	COFFERDAMS AND EXCAVATION BRACING, AS PER PLAN				LUMP	
503	21300	LS	LS	UNCLASSIFIED EXCAVATION				LUMP	
505	11100	LS	LS	PILE DRIVING EQUIPMENT MOBILIZATION	LUMP	LUMP			
507	00602	560	FT	14" CAST-IN-PLACE REINFORCED CONCRETE PILES, DRIVEN WITH QC/QA	80	480			
507	00650	630	FT	14" CAST-IN-PLACE REINFORCED CONCRETE PILES, FURNISHED	90	540			
507	93300	14	EACH	STEEL POINTS OR SHOES	2	12			
523	20000	4	EACH	DYNAMIC LOAD TESTING	2	2			
509	26000	35628	LB	GALVANIZED STEEL REINFORCEMENT	4453	3248	27927		
510	10001	264	EACH	DOWEL HOLES WITH NON-SHRINK, NON-METALLIC GROUT, AS PER PLAN	264				
511	33312	142	CY	CLASS QC2 CONCRETE WITH QC/QA, SUPERSTRUCTURE		32	110		
511	45712	18	CY	CLASS QC1 CONCRETE WITH QC/QA, ABUTMENT	18				
512	10100	127	SY	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)	32	68	27		
512	33000	14	SY	TYPE 2 WATERPROOFING	14				
514	00050	541	SF	SURFACE PREPARATION OF EXISTING STRUCTURAL STEEL	15	526			
514	00056	541	SF	FIELD PAINTING OF EXISTING STRUCTURAL STEEL, PRIME COAT	15	526			
514	00060	449	SF	FIELD PAINTING OF EXISTING STRUCTURAL STEEL, INTERMEDIATE COAT		449			
514	00066	449	SF	FIELD PAINTING OF EXISTING STRUCTURAL STEEL, FINISH COAT		449			
516	13200	172	SF	½" PREFORMED EXPANSION JOINT FILLER	172				
516	13600	108	SF	1" PREFORMED EXPANSION JOINT FILLER	108				
516	14014	84	FT	INTEGRAL ABUTMENT EXPANSION JOINT SEAL	84				
517	70100	126.13	FT	RAILING (THREE STEEL TUBE BRIDGE RAILING)			126.13		
518	21200	55	CY	POROUS BACKFILL WITH GEOTEXTILE FABRIC	55				
SPECIAL	51822300	139	FT	STEEL DRIP STRIP			139		
518	40000	124	FT	6" PERFORATED CORRUGATED PLASTIC PIPE	124				
518	40010	100	FT	6" NON-PERFORATED CORRUGATED PLASTIC PIPE, INCLUDING SPECIALS	100				
526	25001	186	SY	REINFORCED CONCRETE APPROACH SLABS (T=13"), AS PER PLAN				186	
526	90011	80	FT	TYPE A INSTALLATION, AS PER PLAN				80	
846	00110	23.74	CF	POLYMER MODIFIED ASPHALT EXPANSION JOINT SYSTEM				23.74	

STRUCTURE ESTIMATED QUANTITIES
BRIDGE No.: CLI-133-0211
OVER WHITAKERS RUN

SFN
1402641

DESIGN AGENCY

DESIGNER
GTF

CHECKER
BCP

REVIEWER
CAH 11/07/25

PROJECT ID
102750

SUBSET
3

TOTAL
15

SHEET
20

TOTAL
31