

I:\Project+Data\CLI\09678_CLI-350-4.20\Design\Roadway\Sheets\09678_CS001.dgn Sheet 2/19/2021 2:05:35 PM jdavis4

SHEET NUM.					PART.		ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
3	4	6	7	01/STR/PV	02/SAF/OT							
											PAVEMENT	
	400					400	253	02000	400	CY	PAVEMENT REPAIR	
			5,003			5,003	407	20000	5,003	GAL	NON-TRACKING TACK COAT	
			1,930			1,930	441	50000	1,930	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	
			181			181	617	10100	181	CY	COMPACTED AGGREGATE	
			4,353			4,353	617	20000	4,353	SY	SHOULDER PREPARATION	
				4		4	617	25000	4	MGAL	WATER	
				3.71			618	43000	3.71	MILE	RUMBLE STRIPES, CENTER LINE (ASPHALT CONCRETE)	
				19,588			874	20000	19,588	FT	LONGITUDINAL JOINT PREPARATION	7
				55,583			897	01010	55,583	SY	PAVEMENT PLANING, ASPHALT CONCRETE, CLASS A, 1"	
				556			897	02000	556	SY	PATCHING PLANED SURFACE	
											TRAFFIC CONTROL	
	245					245	621	00100	245	EACH	RPM	
	245					245	621	54000	245	EACH	RAISED PAVEMENT MARKER REMOVED	
				7.42			644	00104	7.42	MILE	EDGE LINE, 6"	
				105			644	00400	105	FT	CHANNELIZING LINE, 8"	
				15			644	00500	15	FT	STOP LINE	
				3.71			644	00300	3.71	MILE	CENTER LINE	
											MAINTENANCE OF TRAFFIC	
			3.71				614	21550	3.71	MILE	WORK ZONE CENTER LINE, CLASS III, 642 PAINT	
			7.42				614	22350	7.42	MILE	WORK ZONE EDGE LINE, CLASS III, 4", 642 PAINT	
			15				614	26610	15	FT	WORK ZONE STOP LINE, CLASS III, 642 PAINT	
											INCIDENTALS	
							LUMP	614	11000	LS	MAINTAINING TRAFFIC	
							LUMP	623	10001	LS	CONSTRUCTION LAYOUT STAKES AND SURVEYING, AS PER PLAN	3
							LUMP	624	10000	LS	MOBILIZATION	

GENERAL SUMMARY

CLI-SR 350-4.20

I:\ProjectData\CLI\09678_CLI-350-4.20\Design\Roadway\Sheets\09678_PM001.dgn Sheet 2/19/2021 12:25:41 AM jdav1s4

PART	COUNTY-ROUTE	LOG POINT (MILE)		TOTAL MILE	644		644		644	618	874	REMARKS
		FROM	TO		EDGE LINE 6"		STOP LINE FEET	8"CHANNELIZING LINE FEET	CENTER LINE RUMBLE STRIPES (ASPHALT CONCRETE) MILE	LONGITUDINAL JOINT PREPARATION FEET		
					WHITE MILE						DASHED MILE	
01/STR/PV	CLI-350	4.20	7.91	3.71	7.42		0.28	3.43	15	105	3.71	19588
TOTALS CARRIED TO GENERAL SUMMARY					7.42		3.71		15	105	3.71	19588

CALCULATED
JED
CHECKED
JDO

PAVEMENT MARKINGS

CLI-SR 350-4.20

7
7