SHEET NUM.										PART.				ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
P.013	P.015	P.016	P.017	P.022	P.023	P.024	P.025	P.029		01/NHS/PV	02/BRO/BR	03/SAF/OT							
																		STRUCTURE REPAIR (CRA-30-2079 LEFT)	
								22			22			407	13900	22	GAL	TACK COAT, 702.13 (0.08 GAL/SY)	
								113			113			409	30001	113	FT	SAWING AND SEALING ASPHALT CONCRETE PAVEMENT JOINTS, AS PER PLAN	P.0.28
								1,416			1,416			512	73500	1,416	SY	TREATING CONCRETE BRIDGE DECKS WITH GRAVITY FED RESIN	
								123			123			516	31000	123	FT	JOINT SEALER	
								1			1			861	11100	1	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, 12.5 MM, TYPE A (446) (VARIABLE THICKNESS)	
								1,311			1,311			897	01021	1,311	SY	PAVEMENT PLANING, ASPHALT CONCRETE, CLASS B, AS PER PLAN (VARIABLE THICKNESS)	P.028
																		STRUCTURE REPAIR (CRA-30-2078 RIGHT)	
								18			18			407	13900	18	GAL	TACK COAT, 702.13 (0.08 GAL/SY)	
								91			91			409	30001	91	FT	SAWING AND SEALING ASPHALT CONCRETE PAVEMENT JOINTS, AS PER PLAN	P.0.28
								1,151			1,151			512	73500	1,151	SY	TREATING CONCRETE BRIDGE DECKS WITH GRAVITY FED RESIN	
								100			100			516	31000	100	FT	JOINT SEALER	
								1			1			861	11100	1	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, 12.5 MM, TYPE A (446) (VARIABLE THICKNESS)	
								1,075			1,075			897	01021	1,075	SY	PAVEMENT PLANING, ASPHALT CONCRETE, CLASS B, AS PER PLAN (VARIABLE THICKNESS)	P.028
																		MAINTENANCE OF TRAFFIC	
			240							240				614	11110	240	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	
										LS				614	12420	LS		DETOUR SIGNING	
	12									12				614	12460	12	EACH	WORK ZONE MARKING SIGN	
		12								12				614	12484	12	EACH	WORK ZONE INCREASED PENALTIES SIGN	
	25									25				614	13000	25	CY	ASPHALT CONCRETE FOR MAINTAINING TRAFFIC	
		36								36				614	18600	36	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN	
					38.4					38.4				614	20560	38.4	MILE	WORK ZONE LANE LINE, CLASS III, 6", 642 PAINT	
					42					42				614	22360	42	MILE	WORK ZONE EDGE LINE, CLASS III, 6", 642 PAINT (WHITE)	
					42					42				614	22360	42	MILE	WORK ZONE EDGE LINE, CLASS III, 6", 642 PAINT (YELLOW)	
					22,344					22,344				614	23690	22,344	FT	WORK ZONE CHANNELIZING LINE, CLASS III, 12", 642 PAINT	
					544					544				614	26610	544	FT	WORK ZONE STOP LINE, CLASS III, 642 PAINT	
		72								72				808	18700	72	SNMT	DIGITAL SPEED LIMIT (DSL) SIGN ASSEMBLY	
																		INCIDENTALS	
										LS	LS	LS		614	11000	LS		MAINTAINING TRAFFIC	
										4	1	1		619	16020	6	MNTH	FIELD OFFICE, TYPE C	
										LS	LS	LS		623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
										LS	LS	LS		624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

CRA-30-15.80

MODEL: Gen Sum 2 PAPERSIZE: 17x11 (in.) DATE: 01/07/2022 TIME: 13:12:22 USER: kknapp
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 03\Crawford\91097\400-Engineering\Roadway\Sheets\91097_GG001.dgn

DESIGN AGENCY
DISTRICT 3
ENGINEERING TEAM ONE

DESIGNER
KCK

REVIEWER
NRF 09/01/21

PROJECT ID
91097

SHEET P.021 TOTAL P.039