GENERAL CONSTRUCTION INTERIM COMPLETION DATE:

CONSTRUCTION OF THIS PROJECT (EXCEPT ITEM 514 PAINTING OF STRUCTURAL STEEL) SHALL BE COMPLETED AND THE BRIDGE SHALL BE FULLY OPEN TO TRAFFIC BY 10/31/2022. CONSTRUCTION OF ITEM 514 PAINTING OF STRUCTURAL STEEL SHALL BE COMPLETED BY 6/30/2023.

UTILITIES

LISTED BELOW ARE ALL UTILITIES LOCATED WITHIN THE PROJECT CONSTRUCTION LIMITS TOGETHER WITH THEIR RESPECTIVE OWNERS:

CITY OF INDEPENDENCE SEWERS: 6800 BRECKSVILLE ROAD INDEPENDENCE, OHIO 44131 ATTN.: DONALD RAMM PHONE: (216) 524-1374 rammdo@independenceohio.org WATER: CITY OF CLEVELAND DIVISION OF WATER 1201 LAKESIDE AVENUE CLEVELAND, OHIO 44114 ATTN.: FRED ROBERTS PHONE: (216) 664-2444 x75590 fred_roberts@clevelandwater.com TELEPHONE: AT&T LOCAL 13630 LORAIN AVENUE - 2ND FLOOR GAS: CLEVELAND, OHIO 44111 ATTN.: JAMES JANIS PHONE: (216) 476-6142 FAX: (216) 476-6013 pj8191@att.com AT&T TRANSMISSION/LONG LINES 755 EAST PLEASANT VALLEY ROAD, SUITE 140 INDEPENDENCE, OHIO 44131 ATTN.: MIKE DIEDERICH PHONE: (216) 750-0135 md4145@att.com AT&T LNS/METRO THAYER POWER AND COMMUNICATION, LLC 12345 WORTHINGTON ROAD NW PATASKALA, OHIO 43062 ATTN.: CHRIS MCCLOSKEY

PHONE: (614) 379-6419 ChrisMcCloskey@thayerpc.com

CENTURYLINK 400 CHESTER AVENUE CLEVELAND. OHIO 44103 ATTN .: DOUG HOLLOWAY PHONE: (440) 906-6284 doug.holloway@centurylink.com

CHARTER COMMUNICATIONS 7 SEVERENCE CIRCLE CLEVELAND HEIGHTS, OHIO 44118 ATTN.: PAT SANTOIEMMO PHONE: (216) 575-8016 EXT. 12165554202 FAX: (216) 581-3262 Pat.Santoiemmo@charter.com

CROWN CASTLE 15565 NEO PKWY GARFIELD HEIGHTS. OHIO 44128 ATTN.: JON TARNOWSKI PHONE: (585) 445-5813 Jon.Tarnowski@crowncastle.com

WINDSTREAM LEON TAYLOR ATTN.: 50 EXECUTIVE PKWY HUDSON, OHIO 44236 PHONE: (330) 650-7663 Leon.Taylor@windstream.com MARK MILLS 102 EAST SHAFER STREET FORSYTH, ILLINOIS 62535 PHONE: (217) 460-0002 Mark.Mills@windstream.com WOWI CABLE 105 BLAZE INDUSTRIAL PARKWAY BEREA, OHIO 44017 JOSEPH AULT ATTN.: PHONE: (216) 904-6476 ioseph.ault@wowinc.com ZAYO FIBER SOLUTIONS 4199 KINROSS LAKES PARKWAY RICHFIELD. OHIO 44286 ATTN.: COLTON WOODRUFF PHONE: (419) 631-1303 colton.woodruff@zayo.com ELECTRIC: CEI FIRST ENERGY 6896 MILLER ROAD. SUITE 101 BRECKSVILLE, OHIO 44141 ATTN.: JOHN ZASSICK PHONE: (440) 546-8706 jmzassick@firstenergycorp.com DOMINION ENERGY OHIO 320 SPRINGSIDE DRIVE, SUITE 320 AKRON, OHIO 44333 AARON CONANT ATTN.: PHONE: (330) 664-2451 k.aaron.conant@dominionenergy.com ODOT LIGHTING: ODOT DISTRICT 12 25609 EMERY ROAD WARRENSVILLE HEIGHTS, OHIO 44128 ATTN.: DAVID NIMRICHTER SR. PHONE: (216) 584-2296 david.nimrichter@dot.ohio.gov THE LOCATION OF THE UNDERGROUND UTILITIES SHOWN ON THE PLANS ARE AS OBTAINED FROM THE OWNERS AS REQUIRED BY SECTION 153.64 O.R.C. FOR COORDINATION REGARDING THE TORNADO WARNING SIREN LOCATED AT THE SOUTHWEST BRIDGE CORNER, CONTACT: CITY OF INDEPENDENCE 6800 BRECKSVILLE ROAD INDEPENDENCE, OHIO 44131 ATTN.: DONALD RAMM PHONE: (216) 524-1374 rammdo@independenceohio.ora DOMINION EAST OHIO GAS FACILITIES

IT IS THE CONTRACTOR'S RESPONSIBILITY TO MAINTAIN THE LATERAL AND SUBJACENT SUPPORT OF DOMINION ENERGY'S PIPELINE(S), IN COMPLIANCE TO 29 CFR, PART 1926, SUBPART P, (SAFE EXCAVATION & SHORING). ONE-FOOT MINIMUM VERTICAL AND HORIZONTAL CLEARANCE MUST BE MAINTAINED BETWEEN DOMINION ENERGY OHIO'S (DEO) EXISTING PIPELINE(S) AND ALL OTHER IMPROVEMENTS. EXTREME CARE SHOULD BE TAKEN NOT TO HARM ANY DEO FACILITY (PIPELINES, ETC.) OR APPURTENANCE (PIPE COATING, TRACER WIRE, CATHODIC PROTECTION TEST STATION WIRES & DEVICES, VALVE BOXES, ETC.). DEO FACILITIES MUST BE PROTECTED WITH A TARP DURING BRIDGE CONSTRUCTION. THE CONTRACTOR WILL BE RESPONSIBLE AND LIABLE FOR ENSURING THAT ALL DEO EXISTING FACILITIES, ABOVE AND BELOW GROUND, REMAIN UNDAMAGED, ACCESSIBLE, AND IN WORKING ORDER. THE CROSSING OF DEO'S PIPELINE WITH ANOTHER STEEL FACILITY MAY CREATE A POTENTIAL CORROSION ISSUE FOR THE PROPOSED FACILITY AND THE EXISTING DEO FACILITY. PLEASE CONTACT DOMINION EAST OHIO'S CORROSION DEPARTMENT: DAVE CUTLIP (330-266-2121). RICK MCDONALD (330-266-2122). OR AL HUMRICHOUSER (330-478-3757).

COORDINATION WITH OTHER CONTRACTORS

IN ADDITION TO THE REQUIREMENTS OF C&MS 105.08, THE FOLLOWING PROJECTS ARE KNOWN TO BE WORKING CONCURRENTLY:

"BRECKSVILLE ROAD IMPROVEMENTS" PROJECT FOR THE CITY OF INDEPENDENCE.

THE ODOT PROJECT CUY-480-18.42 (PID 90591), I.R. 480 BRIDGE OVER THE CUYAHOGA RIVER VALLEY, INCLUDING APPROACH ROADWAY WORK ON THE MAINLINE AND I.R. 77 INTERCHANGE RAMPS.

ODOT PROJECT CUY-21-8.22 (PID 89257), RESURFACING OF BRECKSVILLE ROAD FROM ROCKSIDE ROAD TO GRANGER ROAD.

GREATER CLEVELAND REGIONAL TRANSIT AUTHORITY (GCRTA)

THE CONTRACTOR SHALL NOTIFY GCRTA FIVE (5) DAYS PRIOR TO THE IMPLEMENTATION OF MAINTENANCE OF TRAFFIC OPERATIONS.

CONSTRUCTION NOISE

ACTIVITIES AND LAND USE ADJACENT TO THIS PROJECT MAY BE AFFECTED BY CONSTRUCTION NOISE. A NOISE WAIVER HAS BEEN GRANTED BY THE CITY OF INDEPENDENCE FOR DEMOLITION AND DECK POURING ACTIVITIES ONLY. CONDUCT ALL OPERATIONS TO MINIMIZE THE NOISE AND COMPLY WITH SPECIFICATION 107.

SURVEYING PARAMETERS

PRIMARY PROJECT CONTROL MONUMENTS GOVERN ALL POSITIONING ON ODOT PROJECTS. SEE THIS SHEET FOR A TABLE CONTAINING PROJECT CONTROL INFORMATION.

USE THE FOLLOWING PROJECT CONTROL, VERTICAL POSITIONING, AND HORIZONTAL POSITIONING PARAMETERS FOR ALL SURVEYING:

PROJECT CONTROL

POSITIONING METHOD: MONUMENT TYPE:	RTK GPS B
VERTICAL POSITIONING ORTHOMETRIC HEIGHT DATUM: GEOID:	NAVD88 BOOTTON 1200NE (3401)
HORIZONTAL POSITIONING REFERENCE FRAME:	NAD83(2011)
ELLIPSOID: GRS80 MAP PROJECTION:	LAMBERT CONFORMAL CONIC
COORDINATE SYSTEM:	OHIO STATE PLANE

COMBINED SCALE FACTOR: 0.99923526889 ORIGIN OF COORDINATE SYSTEM: X=0. Y=0

USE THE POSITIONING METHODS AND MONUMENT TYPE USED IN THE ORIGINAL SURVEY TO RESTORE ALL MONUMENTS RELATED TO PRIMARY PROJECT CONTROL THAT ARE DAMAGED OR DESTROYED BY CONSTRUCTION ACTIVITIES. RESTORE THE DAMAGED OR DESTROYED MONUMENTS IN ACCORDANCE WITH CMS 623.

UNITS ARE IN U.S. SURVEY FEET.

PRIMARY PROJECT CONTROL INFORMATION

POINT	NORTHING	EASTING	ELEV.	FEATURE
2	635144.314	2204572.204	726.82	CMONS
202	635632.070	2204454.412	715.90	CNPT-IPINS

WORK LIMITS

THE WORK LIMITS SHOWN ON THESE PLANS ARE FOR PHYSICAL CONSTRUCTION ONLY. PROVIDE THE INSTALLATION AND OPERATION OF ALL WORK ZONE TRAFFIC CONTROL AND WORK ZONE TRAFFIC CONTROL DEVICES REQUIRED BY THESE PLANS WHETHER INSIDE OR OUTSIDE THESE WORK LIMITS.

 \bigcirc

 \bigcirc

 \bigcirc

 \bigcirc

PROJECT PARTICIPATION SPLITS

THE FOLLOWING PARTICIPATION SPLITS ARE PRESENT WITHIN THIS PROJECT:

01/BRO/BR	PROJECT
02/NFP/BR	CITY OF INDEPENDENCE
03/NFP/BR	CROWN CASTLE
04/NFP/BR	CENTURYLINK
05/NFP/BR	WINDSTREAM
06/NFP/BR	CHARTER COMMUNICATIONS

ITEM 202 - PAVEMENT REMOVED, AS PER PLAN

PAVEMENT REMOVAL SHALL INCLUDE THE REMOVAL OF CONCRETE BASE, WEARING COURSE AND INTEGRAL CONCRETE CURB. ALL OTHER REQUIREMENTS OF C&MS 202 SHALL STILL APPLY.

CLEARING AND GRUBBING

ALTHOUGH THERE ARE NO TREES OR STUMPS SPECIFICALLY MARKED FOR REMOVAL WITHIN THE LIMITS OF THE PROJECT, A LUMP SUM QUANTITY IS INCLUDED IN THE GENERAL SUMMARY FOR ITEM 201, CLEARING AND GRUBBING. ALL PROVISIONS AS SET FORTH IN THE SPECIFICATIONS UNDER THIS ITEM ARE INCLUDED IN THE LUMP SUM PRICE BID FOR ITEM 201, CLEARING AND GRUBBING.

ROADWAY

ITEM 606 - ANCHOR ASSEMBLY, MGS TYPE E (MASH 2016)

THIS ITEM SHALL CONSIST OF FURNISHING AND INSTALLING ANY OF THE GUARDRAIL END TERMINALS FOR TYPE MGS GUARDRAIL AS LISTED ON ROADWAY ENGINEERING'S WEB PAGE UNDER ROADSIDE SAFETY DEVICES FOR APPROVED GUARDRAIL END TREATMENTS. INSTALLATION SHALL BE AT THE LOCATIONS SPECIFIED IN THE PLANS, IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS.

THE FACE OF THE TYPE E IMPACT HEAD SHALL BE COVERED WITH A SHEET OF TYPE G REFLECTIVE SHEETING, PER CMS 730.19.

REFER TO THE MANUFACTURER'S INSTRUCTIONS REGARDING THE INSTALLATION OF, AND THE GRADING AROUND THE FOUNDATION TUBES AND GROUND STRUT. THE TOP OF ANY FOUNDATION TUBE SHOULD BE LESS THAN 4 INCHES ABOVE THE GROUND. THE PLACEMENT OF THE FOUNDATION TUBES SHOULD BE AN APPROPRIATE DEPTH BELOW THE LEVEL LINE IN ORDER TO MAINTAIN THE FINISHED GUARDRAIL HEIGHT OF 31 INCHES FROM THE EDGE OF THE SHOULDER.

ON-SITE GRADING IS REQUIRED IF THE TOP OF THE FOUNDATION TUBES OR TOP OF THE GROUND STRUT DOES PROJECT MORE THAN 4 INCHES ABOVE THE GROUND LINE.

PAYMENT FOR THE ABOVE WORK SHALL BE MADE AT THE UNIT PRICE BID FOR ITEM 606, ANCHOR ASSEMBLY, MGS TYPE E (MASH 2016), EACH, AND SHALL INCLUDE ALL LABOR, TOOLS, EQUIPMENT AND MATERIALS NECESSARY TO CONSTRUCT A COMPLETE AND FUNCTIONAL ANCHOR ASSEMBLY SYSTEM, INCLUDING ALL RELATED TRANSITIONS, REFLECTIVE SHEETING, HARDWARE, GRADING, EMBANKMENT AND EXCAVATION NOT SEPARATELY SPECIFIED, AS REQUIRED BY THE MANUFACTURER.

G

77