

Special Provisions	▼
Estimated Quantities	^
Item 201 - Trees and Stumps to be Removed and Disposed	
Item 202 - Existing Structures (or portions of) Removed and Disposed	
STRUCTURE REMOVED, AS PER PLAN A - 292 CY STRUCTURE REMOVED	
STRUCTURE REMOVED, AS PER PLAN B - 394 CY STRUCTURE REMOVED, 62 CY UNCLASSIFIED EXCAVATION	
STRUCTURE REMOVED, AS PER PLAN C - 550 CY STRUCTURE REMOVED	
STRUCTURE REMOVED, AS PER PLAN D - 39 CY STRUCTURE REMOVED	
PORTIONS OF STRUCTURE REMOVED, AS PER PLAN A - 251 CY STRUCTURE REMOVED	
PORTIONS OF STRUCTURE REMOVED, AS PER PLAN B - 329 CY STRUCTURE REMOVED	
PORTIONS OF STRUCTURE REMOVED, AS PER PLAN C - 238 CY STRUCTURE REMOVED	
PORTIONS OF STRUCTURE REMOVED, AS PER PLAN D - 90 CY STRUCTURE REMOVED	
PORTIONS OF STRUCTURE REMOVED, AS PER PLAN E - 863 CY STRUCTURE REMOVED	
Retaining Wall 5A – Portions of Existing Retaining Wall Removed: Wall Including Footing Concrete = 904 CY	
Retaining Wall 7 – Portions of Existing Bridge Removed: Pier Footing Concrete = 8 CY, Timber Piles = 3 EACH	
CUY-77-1297 – Existing Bridge Removed: Superstructure Concrete = 58 CY, Pier Above Footing Concrete = 44 CY, Abutment Above Footing Concrete = 30 CY, Structural Steel = 94,000 LBS, Chain Link Fence = 352 LF	
CUY-77-1322 – Portions of Existing Bridge Removed: Superstructure Concrete = 178 CY, Abutment Above Footing Concrete = 180 CY, Structural Steel = 286,000 LBS	
CUY-77-1331 – Portions of Existing Bridge Removed: Superstructure Concrete = 755 CY, MSE Wall = 899 SF	
Item 502 - Structure for Maintaining Traffic	
Item 503 - Unclassified Excavation	
Item 509 - Reinforcing Steel	
Item 513 - Structural Steel	
Item 514 - Steel Surfaces to be Painted	
Item 518 - Porous Backfill	
Item 615 - Roads and Pavements for Maintaining Traffic	
Excavation - 30154 CY, Embankment - 2406 CY, Catch Basin Removed - 9 EACH, Pipe Removed - 575 FT, Trench Drain Removed - 947 FT	
Miscellaneous Items	