March 4, 2021

Mr. Mark Carpenter, P.E. District 12 Environmental Engineer 5500 Transportation Blvd Garfield Hts., Ohio 44125

Re: CUY-BH-FY2023 Misc (PID 105909) Asbestos Survey

CUY-271-15.410, Highland Road over I-271

SFN 1811851

Dear Mr. Carpenter,

EnviroScience, Inc. was contracted by the Ohio Department of Transportation to provide an asbestos survey of the CUY-271-15.410 bridge structure over Interstate 271. The bridge location coordinates are 41.55250, -81.44833.

The 387-foot long six-span continuous steel beam bridge with reinforced concrete deck and substructure will be replaced. Bridge inventory report information indicates the structure to have been originally built in 1963 with a major reconstruction in 2001. A site location map is included in Appendix A.

Asbestos Regulations and Definitions

Prior to the demolition or renovation of a structure (including bridge structures), an asbestos inspection must be conducted by a licensed asbestos hazard evaluation specialist in accordance with National Emissions Standard for Hazardous Air Pollutants (NESHAP) Guidelines, EPA Regulation 40 CFR, Subpart M, Part 61 and OEPA asbestos regulations (OAC 3745-20). Further, the Occupational Safety and Health Administration's (OSHA's) Asbestos Standard for the Construction Industry (29 CFR 1926.1101) regulates all renovation and demolition work involving building materials which contain any amount of asbestos.

NESHAP, OEPA, and OSHA asbestos regulations define asbestos-containing material (ACM) as any material containing greater than one (1) percent asbestos as determined by polarized light microscopy. NESHAP regulations require that all materials suspected of containing asbestos be sampled to determine asbestos content or be assumed to be an ACM and, therefore, treated as such. Materials that are determined or assumed to be ACMs shall be quantified and assessed by a licensed inspector. The materials then shall be characterized and assigned one of the following designations: Friable, Category I Non-friable, and Category II Non-friable.

<u>Friable ACM</u> is defined by the Asbestos NESHAP regulations as any material containing more than one percent (1%) asbestos as determined using the method specified in Appendix E, Subpart E, 40 CFR Part 763, Section 1, Polarized Light Microscopy (PLM), that, when dried, can be crumbled, pulverized, or reduced to powder by hand pressure.

<u>Non-friable ACM</u> is any material containing more than one percent (1%) asbestos as determined using the method specified in Appendix E, Subpart E, 40 CFR Part 763, Section 1, Polarized Light Microscopy (PLM), that, when dry, cannot be crumbled, pulverized, or reduced to powder by hand pressure. Non-friable ACM can remain on the structure during renovation/demolition if it will not be sanded, grinded, cut, abraded, or made friable by any means. The two categories of non-friable ACM are described as follows:

EnviroScience
5070 Stow Road
Stow OH 44224

- <u>Category I Non-friable ACM</u> asbestos-containing packing, gaskets, resilient floor covering, and asphalt roofing products.
- <u>Category II Non-friable ACM</u> any asbestos-containing material excluding Category I Non-friable ACM.

Regulated ACM (RACM) is defined as:

- · Friable asbestos material.
- Category I Non-friable ACM that has become friable.
- Category I Non-friable ACM that has been or will be involved in sanding, grinding, cutting, or abrading.
- Category II Non-friable ACM that has a high probability of becoming crumbled, pulverized, or reduced to powder by forces expected to act on the material during renovation or demolition.

Asbestos Survey Summary

Bridge Plan Review- EnviroScience performed a limited review of available bridge construction plans that were compiled by the department and placed on ODOTs FTP site. Original construction plans and deck replacement plans from 2000 were reviewed. The rehab plans illustrated the presence of a 4" gas line (unidentified material) to remain on the structure. The abutment detail called out 1" preformed expansion joint material in the joint between the top of the abutment and the bottom of the abutment diaphragm; and caulk was called out beneath the vandal fence mounting flanges. In summary, asbestos is sometimes found in various caulks and joint materials, but no conclusive evidence of suspect asbestos containing materials was noted.

<u>Asbestos Survey</u>- An asbestos survey of the subject bridge structure was conducted on 01/13/21 by C.E. Kessler, Certified Asbestos Hazard Evaluation Specialist #ES34704 and Amy Wakefield, Certified Asbestos Hazard Evaluation Specialist #ES543881.

All accessible portions of the CUY-271-15.410 bridge were field investigated for the presence of suspected ACMs. A visual inspection of the top and bottom sides of the structure including the deck, parapets, vandal fence, beams, and abutments was conducted. One 4" PVC utility line was confirmed to be affixed to the north beam line for the length of the structure. No other utilities were observed beneath the structure. Samples were taken of the preformed expansion joint material and caulk mentioned above.

The following table summarizes the samples that were collected:

Table 1 – Sample Summary – CUY-271-15.410 Bridge SFN 1811851					
Sample	Homogeneous Area	Category	Location of Sample	Positive for Asbestos?	
High-1	Mastic Side Sealant	Misc	East Abutment North End	No	
High-2	Mastic Side Sealant	Misc	East Abutment North End	No	
High-3	Mastic Side Sealant	Misc	East Abutment South End	No	
High-4	Paint	Misc	Beam Line – south	No	
High-5	Paint	Misc	Beam Line – south	No	



Table 1 – Sample Summary – CUY-271-15.410 Bridge SFN 1811851					
Sample	Homogeneous Area	Category	Location of Sample	Positive for Asbestos?	
High-6	Paint	Misc	Beam Line - north	No	
High-7	Internal Mastic Packing	Misc.	PVC Conduit Casing	No	
High-8	External Pipe Wrap	Misc	PVC Conduit	No	
High-9	External PipeWrap	Misc.	PVC Conduit	No	
High-10	Expansion Joint	Misc	East Back Wall	No	
High-11	Expansion Joint	Misc.	East Back Wall	No	
High-12	Expansion Joint	Misc.	East Back Wall	No	
High-13	Caulk Compound	Misc.	Vandal Fence Mounting Flange	No	
High-14	Caulk Compound	Misc.	Vandal Fence Mounting Flange	No	
High-15	Caulk Compound	Misc.	Vandal Fence Mounting Flange	No	
High-16	Joint Caulking	Misc.	Parapet Railing, Deck	No	
High-17	Joint Caulking	Misc.	Parapet Railing, Deck	No	
High-18	Joint Caulking	Misc.	Parapet Railing, Deck	No	
High-19	Expansion Joint	Misc.	Parapet End Piece	No	
High-20	Expansion Joint	Misc.	Parapet End Piece	No	
High-21	Expansion Joint	Misc.	Parapet End Piece	No	

All bulk samples collected were submitted to IATL International Asbestos Testing Laboratories of Mount Laurel, New Jersey, for analysis of asbestos content by polarized light microscopy (PLM) using the Environmental Protection Agency (EPA) Method 600/R-93/116. Appendix B includes an IATL laboratory Chain of Custody, sampling log, and laboratory analysis report. A bridge diagram indicating sample locations and a photo log is provided in Appendix C.

Conclusion and Recommendations

Lab analysis of bulk samples taken from the CUY-271-15.410 bridge structure indicate that no asbestos containing material was identified.

If suspect ACMs are revealed during demolition or renovation activities that were not identified during this survey it is recommended that work activities cease until a Certified Asbestos Hazard Evaluation Specialist can evaluate the new material(s). Any removal and subsequent disposal of the asbestos containing material during demolition operations must comply with the Ohio Administrative code, the occupational Safety and Health Administration (OSHA) regulations and the National Emission Standard for Hazardous Air pollutants (NESHAP). Reference the Ohio Environmental Protection Agency adopted chapters 3745-20-03 & 3745-20-04 of the Ohio Administrative Code. This implements the NESHAP standards for asbestos and its removal.



Notification

An OEPA Notification of Demolition and Renovation form must be submitted ten (10) working days prior to work activities. Appendix D contains the OEPA form of which Section 1 - General Information 1, 2, 3, 4, and 5; and Section 2 - Project Address Specific Information A, B, C, and D have been completed.

Once the Contractor has been selected for the project, the remaining sections of the form shall be completed (as applicable) and the notification form submitted with the proper remittance to the following address at least 10 working days prior to starting work:

Ohio EPA, DAPC Asbestos P.O. Box 1049 Columbus, Ohio 43216-1049

The form may also be completed/submitted via on-line at https://epa.ohio.gov/dapc/atu/asbestos

AHES Signature

Charles E. Kessler, AICP, CAHES, CEP

Asbestos Hazard Evaluation Specialist #ES34704

Attachments





Client: ENV507

9000 Commerce Parkway Suite B Mt. Laurel, New Jersey 08054 Telephone: 856-231-9449

Email: customerservice@iatl.com

CERTIFICATE OF ANALYSIS

Client: EnviroScience, Inc. Report Date: 1/22/2021

5070 Stow Road Report No.: 626740 - PLM

ODOT District 12 Bridges-CUY Stow OH 44224 Project:

Project No.:

PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 7129137 Analyst Observation: Black Sealant Location: East Abutment North End Facility: Client No.: High-1 Client Description: Mastic Side Sealant At Gap Percent Non-Asbestos Fibrous Material: Percent Asbestos: Percent Non-Fibrous Material: 95 5 Cellulose None Detected **Lab No.:** 7129138 Analyst Observation: Black Sealant Location: East Abutment North End Client No.: High-2 Client Description: Mastic Side Sealant At Gap Facility: Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material: None Detected Lab No.: 7129139 **Analyst Observation:** Black Sealant Location: East Abutment South End Client No.: High-3 Client Description: Mastic Side Sealant At Gap **Facility:** Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material: None Detected 5 Cellulose **Lab No.:** 7129140 **Analyst Observation:** Grey Paint **Location:** Beam South Line Client Description: Paint Client No.: High-4 Facility: Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material: None Detected None Detected **Lab No.:** 7129141 **Analyst Observation:** Grey Paint Location: Beam South Line Client No.: High-5 **Client Description:** Paint Facility: Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material: None Detected None Detected **Lab No.:** 7129142 **Analyst Observation:** Grey Paint **Location:** Beam North Line Client No.: High-6 **Client Description:** Paint Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material: Percent Asbestos: None Detected None Detected

Please refer to the Appendix of this report for further information regarding your analysis.

Date Received:

1/18/2021

Date Analyzed:

01/22/2021

Signature: Analyst:

David Dayen David Hayes

Approved By:

Frank Tuanfol

Frank E. Ehrenfeld, III Laboratory Director

Dated: 1/22/2021 4:59:48

Page 1 of 7



Client: ENV507

9000 Commerce Parkway Suite B Mt. Laurel, New Jersey 08054 Telephone: 856-231-9449

Email: customerservice@iatl.com

CERTIFICATE OF ANALYSIS

Client: EnviroScience, Inc. Report Date: 1/22/2021

5070 Stow Road Report No.: 626740 - PLM

ODOT District 12 Bridges-CUY Stow OH 44224 Project:

Project No.:

PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 7129143 Analyst Observation: Black/Off-White Insulation Location: Client Description: PVC Conduit Casing Internal Mastic Facility: Client No.: High-7 Percent Non-Asbestos Fibrous Material: Percent Asbestos: Percent Non-Fibrous Material: 15 Synthetic None Detected 3 Cellulose Analyst Observation: Off-White/Black Wrap Lab No.: 7129144 Location: Client Description: PVC Conduit 4" External Wrap Client No.: High-8 Facility: Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material: 25 Synthetic None Detected Analyst Observation: Off-White/Black Wrap **Lab No.:** 7129145 Location:

Client Description: PVC Conduit 4" External Wrap Client No.: High-9 **Facility:**

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

25 Synthetic None Detected

Lab No.: 7129146 Analyst Observation: Black Expansion Joint Location: East Back Wall

Client No.: High-10 **Client Description:** Expansion Joint Facility:

Percent Non-Asbestos Fibrous Material: Percent Asbestos: Percent Non-Fibrous Material:

70 Cellulose None Detected

Lab No.: 7129147 Analyst Observation: Black Expansion Joint Location: East Back Wall

Client No.: High-11 **Client Description:** Expansion Joint Facility:

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

70 Cellulose None Detected

Analyst Observation: Black Expansion Joint **Lab No.:** 7129148 Location: East Back Wall

Facility: Client No.: High-12 **Client Description:** Expansion Joint

Percent Non-Fibrous Material: Percent Asbestos: Percent Non-Asbestos Fibrous Material:

70 Cellulose None Detected

Please refer to the Appendix of this report for further information regarding your analysis

1/18/2021 Date Received: 01/22/2021 Date Analyzed:

David Dayen Signature: David Hayes Analyst:

Approved By:

Frank Tuanfol Frank E. Ehrenfeld, III Laboratory Director

Dated: 1/22/2021 4:59:48

Page 2 of 7



9000 Commerce Parkway Suite B Mt. Laurel, New Jersey 08054 Telephone: 856-231-9449 Email: customerservice@iatl.com

CERTIFICATE OF ANALYSIS

Client: EnviroScience, Inc. Report Date: 1/22/2021

5070 Stow Road Report No.: 626740 - PLM

Stow OH 44224 Project: ODOT District 12 Bridges-CUY

Client: ENV507 Project No.: 33582

PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 7129149 **Analyst Observation:** Grey Caulk **Location:** Vandal Fence Mounting Flange Client Description: Joint Compound Facility: Client No.: High-13 Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material: Percent Asbestos: None Detected None Detected 100 **Lab No.:** 7129150 Analyst Observation: Grey Caulk Location: Vandal Fence Mounting Flange Client No.: High-14 Client Description: Joint Compound Facility: Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material: None Detected None Detected **Lab No.:** 7129151 **Analyst Observation:** Grey Caulk **Location:** Vandal Fence Mounting Flange Client No.: High-15 Client Description: Joint Compound Facility: Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material: None Detected None Detected **Lab No.:** 7129152 Analyst Observation: Grey Caulk **Location:** Parapet Railing Deck Client No.: High-16 Client Description: Joint Caulking Percent Non-Asbestos Fibrous Material: Percent Asbestos: Percent Non-Fibrous Material: None Detected None Detected **Lab No.:** 7129153 **Analyst Observation:** Grey Caulk **Location:** Parapet Rail Deck Client No.: High-17 Client Description: Joint Caulking Facility: Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material: None Detected None Detected **Lab No.:** 7129154 Analyst Observation: Grey Caulk **Location:** Parapet Rail Deck Client No.: High-18 Client Description: Joint Caulking Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material: Percent Asbestos: None Detected None Detected

Please refer to the Appendix of this report for further information regarding your analysis.

Date Received:

Date Analyzed:

1/18/2021

Date Mary Zea.

01/22/2021

Signature: Analyst:

David Hayes

Approved By:

Frank E. Ehrenfeld, III

Frank E. Ehrenfeld, II Laboratory Director

Dated: 1/22/2021 4:59:48 Page 3 of 7

David Dayen



9000 Commerce Parkway Suite B Mt. Laurel, New Jersey 08054 Telephone: 856-231-9449 Email: customerservice@iatl.com

CERTIFICATE OF ANALYSIS

Client: EnviroScience, Inc. Report Date: 1/22/2021

5070 Stow Road Report No.: 626740 - PLM

ODOT District 12 Bridges-CUY Stow OH 44224 Project:

Project No.: Client: ENV507

PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 7129155 Analyst Observation: Black Expansion Joint **Location:** Parapet End Piece

Client Description: Expansion Joint Facility: Client No.: High-19

Percent Non-Asbestos Fibrous Material: Percent Asbestos: Percent Non-Fibrous Material:

70 Cellulose None Detected 30

Lab No.: 7129156 Analyst Observation: Black Expansion Joint **Location:** Parapet End Piece Client Description: Expansion Joint Client No.: High-20 Facility:

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

70 Cellulose None Detected

Lab No.: 7129157 Analyst Observation: Black Expansion Joint **Location:** Parapet End Piece

Client No.: High-21 **Client Description:** Expansion Joint Facility:

Percent Non-Asbestos Fibrous Material: Percent Asbestos: Percent Non-Fibrous Material:

70 Cellulose None Detected

Please refer to the Appendix of this report for further information regarding your analysis

1/18/2021 Date Received: 01/22/2021 Date Analyzed:

Daviel Bayen Signature: David Hayes Analyst:

Frank Franks Frank E. Ehrenfeld, III

Approved By:

Laboratory Director

Dated: 1/22/2021 4:59:48

Page 4 of 7



9000 Commerce Parkway Suite B Mt. Laurel, New Jersey 08054 Telephone: 856-231-9449

Email: customerservice@iatl.com

CERTIFICATE OF ANALYSIS

Client: EnviroScience, Inc. Report Date: 1/22/2021

5070 Stow Road Report No.: 626740 - PLM

Stow OH 44224 Project: ODOT District 12 Bridges-CUY

Client: ENV507 Project No.: 33582

Appendix to Analytical Report

Customer Contact: Chuck Kessler

Method: 40 CFR Appendix E to Subpart E of Part 763, interim method for the Determination of Asbestos in Bulk Insulation Samples, and USEPA 600, R93-116 as needed.

This appendix seeks to promote greater understanding of any observations, exceptions, special instructions, or circumstances that the laboratory needs to communicate to the client concerning the above samples. The information below is used to help promote your ability to make the most informed decisions for you and your customers. Please note the following points of contact for any questions you may have.

iATL Customer Service: customerservice@iatl.com iATL Office Manager:wchampion@iatl.com iATL Account Representative: House Account Sample Login Notes: See Batch Sheet Attached Sample Matrix: Bulk Building Materials Exceptions Noted: See Following Pages

General Terms, Warrants, Limits, Qualifiers:

General information about iATL capabilities and client/laboratory relationships and responsibilities are spelled out in iATL policies that are listed at www.iATL.com and ir our Quality Assurance Manual per ISO 17025 standard requirements. The information therein is a representation of iATL definitions and policies for turnaround times, sample submittal, collection media, blank definitions, quantification issues and limit of detection, analytical methods and procedures, sub-contracting policies, results reporting options, fees, terms, and discounts, confidentiality, sample archival and disposal, and data interpretation.

iATL warrants the test results to be of a precision normal for the type and methodology employed for each sample submitted. iATL disclaims any other warrants, expressed or implied, including warranty of fitness for a particular purpose and warranty of merchantability. iATL accepts no legal responsibility for the purpose for which the client uses test results. Any analytical work performed must be governed by our Standard Terms and Conditions. Prices, methods and detection limits may be changed without notification. Please contact your Customer Service Representative for the most current information.

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA LAP LLC, or any agency of local, state or province governments nor of any agency of the U.S. government.

This report shall not be reproduced except in full, without written approval of the laboratory.

Information Pertinent to this Report:

Analysis by US EPA 600 93-116: Determination of Asbestos in Bulk Building Materials by Polarized Light Microscopy (PLM).

Certifications:

- NIST-NVLAP No. 101165-0
- NYSDOH-ELAP No. 11021
- AIHA-LAP, LLC No. 100188

Quantification at <0.25% by volume is possible with this method. (PC) Indicates Stratified Point Count Method performed. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. PC Trace represents a <0.25% amount. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed (ex. analyze until positive instructions). Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, PLM is not consistently reliable in detecting asbestos in non-friable organically bound (NOB) materials. Quantitative transmission electron microscopy (TEM) is currently the only method that can pronounce materials as non-asbestos containing.

Analytical Methodology Alternatives: Your initial request for analysis may not have accounted for recent advances in regulatory requirements or advances in technology that are routinely used in similar situations for other qualified projects. You may have the option to explore additional analysis for further information. Below are a few options, listed as the matrix followed by the appropriate methodology. Also included are links to more information on our website.

Bulk Building Materials that are Non-Friable Organically Bound (NOB) by Gravimetric Reduction techniques employing PLM and TEM: ELAP 198.6 (PLM-NOB), ELAP 198.4 (TEM-NOB)

Dated: 1/22/2021 4:59:48 Page 5 of 7



9000 Commerce Parkway Suite B Mt. Laurel, New Jersey 08054 Telephone: 856-231-9449

Email: customerservice@iatl.com

CERTIFICATE OF ANALYSIS

Report Date: 1/22/2021 Client: EnviroScience, Inc.

5070 Stow Road Report No.: 626740 - PLM

OH 44224 Project: ODOT District 12 Bridges-CUY Stow

Project No.: 33582 Client: ENV507

Loose Fill Vermiculite Insulation, Attic Insulation, Zonolite (copyright), etc.: US EPA 600 R-4/004 (multi-tiered analytical process) Sprayed On Insulation/Fireproofing with Vermiculite (SOF-V): ELAP 198.8 (PLM-SOF-V)

Soil, sludge, sediment, aggregate, and like materials analyzed for asbestos or other elongated mineral particles (ex. erionite, etc.): ASTM D7521, CARB 435, and other options available

Asbestos in Surface Dust according to one of ASTM's Methods (very dependent on sampling collection technique – by TEM): ASTM D 5755, D5756, or D6480

Various other asbestos matrices (air, water, etc.) and analytical methods are available.

Disclaimers / Qualifiers:

There may be some samples in this project that have a "NOTE:" associated with a sample result. We use added disclaimers or qualifiers to inform the client about something that requires further explanation. Here is a list with highlighted disclaimers that may be pertinent to this project. For a full explanation of these and other disclaimers, please inquire at customerservice@iatl.com.

- 1) Note: No mastic provided for analysis.
- 2) Note: Insufficient mastic provided for analysis.
- 3) Note: Insufficient material provided for analysis.
- 4) Note: Insufficient sample provided for QC reanalysis.
- 5) Note: Different material than indicated on Sample Log $\!\!/$ Description.
- 6) Note: Sample not submitted.
- 7) Note: Attached to asbestos containing material.
- 8) Note: Received wet.
- 9) Note: Possible surface contamination.
- 10) Note: Not building material. 1% threshold may not apply.
- 11) Note: Recommend TEM-NOB analysis as per EPA recommendations.12) Note: Asbestos detected but not quantifiable.
- 13) Note: Multiple identical samples submitted, only one analyzed.
- 14) Note: Analyzed by EPA 600/R-93/116. Point Counting detection limit at 0.080%.
- 15) Note: Analyzed by EPA 600/R-93/116. Point Counting detection limit at 0.125%.
- 16) Note: This sample contains >10% vermiculite mineral. See Appendix for Recommendations for Vermiculite Analysis.

Recommendations for Vermiculite Analysis:

Several analytical protocols exist for the analysis of asbestos in vermiculite. These analytical approaches vary depending upon the nature of the vermiculite mineral being tested (e.g. un-processed gange, homogeneous exfoliated books of mica, or mixed mineral composites). Please contact your client representative for pricing and turnaround

iATL recommends initial testing using the EPA 600/R-93/116 method. This method is specifically designed for the analysis of asbestos in bulk building materials. It provides an acceptable starting point for primary screening of vermiculite for possible asbestos.

Results from this testing may be inconclusive. EPA suggests proceeding to a multi-tiered analysis involving wet separation techniques in conjunction with PLM and TEM gravimetric analysis (EPA 600/R-04/004).

For New York State customers, NYSDOH requires disclaimers and qualifiers for various vermiculite containing samples that direct analysis via ELAP198.6 and ELAP198.8 for samples that contain >10% vermiculite mineral where ELAP198.6 may be used to evaluate the asbestos content of the material. However, any test result using ELAP198.6 will be reported with the following disclaimer: "ELAP198.6 method does not remove vermiculite and may underestimate the level of asbestos present in a sample containing >10% vermiculite.

Further information on this method and other vermiculite and asbestos issues can be found at the following: Agency for Toxic Substances and Disease Registry (ATSDR) www.atsdr.cdc.gov, United States Geological Survey (USGS) www.minerals.usgs.gov/minerals/, US EPA www.epa.gov/asbestos. The USEPA also has an informative brochure "Current Best Practices for Vermiculite Attic Insulation" EPA 747F03001 May 2003, that may assist the health and remediation professional. NYS customers please follow current NYSDOH ELAP requirements per policy on subject of surfacing and vermiculite, May 6, 2016, Testing Requirements for Surfacing Material Containing Vermiculite (https://www.wadsworth.org/sites/default/files/WebDoc/I198_8_02_2.pdf)

The following is a summary of the analytical process outlines in the EPA 600/R-04/004 Method:

1) Analytical Step/Method: Initial Screening by PLM, EPA 600R-93/116

Requirements/Comments: Minimum of 0.1 g of sample. ~0.25% for most samples.

Dated: 1/22/2021 4:59:49 Page 6 of 7



9000 Commerce Parkway Suite B Mt. Laurel, New Jersey 08054 Telephone: 856-231-9449 Email: customerservice@iatl.com

CERTIFICATE OF ANALYSIS

Client: EnviroScience, Inc.

5070 Stow Road

OH 44224 Stow

Client: ENV507

Report Date: 1/22/2021

Report No.: 626740 - PLM

Project: ODOT District 12 Bridges-CUY

Project No.: 33582

2)**Analytical Step/Method:** Wet Separation by PLM Gravimetric Technique, EPA R-04/004 **Requirements/Comments:** Minimum 50g** of dry sample. Analysis of "Sinks" only.


3) **Analytical Step/Method:** Wet Separation by PLM Gravimetric Technique, EPA R-04/004 **Requirements/Comments:** Minimum 50g** of dry sample. Analysis of "Floats" only.

4) **Analytical Step/Method:** Wet Separation by TEM Gravimetric Technique, EPA R-04/004 **Requirements/Comments:** Minimum 50g** of dry sample. Analysis of "Sinks" only.

5)**Analytical Step/Method:** Wet Separation by TEM Gravimetric Technique, EPA R-04/004 **Requirements/Comments:** Minimum 50g** of dry sample. Analysis of "Suspension" only. *With advance notice and confirmation by the laboratory.

**Approximately 1 Liter of sample in double-bagged container (~9x6 inch bag of sample).

Dated: 1/22/2021 4:59:49 Page 7 of 7





Chain of Custody

-Bulk Asbestos -

Contact Inform	ation				
Client Company:		Project Number:	33582		
Office Address:	5070 Stow Road	Project Name:	ODOT District 12 Bridges- CUY		
City, State, Zip:	Stow, Ohio 44224	Primary Contact:	Chuck Kessler		
Fax Number:		Office Phone:	330-688-0111		
1					
Email Address:	ckessler@enviroscienceinc.com	Cell Phone:	330-592-9619		
PLM Instruction	ns:				
PLM: Bulk Asb	estos Building Materials EPA 600 R-93/1	16, 1993			
2 physicians	estos Building Materials EPA 600 M-4/82	-			
the contract of the contract o	estos Building Materials NIOSH 9002, 19				
*******	estos Building Materials NYSDOH-ELAI				
91640000	estos Building Materials NYSDOH-ELAI				
i IEM: Bulk Asb	estos Building Materials NYSDOH-ELAI	7 198.4, 2009			
☐ PLM: Point Cou	nting	PI M. Analuz	e Until Positive (Positive Stop)		
PC: via ELA			Homogenous Area as Noted		
PC: 400 Poin			Material Type as Noted		
PC: 800 Poir		PLM: NOB v			
PC: 1600 Po		(moved	able via EPA 600 2.3		
		☐ If <1% by PLM, to TEM via 198.4 *			
PLM: Instructio	ns for Multi-Layered Samples		PLM, Hold for Instructions		
Analyze and	Report All Separable Layers per EPA 60				
Report Com	posite for Drywall Systems per NESHAP	PLM: Non-B	uilding Material*,*** (Dust, Wipe, Tape)		
Report All L	ayers and Composite Where Applicable	Soil or Ve	ermiculite Analysis*		
Only Analyz	e and Report Specifically Noted Layer	CARB 43	5		
Special Instruction	ons:				
* Additional o	charge and turnaround may be required ** Alte	rnative Method (ex: EPA 600/R-0	14/004) may be recommended by Laboratory		
Turnaround Ti	me				
· · · · · · · · · · · · · · · · · · ·	equested Date: January 22, 2021	Verb	al Email Fax		
	Specific date / time				
· · ·	10 Day	1 Day* 12 Hour**	6 Hour** RUSH**		
* End of next	business day unless otherwise specified. ** M	fatrix Dependent. ***Please n	otify the lab before shipping***		
	1				
Chain of Custo		Data: 1/14/21	Time: 13:00		
Received (Name / i.	e/Organization); C. Kessler/EnviroScience Inc	Date: 1/14/21 Date:	Time:		
Sample Login (Name		_ Date:	Time:		
Analysis(Name(s) /		Date:	Time:		
QA/QC Review (Na	me / iATL):	Date:	Time:		
Archived / Released		Date:	Time:		
			The second secon		




Sample Log

-Bulk Asbestos -

Client: ODOT District 12 Project: CUY-271-15.410
--

Sampling Date/Time: 01/13/21 09:40

Bulk Asbestos Sample Log			
Client Sample #	iATL#	Location/Description	Notes
High-1		East Abutment North End	Mastic Side Sealant at Gap
High-2		East Abutment North End	Mastic Side Sealant at Gap
High-3		East Abutment South End	Mastic Side Sealant at Gap
High-4		Beam- South Line	Paint
High-5		Beam- South Line	Paint
High-6		Beam- North Line	Paint
High-7		PVC- Conduit Casing	Internal Mastic Packing
High-8		PVC Conduit 4"	External Wrap
High-9		PVC Conduit 4"	External Wrap
High-10		East Back Wall	Expansion Joint
High-11		East Back Wall	Expansion Joint
High-12		East Back Wall	Expansion Joint
High-13		Vandal Fence Mounting Flange	Joint Compound
High-14		Vandal Fence Mounting Flange	Joint Compound
High-15		Vandal Fence Mounting Flange	Joint Compound
High-16		Parapet Railing Deck	Joint Caulking






Sample Log

-Bulk Asbestos -

Client: ODOT District 12) Project:	CUY-271-15.410
Sampling Date/Time: 1/13/21	09:40	

Bulk Asbestos Sample Log			
Client Sample #	iATL#	Location/Description	Notes
High-17		Parapet Rail Deck	Joint Caulking
High-18		Parapet Rail Deck	Joint Caulking
High-19		Parapet End Piece	Expansion Joint
High-20		Parapet End Piece	Expansion Joint
High-21		Parapet End Piece	Expansion Joint





Sample Log

-Bulk Asbestos -

Client: ODOT District 12	Project:_	CUY-271-15.410 Highland Road over I-271
Sampling Date/Times 1/13/21	09:40	

	Bulk	Asbestos Sample Log	
. 1			
Client Sample #	iATL#	Location/Description	Notes
High-17	7129137	Parapet Rail Deck	Joint Caulking
High-18	7129138	Parapet Rail Deck	Joint Caulking
High-19⊡	†1 29139	Parapet End Piece	Expansion Joint
High-20	7129140	Parapet End Piece	Expansion Joint
High-21	7129141	Parapet End Piece	Expansion Joint
High-6	7109.42	Beam- North Line	Paint
High-7	7129143	PVC- Conduit Casing	Internal Mastic Packing
High-8	7129.44	PVC Conduit 4"	External Wrap
High-9	7129.45	PVC Conduit 4"	External Wrap
High-10	7129.46	East Back Wall	Expansion Joint
High-11	7129147	East Back Wall	Expansion Joint
High-12	7129148	East Back Wall	Expansion Joint
High-13	7129149	Vandal Fence Mounting Flange	Joint Compound
High-14	7109150	Vandal Fence Mounting Flange	Joint Compound
High-15	7109151	Vandal Fence Mounting Flange	Joint Compound
High-16	71 20102	Parapet Railing Deck	Joint Caulking

* assiment thish - 1-7 -5

IATL

- 2 -



9000 Commerce Parkway, Suite B • Mount Laurel, NJ 08054 Phone: 877-428-4285/856-231-9449 • Fax: 856-231-9818

Sample Log -Bulk Asbestos -

Client: ODOT District 12	Project:	CUY-271-15.410 Highland Road over I-271
Sampling Date/Time: 1/13/21	09:40	

Bulk Asbestos Sample Log				
. /V.L.W				
Client Sample #	iATL#	Location/Description	Notes	
High-17	7129153	Parapet Rail Deck	Joint Caulking	
High-18	7129154	Parapet Rail Deck	Joint Caulking	
High-19	7119255	Parapet End Piece	Expansion Joint	
High-20	7129156	Parapet End Piece	Expansion Joint	
High-21	7129157	Parapet End Piece	Expansion Joint	
rea (C	,			
VI				
(5) (5) (7) (8) (8) (8) (8) (8) (8) (8) (8) (8) (8				
27		Fig. 1		
	~ ~~	- Commence of the commence of		
		Like State S		

derby to a relation	most north-date			Angula Marie - North Control of St. St.	
		•	t elebrating / S	chas, concrample as a fone	\$ APPR
	water on market.	An an c	· 6	(ATTIO COAL	IMIL
					- 2 -
and the second	ne dia anti-	1		Makes work and	





PHOTO 1 Looking west at CUY-271-15.410 bridge



PHOTO 2 Looking at the north end east abutment 4"x4" mastic sealant. Sample collected here.



PHOTO 3 Underside of bridge. Paint samples collected.



PHOTO 4 Internal mastic packing in coupler. Sample taken here.



PHOTO 5 External pipe wrap around 4" PVC conduit at north beam. Sample taken here.



PHOTO 6 Expansion joint on east back wall. Sample taken here.



PHOTO 7 Vandal fence mounting flange. Caulking samples taken here.



PHOTO 8 Parapet railing on the deck. Sample taken of joint compound.




PHOTO 9
Parapet railing on the deck.
Sample taken of expansion joint.



Notification of Demolition and Renovation/Abatement Section 1: General Information

Division of Air Pollution Control

Work on projects cannot begin until 10 working days after a COMPLETE original notification form, <u>including payment</u>, is submitted to Ohio EPA. Instructions and a worksheet for fee calculation are available at *epa.ohio.gov/asbestos*. This form can be completed, and payment made, at *ebiz.epa.ohio.gov*. Questions? *asbestos@epa.ohio.gov* or (614) 466-0061.

Ohio EPA Use Only Notification #: Postmar 1) Notification Information (Check all that apply)	·ked: /	/	Received:	/ /	☐ Hand-Delivered					
☐ Original ☐ Revision # (count): ☐ Installation ☐ Emerg	gency \square	Annual	Cancellation F	Proiect Co	unty: Cuyahoga					
2) Owner, Asbestos Abatement Contractor, Billing and Fire Department	Information				Revised?					
Owner										
Name: Ohio Department of Transportation Is this a company? ☐ Yes ☒ No										
Address: 5500 Transportation Blvd Contact Person: Mark Carpenter										
city: Garfield Heights	State: OH			<u> </u>	Zip: 44125 -					
Email: Mark.Carpenter@dot.state.oh.us	Phone: (2	16) 584	- 2089	Fax: (
Asbestos Abatement Contractor (if applicable)										
Name:	1	_icense #: AC	·		Expiration Date: / /					
Address:		Contact Pe	rson:							
City:	State:			Zip:	Zip: -					
Email:	Phone: () -	-	Fax: () -					
Billing Contact	<u>'</u>									
Is this contact associated with the Owner, Asbestos Abatement Contractor, or Demolition Contractor (if not installation)?										
Address:		Contact Pe	rson:							
City:	State:			Zip:	-					
Email:	Phone: () -	-	Fax: () -					
Fire Department (if applicable)										
Name:		_								
Address:	,	Contact Pe	rson:	,						
City:	State:			Zip:	Zip: -					
Email:	Phone: () -	-	Fax: () -					
3) Ohio Asbestos Hazard Evaluation Specialist and Evaluation Procedure	2				Revised?					
Evaluation Specialist: Charles Kessler	Cer	tification #:	es 34704	Expira	Expiration Date: 10 /7 /2021					
Procedure, including analytical methods, employed to detect the presence of and to estimate the quantity of regulated asbestos-containing material (RACM) and Category I and Category II non-friable asbestos-containing material:										
Bulk Sampling w/point count of samples that are less than 10% asbestos containing										
4) Procedures to be followed should unexpected RACM be discovered (check all that apply) Revised?										
	Demarcate a	rea	☐ Cor	ntact licens	sed abatement contractor					
Contact district office/local air authority										
Other (Explain): Notify ODOT Project Engineer and Project Superintendent										
5) Planned Demolition (check all that apply) Revised?										
Describe demolition work to be performed and method(s) to be employed, including demolition techniques to be used: Implosion Fire Training Wet Methods Manual Demolition Mechanical Demolition Other (Explain):										
Existing structure components will be removed by industry standard means and methods										

Notification of Demolition and Renovation/Abatement Section 1: General Information

Mail completed form and payment to: Ohio EPA, DAPC – Asbestos P.O. Box 1049, Columbus, OH 43216-1049

Continued

Description of affected facility	y components (include a	ittachment if necessary):										
(Revised 02/18)		Page	1	of	3								
6) Asbestos Description and	d Engineering Controls	_									Revised?		
For the material listed in each ensure proper waste handling	n project, describe the ty			gineeri	ng con	trols and	work practices	to be used	to minir	nize emi	issions and		
Type of ACM to be abated:	Surfacing	☐ Mechanical		ther									
Engineering Controls:	☐ Wet Methods	Glove Bag	□N	PE		AFD Other:							
Work Practices:	☐ Intact Removal	☐ Manual	□ №	1echar	ical	Other	:						
7) Asbestos Waste Transpo	rter (if applicable)	1									Revised?		
Transporter #1 Name:													
Address:					Conta	act Person	n:						
City:			State:					Zip:	-				
Email:			Phone	: ()	-		Fax: ()	-			
Transporter #2 Name (if appli	cable):		•					•					
Address:					Conta	act Person	1:						
City:			State:					Zip:	-				
Email:			Phone	: ()	-		Fax: ()	-			
8) Asbestos Waste Disposa	l Site (if applicable)							•			Revised?		
Name:													
Address:					Conta	act Person	:						
City:			State:					Zip:	-				
Email:			Phone	: ()	-		Fax: ()	-			
9) Emergency Demolition (complete if you checked	d "Emergency" above a	nd "Dei	nolitic	n" for	any proje	ect)				Revised?		
A copy of the issued order, in	cluding the following in	ormation, must be atta	ched to	this n	otifica	tion.							
Government Official Issuing C	Order:		Tit	le:									
Agency:				Authority of Order (Citation of Code):									
Date of Order: / /						Demolition Date: / /							
10) Emergency Renovation/	Abatement (complete i	f you checked "Emerge	ncy" ab	ove an	d "Rei	novation/	Abatement" f	or any proje	ect)		Revised?		
Date of Emergency: /	/		Tir	ne of E	merge	ency: :	a.m	□ p.m.					
Description of Sudden, Unexp	pected Event:												
Explanation of how the event	t caused unsafe condition	ns or equipment dama	ge:										
11) Attestation											Revised?		
In accordance with Ohio Adm the Administrative Code will s is prohibited by law and I cert	supervise the stripping a	nd removal described b	y this n	otifica	tion. I	acknowle	-						
Signature:							Date: ///						
Name: Mark Carpenter			Titl	e: Dis	trict	12 Env	ironmenta	l Engine	er				
Organization: Ohio Depar	tment of Transpo	ortation	_	· <u> </u>			·						



Notification of Demolition and Renovation/Abatement Section 2: Project Address Specific Information

Division of Air Pollution Control

Please complete Section 2 for the address included with this notification. If the project is an "Installation" per OAC 3745-20, complete a separate Section 2 page for each address associated with this notification.

Ohio EPA Use Only	Project ID #	† :									
A. Facility Descri	iption								Revised?		
Building Name (if applicable): CUY-271-15.410				Site Location (specific): Highland Rd over I-271 SFN 1811851							
Address: Highlan	d Rd over	I-271, Coordinate	s: 41.55250	, -81.44	1833						
city: Highland Heights					ОН	Zip: 4 4	4143 -	13 -			
Building Size (squar	e feet):		No	No. of Floors:			Age: 58				
Present Use: Highway Bridge Prior Use: Highway Bridge											
B. Type of Operation (check all that apply) Revised?											
□ Demolition	☑ Demolition ☐ Renovation/Abatement – Type: ☐ Removal ☐ Repair ☐ Encapsulation ☐ Enclosure										
C. Asbestos Pres	sent (check on	ie)							Revised?		
☐ Yes ☐ No		No, previously abated	Year A	bated:							
D. Approximate	D. Approximate Amount of Asbestos-Containing Materials (complete table below and Section 1 #6 if asbestos is present) Revised?										
			Material to	be Remov	ved		Material NOT to be Removed				
			Non-fria	ble Asbestos-Containing Material			Non-friab	le Asbestos-	-Containing Material		
		RACM	Catego	ry l	Category	/ II	Categ	ory I	Category II		
Pipes (linear feet)											
Surface area on oth components (ft²)	er facility										
Volume if length or be measured (ft³)	area cannot										
E. Asbestos Aba	tement Sched	lule and Abatement Spe	cialist (original r	otificatio	n is required 10 wor	rking days p	rior to the sta	art of work)	Revised?		
Setup Date: /	/	Abaten	nent Date: /	/		Com	plete Date:	/ /			
(Shift 1) Time Monda		, Tuesday	Wednes	day	Thursday	Frida	ıy	Saturday	Sunday		
start/end on site								1			
Abatement Speciali	st Name:			Certific	ation #: AS		Expirat		on Date: / /		
(Shift 1) Time start/end on site			day Thursday		Frida	ıy	Saturday	Sunday			
Abatement Speciali	st Name:			Certific	ation #: AS			Expiration [late: / /		
F. Demolition Co		pplicable)		oc. cinio					Revised?		
Name:											
Address: Contact Person:											
City: St							Zip:	-			
Email: Pr				Phone: (-						
G. Demolition So	chedule (origi	nal notification is requir	ed 10 working d	ays prior	to the start of work)		1		Revised?		
Start Date: / / Complete Date: / /											
H. Project Hold									Revised?		
Hold Begin Date: / / Work Resume Date: / /											

(Revised 02/18) Page <u>3</u> of <u>3</u>