




PID: 112998	SFN: 1802437	PROJECT: CUY-17-13.50	STATION / OFFSET: 117+33, 47' LT.				START: 3/21/22	END: 3/23/22	PG 2 OF 3	B-002-0-22													
MATERIAL DESCRIPTION AND NOTES			ELEV.	DEPTHS		SPT/ RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				ODOT CLASS (GI)	HOLE SEALED		
			641.8								GR	CS	FS	SI	CL	LL	PL	PI	WC				
STIFF TO VERY STIFF, GRAY, <b>SILT AND CLAY</b> , TRACE TO LITTLE SAND, MOIST TO WET <i>(continued)</i>					61																		
					62																		
					63																		
					64	2 3 5	9	100	SS-19	2.00	-	-	-	-	-	-	-	26	A-6a (V)				
					65																		
					66																		
					67																		
					68																		
					69	2 3 5	9	100	SS-20	1.00	0	0	1	60	39	25	19	6	28	A-4b (8)			
					70																		
MEDIUM STIFF TO STIFF, GRAY, <b>SILT</b> , "AND" CLAY, WET					71																		
					72			100	ST-21	2.00	-	-	-	-	-	-	-	26	A-4b (V)				
					73																		
					74	2 2 3	6	100	SS-22	1.50	-	-	-	-	-	-	-	27	A-4b (V)				
					75																		
					76																		
					77																		
					78																		
					79	2 3 4	8	100	SS-23	1.50	-	-	-	-	-	-	-	35	A-4b (V)				
					80																		
					81																		
					82																		
					83																		
					84	2 3 4	8	100	SS-24	1.00	-	-	-	-	-	-	-	28	A-4b (V)				
					85																		
					86																		
					87																		
					88																		
					89	3 3 4	8	100	SS-25	2.00	0	0	1	66	33	25	21	4	23	A-4b (8)			
					90																		
					91																		
					92																		
					93																		
					94	2 3 4	8	100	SS-26	1.00	-	-	-	-	-	-	-	32	A-4b (V)				
					95																		
					96																		
					97																		
					98																		
					99	3 7 8	18	100	SS-27A	-	-	-	-	-	-	-	-	-	-	A-4b (V)			
					100				SS-27B	2.00	-	-	-	-	-	-	-	20	A-4a (V)				
					101																		
					102																		
					103																		
					104	11 17 29	54	100	SS-28	4.00	5	6	9	44	36	26	18	8	14	A-4a (8)			
					105																		
					106																		
					107																		
					108																		
					109	18 24 30	63	100	SS-29	4.00	-	-	-	-	-	-	-	14	A-4a (V)				
					110																		
					111																		
					112																		
					113																		
					114	20 50/6"	-	100	SS-30A	4.00	-	-	-	-	-	-	-	13	A-4b (V)				
					<b>SHALE</b> , GRAY, MODERATELY TO HIGHLY WEATHERED, WEAK TO SLIGHTLY STRONG, VERY FINE GRAINED, THIN TO MEDIUM BEDDED, SLIGHTLY ARGILLACEOUS, FRACTURED; RQD 45%, REC 100%.				TR	114				SS-30B	-	-	-	-	-	-	-	-	-
115																							
116																							
117																							
118																							
119																							
120	45		100	RC-31																			
121																							