

CUY-71-10.48  
BEGIN  
S.L.M. 239.10

CUY-71-10.48  
END  
S.L.M. 243.36

CUY-77-1.89  
END  
S.L.M. 155.50

CUY-480-22.45  
BEGIN WB  
S.L.M. 25.20

CUY-77-1.89  
BEGIN  
S.L.M. 149.17

CUY-480-22.45  
END  
S.L.M. 28.41

CUY/LAK-271-13.61/0.00  
BEGIN  
S.L.M. 35.45

CUY/LAK-271-13.61/0.00  
END  
S.L.M. 40.22

LOCATION PLAN

DESIGN AGENCY	
DESIGNER	FLK
REVIEWER	FLK 7/27/21
PROJECT ID	115312
SHEET	TOTAL
P.2	11



ROUTE	LOCATION	850	850	850		850	850	850		807	807	807	807	807
		GROOVING FOR 6" RECESSED PAVEMENT MARKING (ASPHALT)	GROOVING FOR 6" RECESSED PAVEMENT MARKING (ASPHALT)	GROOVING FOR 12" RECESSED PAVEMENT MARKING (ASPHALT)		GROOVING FOR 6" RECESSED PAVEMENT MARKING (CONCRETE)	GROOVING FOR 6" RECESSED PAVEMENT MARKING (CONCRETE)	GROOVING FOR 12" RECESSED PAVEMENT MARKING (CONCRETE)		WET REFLECTIVE EPOXY PAVEMENT MARKING, 6" EDGE LINE	WET REFLECTIVE EPOXY PAVEMENT MARKING, 6" LANE LINE	WET REFLECTIVE EPOXY PAVEMENT MARKING, 12" CHANNELIZING LINE	WET REFLECTIVE EPOXY PAVEMENT MARKING, 6" DOTTED LINE	WET REFLECTIVE EPOXY PAVEMENT MARKING, 12" DOTTED LINE
		MILE	FEET	FEET		MILE	FEET	FEET		MILE	MILE	FEET	FEET	FEET
IR-71	SR-237 Split to Median Barrier End	46.84	6385	16250						23.71	25.09	12500	6385	3980
	Bridge Decks					1.96	230							
IR-77	Oakes Rd. to Rockside Rd.	60.02	12340	13430						32.49	29.44	12780	12340	2200
	Bridge Decks					1.91	1550							
IR-271	South of Wilson Mills Rd. to IR-90 Interchange	54.01	5205	18955						28.93	25.31	14700	5205	4255
	Bridge Decks					0.23								
IR-480	Lee Rd. to IR-271 Overlap	19.36	5225	6530						13.28	7.33	6530	5225	
	Bridge Decks					1.25								
<b>TOTALS</b>		<b>180.23</b>	<b>29155</b>	<b>55165</b>		<b>5.35</b>		<b>1780</b>		<b>98.41</b>	<b>87.17</b>	<b>46510</b>	<b>29155</b>	<b>10435</b>

SUBSUMMARY

DESIGN AGENCY



DESIGNER

FLK

REVIEWER

FLK 7/27/21

PROJECT ID

115312

SHEET


P.7

TOTAL

11

ROUTE	S.L.M.		PAVEMENT MARKING LINE DATA								REMARKS		
			EDGE LINE, 6"				LANE LINE, 6"	CHANNELIZING LINE, 12"				DOTTED LINE, 6"	DOTTED LINE, 12"
			WHITE	YELLOW	WHITE	YELLOW		GORE	MAIN	RAMP			
			FROM	TO	MILE-Mainline	MILE-Ramp	MILE	FEET				FEET	FEET
IR-480	25.20	25.95	0.75	0.75			2.25					Begin Project to Warrensville Center Rd._WB	
	25.95	26.37	0.42	0.42			0.84			850		Warrensville Center Rd. to Structure CUY-480N-0011_WB	
	26.31	28.41	2.10	2.10			2.10					Ramp S-96/Ramp N-W Gore to End Project_WB	
	26.55	28.41	1.86	1.86			1.86					Structure CUY-480-2437R/Ramp S-95 to End Project_EB	
Ramps	24.87				0.21	0.21		560	500	545		IR-480 WB exit ramp to Lee Rd. (E-L)	
	25.57							1050		870		Warrensville Center Rd. SB entrance ramp to IR-480 WB (Ramp WN-N)	
					0.15	0.15		290		645			
					0.15	0.15							
	25.81				0.34	0.34						Warrensville Center Rd. NB entrance ramp to Ramp WN-N to IR-480 WB (Ramp WS-W)	
	26.24				0.36	0.16	0.22		2180	865		Ramp S-96 to IR-480 WB Mainline	
									650				
					0.20	0.20	0.06				250		Ramp N-W to Ramp S-96
				0.10	0.10		700			875		Ramp N-SE	
				0.10	0.10		600			325		Ramp SE-N	
											Dotted Line, 6" (2' segment - 6' gap)		
SHEET SUB-TOTALS			5.13	5.13	1.61	1.41	7.33	3200	3330	5225			
GRAND TOTALS			98.41				87.17	46510			29155	10435	

PAVEMENT MARKING DATA

DESIGN AGENCY  
  
 DESIGNER  
 FLK  
 REVIEWER  
 FLK 7/27/21  
 PROJECT ID  
 115312  
 SHEET TOTAL  
 P.11 | 11