



Project:	CCG3A	Computed:	NJH/JML/D	Date:	5/16/2024
Subject:	Bridge 9	Checked:	DWW	Date:	5/16/2024
Task:	Estimated Quantities	Page:		of:	
Job #:	10021558	No:			

Item 518E40011 - 6" Non-Perforated Corrugated Plastic Pipe, Including Specials, As Per Plan (FT):

Included with Wall N items for payment.

Item 518E51101 - 8" Pipe Downspout, Including Specials, As Per Plan (FT):

Rear Abutment =	58.67	ft.	
Pier 4 =	40.39	ft	
Pier 10 =	52.21	ft.	
Foward Abutment =	88.39	ft.	
Total Abutment =	170.00	ft.	(with additional 15% for bends and misc)
Total Piers	107.00	ft.	(with additional 15% for bends and misc)
Total Length =	277.00	ft.	

Made by: GDS	Date:	11/7/25'
Checked by : JTW	Date:	11/7/25'

	Total 8" Pipe Downspout Length =	277	FT
--	----------------------------------	-----	----

Item 518E51201 - Pipe Downspout, Including Specials, As Per Plan (FT) (10" Diameter Pipe):

Rear Abutment =	25.46	ft.	
Pier 4 =	64.99	ft	
Pier 10 =	45.24	ft.	
Foward Abutment =	23.23	ft.	
Total Abutment =	56.00	ft.	(with additional 15% for bends and misc)
Total Piers	127.00	ft.	(with additional 15% for bends and misc)
Total Length =	183.00	ft.	

Made by: GDS	Date:	11/7/25'
Checked by : JTW	Date:	11/7/25'

	Total 10" Pipe Downspout Length =	183	FT
--	-----------------------------------	-----	----