

SHEET NUM.											PART.		ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.										
5	6	7	9	10	12	14	19	23	25	26	01/NHS/OT	02/NHS/OT																
	LUMP											LUMP	201	11000	LS		ROADWAY CLEARING AND GRUBBING											
			3										204	20000	3	CY	EMBANKMENT											
			6										859	20500	8	SY	SEEDING AND MULCHING, CLAS 1											
													5,000	832	30000	5,000	EACH	EROSION CONTROL										
			1,860										1,500	360	605	05100	1,860	FT	4" SHALLOW PIPE UNDERDRAINS									
			8										8		611	07600	8	FT	18" CONDUIT, TYPE C									
						46	126		38				184	26	625	00450	210	EACH	CONNECTION, FUSED PULL APART									
						78	138		63				225	54	625	00480	279	EACH	CONNECTION, UNFUSED PERMANENT									
													3		625	10490	3	EACH	LIGHT POLE, CONVENTIONAL, A15B40									
													1		625	10490	1	EACH	LIGHT POLE, CONVENTIONAL, AT15B30									
													1		625	10490	1	EACH	LIGHT POLE, CONVENTIONAL, A12B40									
													2		625	10490	2	EACH	LIGHT POLE, CONVENTIONAL, AT12B40									
													6		625	10490	19	EACH	LIGHT POLE, CONVENTIONAL, AT15B40									
													8		625	10490	47	EACH	LIGHT POLE, CONVENTIONAL, AT18B40									
													5		625	10490	28	EACH	LIGHT POLE, CONVENTIONAL, AT20B40									
															1	625	14000	1	EACH	LIGHT POLE FOUNDATION, 24" X 6' DEEP								
															85	11	625	14100	96	EACH	LIGHT POLE FOUNDATION, 24" X 8' DEEP							
													10		8	2	625	14600	10	EACH	LIGHT POLE FOUNDATION, MISC.: EXCAVATION AND RESTORATION	10						
															4,518		9,078		2,205	14,226	1,575	625	23302	15,801	FT	NO. 6 AWG 2400 VOLT DISTRIBUTION CABLE		
															3,924		10,884		3,339	15,849	2,298	625	23400	18,147	FT	NO. 10 AWG POLE AND BRACKET CABLE		
															7,468		14,523		6,802	23,573	5,220	625	24324	28,793	FT	1-1/2" DUCT CABLE WITH THREE NO. 6 AWG 2400 VOLT CABLES		
															65		51		17	116	17	625	25500	133	FT	CONDUIT, 3", 725.04		
															764		1,585		591	2,544	396	625	25900	2,940	FT	CONDUIT, JACKED OR DRILLED, 725.04, 3"		
															277		1,009			1,286		625	25910	1,286	FT	CONDUIT CLEANED AND CABLES REMOVED		
															23		63		19	92	13	625	26252	105	EACH	LUMINAIRE, CONVENTIONAL, SOLID STATE (LED), IES-III, 16,400-17,600 LUMENS, AS PER PLAN	9	
															7,272		13,744		6,499	22,518	4,997	625	29002	27,515	FT	TRENCH, 24" DEEP		
															17		28		16	48	13	625	30700	61	EACH	PULL BOX, 725.08, 18"		
															8		18		6	27	5	625	30706	32	EACH	PULL BOX, 725.08, 24"		
															21	14	59	47	11	72		625	31510	72	EACH	PULL BOX REMOVED		
															1		2		1	86	11	625	32000	97	EACH	GROUND ROD		
															1		2		1	3	1	625	34001	4	EACH	POWER SERVICE, AS PER PLAN	9	
															7,272		13,744		6,499	22,518	4,997	625	36000	27,515	FT	PLASTIC CAUTION TAPE		
													LUMP							LUMP		SPECIAL	62540000	LS		MAINTAIN EXISTING LIGHTING	10	
													4							4		SPECIAL	62540010	4	EACH	REPLACEMENT OF EXISTING LIGHTING UNIT	10	
															19		4			4		625	75400	4	EACH	LIGHT POLE REMOVED		
																	47		15	81		625	75401	81	EACH	LIGHT POLE REMOVED, AS PER PLAN	9	
																	10			10		625	75403	10	EACH	LIGHT POLE REMOVED FOR STORAGE, AS PER PLAN	9	
															19		57		15	91		625	75500	91	EACH	LIGHT POLE FOUNDATION REMOVED		
															21		61		17	99		625	75506	99	EACH	LUMINAIRE REMOVED		
															1		2		1	4		625	75510	4	EACH	POWER SERVICE REMOVED		
															730		2,023		1,085	3,838		625	75550	3,838	FT	DISTRIBUTION CABLE REMOVED		
																	8,927		16,273	30,639		625	75551	30,639	FT	DISTRIBUTION CABLE REMOVED, AS PER PLAN	9	
															1					1		625	76000	1	EACH	ARC FLASH CALCULATIONS AND LABEL (CC-'A')		
															1					1		625	76000	1	EACH	ARC FLASH CALCULATIONS AND LABEL (CC-'B')		
															1					1	1	625	76000	1	EACH	ARC FLASH CALCULATIONS AND LABEL (CC-'D')		
															1					1		625	76000	1	EACH	ARC FLASH CALCULATIONS AND LABEL (CC-'G')		
															160					160		614	11110	160	HOUR	MAINTENANCE OF TRAFFIC LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE		
															16					16		614	18601	16	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	7	
													LUMP							LUMP		614	11000	LS		MAINTAINING TRAFFIC		
															8					8		619	16010	8	MNTH	FIELD OFFICE, TYPE B		
															LUMP					LUMP		623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING		
															LUMP					LUMP		624	10000	LS		MOBILIZATION		

CALCULATED  
 CFD  
 CHECKED  
 KWR  
  
**GENERAL SUMMARY**  
 REVISION #3 5/28/2020  
 REVISION #1 2/26/2020  
 REVISION #2 3/23/2020  
  
**D03-LG-FY2020**  
 8  
 44