

MICROFILMED
AUG 21 1990

STRUCTURAL GENERAL NOTES

F.H.W.A. REGION	STATE	PROJECT
5	OHIO	

158
284

ERIE COUNTY
ERI-2-(16.13-17.39)

THE FOLLOWING GENERAL NOTES APPLY TO THESE STRUCTURES:

BRIDGE NO. ERI-2-1640	EASTBOUND THRU RAMP
BRIDGE NO. ERI-2-1701 L/R	S.R. 2 OVER BOGART ROAD
BRIDGE NO. ERI-2-1781	HURON AVERY ROAD OVER S.R. 2
BRIDGE NO. ERI-2-1833	S.R. 13 OVER S.R. 2

REFERENCE SHALL BE MADE TO STANDARD DRAWINGS:

SUPERSTRUCTURE DETAILS	SD-1-69 SHEETS 1, 2, 3 AND 4 OF 4	DATED 6-12-69
ROCKER AND BOLSTER DETAILS	RB-1-55	REVISED 2-2-59
APPROACH SLAB DETAILS	AS-1-81 SHEETS 1, 2 AND 3 OF 3	DATED 11-27-81
BRIDGE RAILING DETAILS	BR-1	DATED 5-29-79
ELASTOMERIC JOINT SEAL TYPE 1A	TS-EJS-2-81	DATED 9-1-81

AND TO SUPPLEMENTAL SPECIFICATIONS:

836 CONCRETE CURING AND PROTECTIVE MEMBRANE	DATED 11-12-85
824 EPOXY COATED REINFORCING STEEL	DATED 10-8-82

DESIGN SPECIFICATIONS:

THIS STRUCTURE CONFORMS TO "STANDARD SPECIFICATIONS FOR HIGHWAY BRIDGES" ADOPTED BY THE AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS, 1969, AND THE OHIO "SUPPLEMENT" TO THESE SPECIFICATIONS.

DESIGN DATA:

DESIGN LOADING	HS20-44 AND THE ALTERNATE MILITARY LOADING
CONCRETE CLASS S	UNIT STRESS 1500 P.S.I. (SUPERSTRUCTURE)
CONCRETE CLASS C	UNIT STRESS 1333 P.S.I. (SUBSTRUCTURE)
REINFORCING STEEL	ASTM A615, A616 OR A617
	GRADE 60 - UNIT STRESS 24,000 P.S.I.
	SPIRAL REINFORCEMENT MAY BE PLAIN BARS, ASTM A82 OR A615
STRUCTURAL STEEL	ASTM A36 - UNIT STRESS 20,000 P.S.I.
DECK PROTECTION METHOD	EPOXY COATED REINFORCING STEEL, TOP MAT ONLY.

ABUTMENT PILING:

BRIDGE NO. ERI-2-1701 L/R; ABUTMENT PILING BENDING STRESS MAY APPROACH, REACH OR EXCEED YIELD STRESS.

EMBANKMENT CONSTRUCTION

THE EMBANKMENTS AT BRIDGE NO. ERI-2-1640, BRIDGE NO. ERI-2-1701 L/R AND BRIDGE NO. ERI-2-1833 SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE REQUIREMENTS STATED IN THE ROADWAY GENERAL NOTES, SHEET 8. THE FOLLOWING WAITING PERIODS SHALL BE OBSERVED AFTER COMPLETION OF THE EMBANKMENTS TO THE LEVEL OF SUBGRADE.

- BRIDGE NO. ERI-2-1640; EASTBOUND THRU RAMP OVER S.R. 2: EXCAVATION FOR PIER NO. 2 AND DRIVING OF PIER NO. 2 PILES MAY BE STARTED AFTER COMPLETION OF THE EMBANKMENTS TO THE LEVEL OF SUBGRADE. THERE SHALL BE A MINIMUM ONE-MONTH WAITING PERIOD BEFORE STARTING ABUTMENT AND PIERS NO. 1 AND NO. 3 CONSTRUCTION AND DRIVING ABUTMENT AND PIERS NO. 1 AND NO. 3 PILES.
- BRIDGE NO. ERI-2-1701 L/R; S.R. 2 OVER BOGART ROAD: THERE SHALL BE A MINIMUM THREE-MONTH WAITING PERIOD BEFORE STARTING ABUTMENT AND PIER CONSTRUCTION AND DRIVING ABUTMENT AND PIER PILES.
- BRIDGE NO. ERI-2-1833; S.R. 13 OVER S.R. 2: EXCAVATION FOR PIER NO. 2 AND DRIVING OF PIER NO. 2 PILES MAY BE STARTED AFTER COMPLETION OF THE EMBANKMENTS TO THE LEVEL OF SUBGRADE. THERE SHALL BE A MINIMUM 5-MONTH WAITING PERIOD BEFORE STARTING ABUTMENT AND PIERS NO. 1 AND NO. 3 CONSTRUCTION AND DRIVING ABUTMENT AND PIERS NO. 1 AND NO. 3 PILES.

PILES:

PILES SHALL BE DRIVEN TO REFUSAL ON BEDROCK. REFUSAL SHALL BE CONSIDERED AS OBTAINED BY PENETRATING SOFT BEDROCK FOR SEVERAL INCHES WITH A MINIMUM RESISTANCE OF 20 BLOWS PER INCH OR REFUSAL SHALL BE CONSIDERED AS OBTAINED AFTER THE PILE HAS CONTACTED HARD BEDROCK AND THE PILE HAS RECEIVED AT LEAST 20 BLOWS.

PILE DESIGN LOADS

	<u>ABUTMENT PILES</u>	<u>PIER PILES</u>
BRIDGE NO. ERI-2-1640	34 TONS/PILE	35 TONS/PILE
BRIDGE NO. ERI-2-1701 L/R	32 TONS/PILE	34 TONS/PILE
BRIDGE NO. ERI-2-1781	33 TONS/PILE	34 TONS/PILE
BRIDGE NO. ERI-2-1833	34 TONS/PILE	35 TONS/PILE

UTILITY LINES:

ALL EXPENSE INVOLVED IN RELOCATING (INSTALLING) THE AFFECTED UTILITY LINES SHALL BE BORNE BY THE OWNER(S). THE CONTRACTOR AND OWNER(S) ARE REQUESTED TO COOPERATE BY ARRANGING THEIR WORK IN SUCH A MANNER THAT INCONVENIENCE TO EITHER WILL BE HELD TO A MINIMUM.

MAINTENANCE AND PROTECTION OF TRAFFIC:

TRAFFIC SHALL BE MAINTAINED ON BOGART ROAD AS INDICATED ON THE ROADWAY PLANS (GENERAL NOTES).

REINFORCING BAR LAPPED SPLICES:

REINFORCING BARS SHALL BE LAPPED AS FOLLOWS, UNLESS OTHERWISE NOTED IN THESE PLANS.

- NO. 4 BAR - 1'-10" MIN.
- NO. 5 BAR - 2'-5" MIN.
- NO. 6 BAR - 2'-10" MIN.
- NO. 8 BAR - 4'-9" MIN.
- NO. 10 BAR - 7'-8" MIN.

ITEM 511, CLASS S CONCRETE, AS PER PLAN

IN LIEU OF THE PROPORTIONING SPECIFIED IN 499.03 AND 511.02, THE FOLLOWING TABLE SHALL BE USED TO ESTABLISH THE QUANTITIES PER CUBIC YARD FOR CONCRETE, THE COARSE AGGREGATE SHALL BE LIMESTONE.

CONCRETE IN THE PARAPETS NEED NOT BE PLACED AT NIGHT.

QUANTITIES PER CUBIC YARD (USING NO. 8 LIMESTONE)

FINE AGGREGATE (LB)	COARSE AGGREGATE (LB)	TOTAL (LB)	CEMENT CONTENT (LB)	WATER-CEMENT RATIO
1555	1100	2655	715	0.40

AIR CONTENT - 8±2%

HIGH RANGE WATER REDUCER MAY BE USED AT THE OPTION OF THE CONTRACTOR. THE DOSAGE RATE WILL BE DETERMINED BY THE CONTRACTOR BASED ON MANUFACTURER'S RECOMMENDATION TO ACHIEVE THE DESIRED WORKABILITY LEVEL.

HIGH RANGE WATER REDUCER SHALL CONFORM TO 705.12, ASTM-C494 TYPE F AND SHALL NOT CONTAIN CALCIUM CHLORIDE.

THE CEMENT CONTENT SHALL BE MAINTAINED AND A MAXIMUM WATER-CEMENT RATIO OF 0.40 SHALL NOT BE EXCEEDED. THE SLUMP OF THE UNPLASTICIZED CONCRETE DELIVERED TO THE JOB SITE SHALL BE 1 1/2 INCH. THE SUPERPLASTICIZING ADMIXTURE SHALL BE ADDED AT THE JOB SITE AND MIXED A MINIMUM OF FIVE (5) MINUTES. AFTER THE SUPERPLASTICIZER HAS BEEN ADDED, THE SLUMP SHALL BE 1 1/2 INCH. THE CONTRACTOR SHALL FURNISH A VOLUMETRIC DISPENSER FOR THE SUPERPLASTICIZER.

CONCRETE MIXTURES CONTAINING A HIGH RANGE WATER REDUCER SHALL MEET THE SAME REQUIREMENTS FOR ENTRAINED AIR CONTENT, MINIMUM STRENGTH, AND MAXIMUM WATER-CEMENT RATIO AS REQUIRED FOR THE RESPECTIVE GRADE OF CONCRETE WITHOUT A HIGH RANGE WATER REDUCER.

SAMPLING AND TESTING FOR ENTRAINED AIR CONTENT AND MINIMUM STRENGTH SHOULD BE TAKEN FROM THE CONCRETE THAT HAS BEEN TREATED WITH A HIGH RANGE WATER REDUCER.


CURING SHALL BE IN ACCORDANCE WITH 511.14 TYPE "A" WATER CURING.

PLACEMENT

PLACEMENT OF CONCRETE SHALL BE COMPLETED UNDER FAVORABLE ATMOSPHERIC CONDITIONS. FAVORABLE ATMOSPHERIC CONDITIONS EXIST WHEN THE SURFACE EVAPORATION RATE AS AFFECTED BY AMBIENT AIR TEMPERATURE, CONCRETE TEMPERATURE, RELATIVE HUMIDITY AND WIND VELOCITY IS 0.1 POUNDS PER SQUARE FOOT PER HOUR OR LESS. FIGURE (1) SHALL BE USED TO DETERMINE GRAPHICALLY THE SURFACE EVAPORATION RATE. FAVORABLE ATMOSPHERIC CONDITIONS MAY REQUIRE PLACEMENT DURING LATE EVENING, NIGHT OR EARLY MORNING HOURS.

IF PLACEMENT OF THE OVERLAY IS TO BE MADE AT NIGHT, THE CONTRACTOR SHALL SUBMIT A PLAN WHICH PROVIDES ADEQUATE LIGHTING FOR THE WORK AREA AT LEAST 15 CALENDAR DAYS IN ADVANCE AND RECEIVE WRITTEN APPROVAL FROM THE ENGINEER BEFORE PLACING THE CONCRETE. THE LIGHTS SHALL BE SO DIRECTED THAT THEY DO NOT AFFECT OR DISTRACT APPROACHING TRAFFIC.

PAYMENT FOR ALL OF THE ABOVE SHALL BE AT THE UNIT PRICE BID PER CUBIC YARD FOR ITEM 511 CLASS S CONCRETE, AS PER PLAN WHICH SHALL INCLUDE ALL LABOR, EQUIPMENT, MATERIALS AND INCIDENTALS NECESSARY TO COMPLETE THE ABOVE.



1 / 1

adache - ciuni - lynn associates
CONSULTING ENGINEERS CLEVELAND, OHIO 44130

**STRUCTURAL
GENERAL NOTES**

BRIDGE No's. ERI-2-1640
ERI-2-1701/L/R
ERI-2-1781
ERI-2-1833

DESIGNED	DRAWN	CHECKED	REVIEWED	DATE	REVISED
L.E.D.	J.D.P.	E.A.F.	L.E.D.	9-23-85	


MICROFILMED
AUG 21 1980

** Included with Item 516 for Payment.
The Angeles, Plates, Studs and Steel Extrusions Shall Be Galvanized As Per 711.02. The Grooves in the Steel Extrusions shall be cleaned to Grade SA 3, ASTM D 2200.

FHWA REGION	STATE	PROJECT	
5	OHIO		

158A
284


ERIE COUNTY
ERI-2 - (16.13 - 17.39)




EPOXY COATED REINFORCING STEEL

MARK	NO.	LENGTH	SHAPE
P501E#	160	4'-0"	S


* TO BE USED AS DIRECTED BY THE ENGINEER IN THE PARAPET EXPANSION JOINT AREA. PLAN REINFORCING STEEL DOES NOT ALLOW FOR SKEW OF EXPANSION JOINT. ALSO SOME BARS MAY BE TRIMMED AS DIRECTED BY THE ENGINEER. COST FOR ALL OF THE ABOVE SHALL BE INCLUDED IN ITEM 516 STRUCTURAL STEEL EXPANSION JOINT INCLUDING STRIP SEALS, AS PER PLAN.



**SECTION B-B
JOINT NORMAL THROUGH PARAPET**



**SECTION C-C
JOINT TRANSVERSE THROUGH PARAPET**



**SECTION A-A
JOINT NORMAL THROUGH ROADWAY**

ITEM 516 STRUCTURAL STEEL EXPANSION JOINTS INCLUDING STRIP SEALS, AS PER PLAN

THIS ITEM SHALL INCLUDE ALL THE WORK REQUIRED TO CONSTRUCT THE STEEL EXPANSION JOINTS AS PER DETAILS IN THE PLAN.

THE STEEL EXTRUSION SHALL BE TYPE E WITH S400E NEOPRENE EXTRUSION AS MANUFACTURED BY WATSON BOWMAN ASSOCIATES, INC., 1280 NIAGARA STREET, BUFFALO, NEW YORK 14213; OR APPROVED EQUAL AS NOTED BELOW.

THE NEOPRENE EXTRUSION SHALL BE ONE CONTINUOUS PIECE. THE NEOPRENE SHALL NOT BE INSTALLED UNTIL ALL OTHER WORK IS COMPLETE UPON THE STRUCTURE. AN ADHESIVE SHALL BE USED TO FACILITATE PLACEMENT OF THE NEOPRENE EXTRUSION. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS PRIOR TO FABRICATION.

PHYSICAL PROPERTIES:

- A. THE STEEL EXTRUSION SHALL CONFORM TO ASTM A36 OR, A588.
- B. ADHESIVES SHALL BE ONE-PART MOISTURE CURING POLY-URETHANE AND HYDRACARBON MIXTURES AS DISTRIBUTED UNDER THE TRADE NAME BON-LASTIC BY WATSON BOWMAN ASSOCIATES, INC., OF BUFFALO, NEW YORK; OR AN APPROVED EQUIVALENT.
- C. THE NEOPRENE EXTRUSION SHALL CONFORM TO THE PHYSICAL PROPERTIES SPECIFIED FOR AASHTO M220 EXCEPT FOR THE RECOVERY TEST.
- D. SET SCREWS FOR FASTENING OF OPTIONAL SPLIT EXTRUSION SHALL BE STAINLESS STEEL.

THE D.S. BROWN COMPANY, P.O. BOX 158, NORTH BALTIMORE, OHIO 45872, WILL BE ACCEPTED AS ONE ALTERNATE. THE STEEL EXTRUSION SHALL BE TYPE SS-E WITH NO. 500 SEAL. THE CONTRACTOR SHALL FURNISH MATERIAL SPECIFICATION, CERTIFIED MATERIAL TEST RESULTS. CERTIFICATION THAT THE PRODUCT MEETS SPECIFICATIONS, APPROPRIATE INSTALLATION PROCEDURES NECESSARY TO ACCOMMODATE ANY ALTERNATE DESIGN.

THE APPROVAL OF AN ALTERNATE JOINT SEAL DESIGN AND THE ISSUANCE OF REVISED PROJECT PLANS SHALL BE BASED ON THE UNDERSTANDING THAT SUCH PROJECT MODIFICATIONS WILL BE DONE WITHOUT COST TO THE STATE.

THE PARAPET JOINT SHALL BE SEALED AS PART OF THIS ITEM. THE PARAPET JOINT SEAL SHALL BE EVAZOTE 50 AS MANUFACTURED BY E-POXY INDUSTRIES INC., 14 WEST SHORE STREET, RAVENA, NEW YORK 12143, TELEPHONE (518) - 756 - 6193 OR E.V.A. AS MANUFACTURED BY THERMAL - CHEM INC, 1400 LOUIS AVENUE, ELK GROVE VILLAGE, IL. 60007 USA, TELEPHONE (323) - 364 - 0364.

THE SEAL SHALL BE CEMENTED IN WITH AN ADHESIVE AS RECOMMENDED BY THE MANUFACTURER OF THE JOINT SEAL. ALL LAITANCIES OR SURFACES CONTAMINANTS SHALL BE REMOVED TO INSURE MAXIMUM ADHESION.

PAYMENT FOR ALL OF THE ABOVE SHALL BE AT THE UNIT PRICE BID PER LINEAL FOOT FOR ITEM 516, STRUCTURAL STEEL EXPANSION JOINTS INCLUDING STRIP SEALS, AS PER PLAN, WHICH SHALL INCLUDE ALL THE LABOR, EQUIPMENT, MATERIALS AND INCIDENTALS NECESSARY TO COMPLETE THE ABOVE WORK

STATE OF OHIO
DEPARTMENT OF TRANSPORTATION
DISTRICT THREE

EXPANSION JOINT DETAILS

ERI - 2 - 1640
ERI - 2 - 1678
ERI - 2 - 1781
ERI - 2 - 1833

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
KW	MA	MA				
10-85	10-85	10-85				

ERI-2-1773

REFERENCES SHALL BE MADE TO STANDARD DRAWINGS:

BR-1	DATED	7/19/02	MT-98.15	DATED	7/16/04
EXJ-4-87	DATED	7/19/02	MT-98.16	DATED	4/19/02
MT-35.10	DATED	4/20/01	MT-105.10	DATED	10/18/02
MT-95.30	DATED	7/16/04	MT-105.11	DATED	10/18/02
MT-97.10	DATED	4/19/02			

DESIGN SPECIFICATIONS:

THIS STRUCTURE CONFORMS TO "STANDARD SPECIFICATIONS FOR HIGHWAY BRIDGES" ADOPTED BY THE AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS, 2002, INCLUDING THE 2003 AND 2004 SPECIFICATIONS AND THE ODOT BRIDGE DESIGN MANUAL.

EXISTING STRUCTURE VERIFICATION:

DETAILS AND DIMENSIONS SHOWN ON THESE PLANS PERTAINING TO THE EXISTING STRUCTURES HAVE BEEN OBTAINED FROM PLANS OF THE EXISTING STRUCTURES AND FROM FIELD OBSERVATIONS AND MEASUREMENTS. CONSEQUENTLY, THEY ARE INDICATIVE OF THE EXISTING STRUCTURES AND THE PROPOSED WORK BUT THEY SHALL BE CONSIDERED TENTATIVE AND APPROXIMATE. THE CONTRACTOR IS REFERRED TO CMS SECTIONS 102.05 AND 105.02.

BASE CONTRACT BID PRICES UPON A RECOGNITION OF THE UNCERTAINTIES DESCRIBED ABOVE AND UPON A PRE BID EXAMINATION OF THE EXISTING STRUCTURES. HOWEVER, THE DEPARTMENT WILL PAY FOR ALL PROJECT WORK BASED UPON ACTUAL DETAILS AND DIMENSIONS THAT HAVE BEEN VERIFIED IN THE FIELD.

EXISTING PLANS:

THE ORIGINAL CONSTRUCTION PLANS OF THE EXISTING BRIDGES ARE AVAILABLE UPON REQUEST AT THE DISTRICT 3 OFFICE OF THE OHIO DEPARTMENT OF TRANSPORTATION, ASHLAND, OH.

DESIGN DATA:

CONCRETE CLASS FS - COMPRESSIVE STRENGTH 4,500 PSI
CONCRETE CLASS S - COMPRESSIVE STRENGTH 4,500 PSI

PLACING ASPHALT CONCRETE FEATHERING ON APPROACHES TO BRIDGES:

SPECIAL CARE SHALL BE TAKEN, WHEN PLACING THE ASPHALT CONCRETE FEATHERING TO EFFECT A SMOOTH TRANSITION FROM THE EXISTING APPROACH PAVEMENT TO THE BRIDGE DECK OR APPROACH SLAB. THE CONTRACTOR'S ATTENTION IS CALLED TO STANDARD DRAWING BP-3.1 FOR REQUIRED TOLERANCES; SPECIFICALLY, THE CONTRACTOR SHALL PROVIDE A 600:1 TAPER RATE FOR PLANING OPERATIONS.

CUT LINE CONSTRUCTION JOINT PREPARATION:

SAW CUT BOUNDARIES OF PROPOSED CONCRETE REMOVALS 1 INCH DEEP. REMOVE CONCRETE TO A ROUGH SURFACE. LEAVE THE EXISTING REINFORCING STEEL IN PLACE. PRIOR TO CONCRETE PLACEMENT ABRASIVELY CLEAN JOINT SURFACES AND EXISTING EXPOSED REINFORCEMENT TO REMOVE LOOSE AND DISINTEGRATED CONCRETE AND LOOSE RUST. THOROUGHLY CLEAN THE JOINT SURFACE AND EXPOSED REINFORCEMENT OF ALL DIRT, DUST, RUST OR OTHER FOREIGN MATERIAL BY THE USE OF WATER, AIR UNDER PRESSURE, OR OTHER METHODS THAT PRODUCE SATISFACTORY RESULTS. EXISTING REINFORCING STEEL DOES NOT HAVE TO HAVE A BRIGHT STEEL FINISH, BUT REMOVE ALL PACK AND LOOSE RUST. THOROUGHLY DRENCH EXISTING CONCRETE SURFACES WITH CLEAN WATER AND ALLOW TO DRY TO A DAMP CONDITION BEFORE PLACING CONCRETE.

ITEM 202 - PORTIONS OF STRUCTURE REMOVED, AS PER PLAN:

THIS ITEM SHALL BE USED AT LOCATIONS IN THE PLAN.

THIS ITEM SHALL INCLUDE THE REMOVAL OF THE CURB, APPROACH SLAB, AND PARAPET AS INDICATED IN THE PLANS.

THE USE OF HEADACHE BALLS AND/OR HOE-RAMS WILL NOT BE PERMITTED. THE METHOD OF REMOVAL AND THE WEIGHT OF THE HAMMER SHALL BE APPROVED BY THE ENGINEER.

THE EXISTING REINFORCING STEEL SHALL BE PRESERVED AS INDICATED IN THE PLANS. EXISTING CURB, APPROACH SLAB, AND PARAPET CONCRETE SHALL BE REMOVED IN A MANNER THAT WILL NOT CUT, ELONGATE, OR DAMAGE THE EXISTING REINFORCING STEEL TO BE PRESERVED.

PAYMENT FOR ALL OF THE ABOVE SHALL BE AT THE UNIT PRICE BID PER CUBIC YARD FOR ITEM 202- PORTIONS OF STRUCTURE REMOVED, AS PER PLAN WHICH WILL INCLUDE ALL LABOR, EQUIPMENT, MATERIALS AND INCIDENTALS NECESSARY TO COMPLETE THE ABOVE WORK.

ITEM 202- REMOVAL MISC.: ELASTOMERIC STRIP SEAL:

THIS ITEM SHALL BE USED TO REMOVE THE EXISTING SEAL IN THE EXPANSION JOINT RETAINERS.

ANY DAMAGED DONE TO THE JOINT OR STEEL RETAINERS SHALL BE REPAIRED BY THE CONTRACTOR, AFTER APPROVAL BY THE ENGINEER, WITH NO ADDITIONAL COST TO THE STATE.

PAYMENT FOR ALL OF THE ABOVE SHALL BE AT THE UNIT PRICE BID PER FOOT FOR ITEM 202- REMOVAL MISC.: ELASTOMERIC STRIP SEAL, WHICH WILL INCLUDE ALL LABOR, EQUIPMENT, MATERIALS AND INCIDENTALS NECESSARY TO COMPLETE THE ABOVE WORK.

I:\projects\18296\struct\strnotes.dgn
tjackson 3/1/2006

DISTRICT 3
OFFICE OF PRODUCTION

DATE 2/06
REVISED DCM
REVISION BTR
REVISION BTR
REVISION DJV

STRUCTURE GENERAL NOTES

ERI-2-16.13

ITEM 511 - CONCRETE, MISC.: ABUTMENT REPAIR:

THIS ITEM SHALL BE USED AT LOCATIONS INDICATED IN THE PLAN.

THE CONCRETE SHALL BE CLASS FS AND MEET THE REQUIREMENTS OF CMS EXCEPT THAT LIMESTONE FOR THE COARSE AGGREGATE SHALL BE USED.

ALL EXISTING SURFACES TO WHICH THE CONCRETE IS TO BOND AND ALL PRESERVED REINFORCING STEEL SHALL BE CLEANED BY ABRASIVE BLASTING. THESE SURFACES SHALL BE MADE FREE OF SPALLS, LAITANCE, AND OTHER CONTAMINANTS DETRIMENTAL TO ACHIEVING AN ADEQUATE BOND.

PAYMENT FOR ALL OF THE ABOVE SHALL BE AT THE UNIT PRICE BID PER CUBIC YARD FOR ITEM 511- CONCRETE, MISC.: ABUTMENT REPAIR WHICH SHALL INCLUDE ALL LABOR, EQUIPMENT, MATERIALS AND INCIDENTALS NECESSARY TO COMPLETE THE ABOVE WORK.

ITEM 511 - CLASS S CONCRETE, SUPERSTRUCTURE, AS PER PLAN (PARAPET RECONSTRUCTION):

THIS ITEM SHALL BE USED AT LOCATIONS INDICATED IN THE PLAN.

THE COARSE AGGREGATE SHALL BE LIMESTONE.

ALL EXISTING SURFACES TO WHICH THE CONCRETE IS TO BOND SHALL BE CLEANED BY ABRASIVE BLASTING. THESE SURFACES SHALL BE MADE FREE OF SPALLS, LAITANCE, AND OTHER CONTAMINANTS DETRIMENTAL TO ACHIEVING AN ADEQUATE BOND.

PAYMENT FOR ALL OF THE ABOVE SHALL BE AT THE UNIT PRICE BID PER CUBIC YARD FOR ITEM 511- CLASS S CONCRETE, SUPERSTRUCTURE, AS PER PLAN WHICH WILL INCLUDE ALL LABOR, EQUIPMENT, MATERIALS AND INCIDENTALS NECESSARY TO COMPLETE THE ABOVE WORK.

ITEM 512 - TREATING CONCRETE BRIDGE DECK WITH GRAVITY-FED RESIN:

THIS WORK SHALL CONSIST OF PREPARING AND TREATING THE CONCRETE BRIDGE DECK AND APPROACH SLAB PATCH JOINTS WITH A GRAVITY-FED CRACK WELDING SYSTEM IN ACCORDANCE WITH THESE SPECIFICATIONS IN REASONABLY CLOSE CONFORMITY WITH THE PLANS AND THE MANUFACTURES RECOMMENDATIONS AND AS DIRECTED BY THE ENGINEER.

SEAL THE CONSTRUCTION JOINTS AROUND THE PATCHES ON THE APPROACH SLABS ON ERI-2-1781 4" WIDE, 2" ON EACH SIDE OF CRACK. THE QUANTITY SHALL BE THE AREA IN SQUARE YARDS OF THE EXPOSED SURFACE, IRRESPECTIVE OF THE DEPTH OF THE JOINT, COMPLETE, IN PLACE AND ACCEPTED.

PAYMENT FOR ALL OF THE ABOVE SHALL BE AT THE UNIT PRICE BID PER SQUARE YARD FOR ITEM 512- TREATING CONCRETE BRIDGE DECK WITH GRAVITY-FED RESIN, WHICH WILL INCLUDE ALL LABOR, EQUIPMENT, MATERIALS AND INCIDENTALS NECESSARY TO COMPLETE THE ABOVE WORK.

ITEM 516 - ELASTOMERIC STRIP SEAL WITHOUT STEEL EXTRUSIONS, AS PER PLAN:

THE ELASTOMERIC STRIP SEAL REPLACEMENT SHALL MATCH THE EXISTING TYPE. THE CONTRACTOR SHALL VERIFY IN THE FIELD THE TYPE AND MANUFACTURER OF THE EXISTING STRIP SEAL. THE EXISTING PLANS CALLED FOR THE S400E NEOPRENE EXTRUSION AS MANUFACTURED BY WATSON BOWMAN ACME, 95 PINEVIEW DRIVE, AMHERST, NEW YORK 14228, PHONE* 800-677-4922 EXT. 253; OR APPROVED EQUAL AS NOTED. THE EXISTING PLANS CALLED FOR THE NO. 500 SEAL MANUFACTURED BY THE D.S. BROWN COMPANY, 300 EAST CHERRY ST, NORTH BALTIMORE, OHIO, 45872, PHONE * 419-257-3561.

PAYMENT FOR ALL OF THE ABOVE SHALL BE AT THE UNIT PRICE BID PER FOOT FOR ITEM 516- ELASTOMERIC STRIP SEAL WITHOUT STEEL EXTRUSIONS, AS PER PLAN, WHICH WILL INCLUDE ALL LABOR, EQUIPMENT, MATERIALS AND INCIDENTALS NECESSARY TO COMPLETE THE ABOVE WORK.
A. DESCRIPTION

ITEM 526 - APPROACH SLABS, MISC.: PATCHING:

THIS ITEM SHALL CONSIST OF FURNISHING THE NECESSARY LABOR, MATERIALS AND EQUIPMENT TO REPAIR THE EXISTING CONCRETE APPROACH SLABS INCLUDING THE REMOVAL OF LOOSE AND UNSOUND CONCRETE, BITUMINOUS PATCHES, SURFACE PREPARATION, SAW CUTTING, AND THE STRENGTH TESTING OF ALL THE PATCHES AS DIRECTED BY THE ENGINEER.

B. REMOVAL OF UNSOUND CONCRETE

THE ENGINEER SHALL VISUALLY INSPECT THE EXISTING CONCRETE APPROACH SLABS AND OUTLINE THE AREAS TO BE REMOVED.

THE PERIMETER OF THE REMOVAL AREAS SHALL BE SAWS TO A DEPTH OF 3/4 INCH TO PRODUCE A VERTICAL OR SLIGHTLY UNDERCUT FACE. AT EACH CORNER OF THE PATCH THE SAW CUTS SHALL COME TOGETHER WITHOUT ANY OVERCUTTING WITH THE SAW. THE CORNERS SHALL BE CHIPPED DOWN TO THE SAW MARKS. ADDITIONAL SAW CUTS MAY BE REQUIRED TO FACILITATE REMOVAL WITHOUT ANY OVERCUTTING. COOLING WATER FROM WET SAWING AND DUST FROM SAWING SHALL BE IMMEDIATELY REMOVED FROM THE EXPOSED PATCH HOLES BEFORE ANY DRYING CAN OCCUR.

UN SOUND CONCRETE INCLUDING ALL PATCHES OTHER THAN SOUND PORTLAND CEMENT CONCRETE, AND ALL OBVIOUSLY LOOSE AND DISINTEGRATED CONCRETE SHALL BE REMOVED. THE UNSOUND CONCRETE MAY BE REMOVED BY CHIPPING OR HAND DRESSING. CHIPPING HAMMERS SHALL NOT BE HEAVIER THAN THE NORMAL 15 POUND CLASS AND SHALL BE OPERATED AT AN ANGLE LESS THAN 45 DEGREES MEASURED FROM THE SURFACE OF THE DECK. CONCRETE SHALL BE REMOVED IN A MANNER THAT PREVENTS CUTTING, ELONGATING OR DAMAGING REINFORCING STEEL. WHERE THE BOND BETWEEN THE CONCRETE AND A REINFORCING BAR HAS BEEN DESTROYED, OR WHERE MORE THAN ONE HALF OF THE PERIPHERY OF SUCH A BAR HAS BEEN EXPOSED, THE ADJACENT CONCRETE SHALL BE REMOVED TO A DEPTH THAT WILL PROVIDE A MINIMUM 3/4 INCH CLEARANCE AROUND THE BAR EXCEPT WHERE OTHER REINFORCING BARS MAKE THIS IMPRACTICABLE. REINFORCEMENT WHICH HAS BECOME LOOSE SHALL BE ADEQUATELY SUPPORTED AND TIED BACK INTO PLACE. ALL REMOVED ASPHALT AND CONCRETE SHALL BE DISPOSED OF PROPERLY OUTSIDE THE RIGHT OF WAY.

it:\projects\18296\struct\strnotes.dgn
tjackson 3/1/2006

DISTRICT 3
OFFICE OF PRODUCTION

DATE 2/06
DCM
BTR
BTR
DJV

STRUCTURE GENERAL NOTES

ERI-2-16.13

**ITEM 526 - APPROACH SLABS, MISC. PATCHING
(CONTINUED):**

C. SURFACE PREPARATION

CLEANING SHALL CLOSELY PRECEDE APPLICATION OF THE PATCHING MATERIAL. THE EXPOSED REINFORCING STEEL SHALL BE THOROUGHLY CLEANED BY ABRASIVE BLASTING (SILICA SAND SHALL NOT BE USED) FOLLOWED BY AN AIR BLAST. IT MAY BE NECESSARY TO USE HAND TOOLS TO REMOVE SCALE FROM THE REINFORCING STEEL.

CONTAMINATION OF THE AREA TO BE PATCHED BY CONSTRUCTION EQUIPMENT OR FROM ANY OTHER SOURCE SHALL BE PREVENTED BY PLACEMENT OF A CLEAN 4 MIL POLYETHYLENE SHEET (OR ANY OTHER COVERING AS APPROVED BY THE ENGINEER) ON THE SURFACE OF THE DECK FOLLOWING THE AIR BLAST CLEANING.

WHERE REINFORCING STEEL IS EXPOSED, THE CONTRACTOR SHALL PROVIDE ADEQUATE SUPPORTS FOR THE CONCRETE MIXER SO THAT REINFORCING STEEL AND ITS BOND WITH THE CONCRETE WILL NOT BE DAMAGED BY THE WEIGHT AND MOVEMENT OF THE MIXER, OR SHALL PROVIDE MEANS TO CONVEY CONCRETE FROM THE MIXER TO THE PATCH LOCATIONS.

D. MATERIALS, PLACING, AND CURING

THE APPROACH SLABS SHALL BE PATCHED WITH CLASS FS CONCRETE WHICH SHALL MEET THE REQUIREMENTS OF CMS EXCEPT THAT LIMESTONE FOR COARSE AGGREGATE SHALL BE USED.

E. PLACING

WHEN NIGHT WORK IS USED THE CONTRACTOR SHALL SUBMIT A PLAN WHICH PROVIDES ADEQUATE LIGHTING FOR THE WORK AREA. THE PLAN SHALL BE SUBMITTED AT LEAST 15 CALENDAR DAYS IN ADVANCE AND BE APPROVED BY THE ENGINEER BEFORE CONCRETE IS PLACED. THE LIGHTS SHALL BE SO DIRECTED THAT THEY DO NOT AFFECT OR DISTRACT APPROACHING TRAFFIC.

THE PATCHING MATERIAL SHALL BE PLACED, CONSOLIDATED AND FINISHED TO THE EXISTING GRADE AND ELEVATION. PATCHES GREATER THAN 50 SQUARE FEET IN AREA SHALL HAVE TEMPORARY BULKHEADS INSTALLED TO FACILITATE PLACEMENT AND FINISHING. THE TEMPORARY BULKHEADS SHALL GO AS DEEP AS THE PATCH AND BE PULLED PRIOR TO THE CONCRETE SETTING. PATCHES EXCEEDING 50 SQUARE FEET SHALL BE STRUCK OFF WITH A SCREED. SMALLER PATCHES THAT ARE UNDER 10 FEET IN LENGTH SHALL BE SCREED LONGITUDINALLY. FOR PATCHES OVER 10 FEET IN LENGTH, THE SCREED SHALL BE PLACED PERPENDICULAR TO THE ROADWAY CENTERLINE.

THE CONTRACTOR SHALL TEST THE SURFACE OF THE PLASTIC CONCRETE FOR TRUENESS AND FOR BEING FLUSH WITH THE EDGES OF THE ADJACENT SURFACES BY USE OF A 10 FOOT STRAIGHTEDGE. FOR PATCHES 10 FEET OR LESS IN LENGTH, THE STRAIGHTEDGE SHALL BE DONE BY PLACING THE STRAIGHTEDGE PARALLEL TO THE BRIDGE CENTERLINE WITH ENDS RESTING ON THE EXISTING WEARING SURFACE AND DRAWING THE STRAIGHTEDGE ACROSS THE PATCH. ANY HIGH OR LOW AREAS EXCEEDING 1/8 INCH IN 10 FEET SHALL BE CORRECTED. IF ANY CORRECTIONS ARE MADE, THE SURFACE SHALL BE RECHECKED.

F. FINISHING

AFTER THE PATCHES HAVE BEEN CONSOLIDATED AND FINISHED, THEY SHALL BE TEXTURED IN ACCORDANCE TO SECTION 451.09 OF THE CMS.

G. INSPECTION, SOUNDING, AND REPAIR OF CONCRETE PATCHES

AFTER CURING AND BEFORE FINAL ACCEPTANCE, ALL PATCHED AREAS SHALL BE INSPECTED AND SOUNDED. ALL DELAMINATED AREAS SHALL BE REMOVED AND REPATCHED ACCORDING TO THIS NOTE.

ALL CRACKS IN BONDED PATCHES SHALL BE SEALED WITH AN APPROVED HIGH MOLECULAR WEIGHT METHACRYLATE SEALER ACCORDING TO THE MANUFACTURER'S RECOMMENDATIONS AND SECTION 512.04 OF CMS.

ALL REPLACEMENT OF REJECTED AREAS AND SEALING OF CRACKS IN NEW BONDED PATCHES WILL BE THE RESPONSIBILITY OF THE CONTRACTOR AND INCLUDED IN THE UNIT BID PRICE FOR THIS ITEM.

H. METHOD OF MEASUREMENT

THE QUANTITY SHALL BE THE ACTUAL AREA IN SQUARE YARDS OF THE EXPOSED SURFACE OF ALL PATCHES, IRRESPECTIVE OF THE DEPTH OF THE PATCH, COMPLETE, IN PLACE AND ACCEPTED.

I. BASIS OF PAYMENT

PAYMENT SHALL BE MADE AT THE UNIT PRICE BID FOR:

ITEM	UNIT	DESCRIPTION
526	SQUARE YARD	APPROACH SLABS, MISC. PATCHING

I:\projects\18296\struct\strnotes.dgn
tjackson 3/1/2006

DATE	2/06
REVISION	DCM
DATE	
REVISION	BTR
DATE	
REVISION	BTR
DATE	
REVISION	DJV
STRUCTURE GENERAL NOTES	
DISTRICT 3 OFFICE OF PRODUCTION	
ERI-2-16.13	
39 61	

ERI-2-1773

STRUCTURE FILE NO.	BRIDGE NO.	STRUCTURE TYPE	LOCATION	SKEW	DECK LENGTH	DECK WIDTH	PROPOSED WORK
2201860	ERI-2-1640	4-SPAN STEEL BEAM	UNDER EB RAMP U.S. 6	36°2'3" L.F.	316'-10"±	28'-10"±	SEAL DECK/DECK EDGE, PIER CAP/COLUMNS, BACKWALL, ABUTMENT, AND WINGWALL
2201186	ERI-2-1678L	3-SPAN STEEL BEAM	OVER NORFOLK SOUTHERN R.R.	36°16'40" L.F.	185'-9"±	38'-10"±	SEAL DECK, FACE/TOP PARAPET, WINGWALL AND ABUTMENT. PARAPET TRANSITION UPGRADE
2201194	ERI-2-1678R	3-SPAN STEEL BEAM	OVER NORFOLK SOUTHERN R.R.	36°16'40" L.F.	185'-9"±	38'-10"±	SEAL DECK, FACE/TOP PARAPET, WINGWALL, AND ABUTMENT. PARAPET TRANSITION UPGRADE, AND REPLACE STRIP SEAL AT BOTH ABUTMENTS
2200953	ERI-2-1694	PIPE	STARR HEIMBERGER DITCH	90°			NO WORK
2201208	ERI-2-1701L	3-SPAN STEEL BEAM	OVER BOGART RD.	2°34'37" L.F.	141'-6"±	38'-10"±	SEAL DECK/DECK EDGE, PARAPET, PIER CAP/COLUMNS, BACKWALL, ABUTMENT, AND WINGWALL, PARAPET TRANSITION UPGRADE, DUMP ROCK UNDER FORWARD ABUTMENT SCUPPERS
2201216	ERI-2-1701R	3-SPAN STEEL BEAM	OVER BOGART RD.	2°34'37" L.F.	141'-6"±	38'-10"±	SEAL DECK/DECK EDGE, PARAPET, PIER CAP/COLUMNS, BACKWALL, ABUTMENT, AND WINGWALL, PARAPET TRANSITION UPGRADE, DUMP ROCK UNDER FORWARD ABUTMENT SCUPPERS
2000988	ERI-2-1737	PIPE	WASHBURN DITCH	10°			NO WORK
2201224	ERI-2-1781	4-SPAN STEEL BEAM	UNDER HURON AVERY RD.	39°32'10" L.F.	306'-0"±	42'-10"±	SEAL DECK/DECK EDGE, PARAPET, PIER CAP/COLUMNS, BACKWALL, ABUTMENT, AND WINGWALL, PATCH TOP OF BACKWALLS, SEAL PATCH JOINTS WITH GRAVITY FED RESIN
2201003	ERI-2-1798L	8-SPAN PRESTRESSED I-BEAM	OVER MUD BROOK	0°	660'-0"±	VARIES 51'-11" TO 65'-10"±	PARAPET TRANSITION UPGRADE, SEAL NEW PARAPET
2201011	ERI-2-1798R	10-SPAN PRESTRESSED I-BEAM	OVER MUD BROOK	0°	780'-0"±	50'±	PARAPET TRANSITION UPGRADE, SEAL NEW PARAPET
2202425	ERI-2-1833	4-SPAN STEEL BEAM	UNDER S.R. 13	14°45'39" L.F.	240'-7"±	42'-10"±	SEAL DECK/DECK EDGE, PIER CAP/COLUMNS, BACKWALL, ABUTMENT, AND WINGWALL
2201038	ERI-2-1911L	27-SPAN STEEL & CONCRETE BEAM	OVER HURON RIVER, NORFOLK SOUTHERN RAILROAD & C.R. 126	VARIES 0° TO 16°29'53" L.F.	2588'-0"±	40'±	PARAPET TRANSITION UPGRADE, SEAL NEW PARAPET
2201046	ERI-2-1911R	27-SPAN STEEL & CONCRETE BEAM	OVER HURON RIVER, NORFOLK SOUTHERN RAILROAD & C.R. 126	VARIES 0° TO 16°29'53" L.F.	2588'-0"	40'±	PARAPET TRANSITION UPGRADE, SEAL NEW PARAPET

I:\projects\18296\struct\strInform.dgn
tjackson 3/1/2006

DISTRICT THREE
PRODUCTION OFFICE


DATE 2/06
REVISED DCM
STRUCTURE FILE NUMBER

DRAWN BTR
CHECKED BTR
DESIGNED BTR
DATE

STRUCTURE INFORMATION

ERI-2-16.13

40
61



S.R. 2 CURVE DATA

PI	=	STA. 1191+14.95
Δ	=	87° 18' 50" LT
Δc	=	2° 00'
Ls	=	300.00'
Bs	=	3° 00'
LT	=	200.03'
ST	=	100.03'
P	=	1.30'
K	=	149.99'
Yc	=	5.24'
Xc	=	299.92'
R	=	2864.79'
θc	=	1° 00'
TS	=	2884.77'
Es	=	1096.71'
Δc	=	81° 18' 50"
Lc	=	4065.69'

EARTHWORK LIMITS SHOWN ARE SCHEMATIC ACTUAL SLOPES SHALL CONFORM TO PLAN CROSS SECTIONS


VERTICAL CURVE DATA

P.V.I.	=	STA. 20+25
EL	=	612.78
CORR.	=	1.53'
PG	=	611.25
VC	=	450'
G ₁	=	+2.40%
G ₂	=	-0.32%

DESIGN TRAFFIC

ADT (2001)	2850
ADTT (2001)	85

P L A N



PRO F I L E

NOTE: ALL ABUTMENT PILES AND ALL PIER PILES SHALL BE HP10x42 STEEL H BEARING PILES ESTIMATED AVERAGE PILE LENGTH: BOTH ABUTMENTS 40 FEET
PIER NO 1. 28 FEET
PIER NO 2. 25 FEET
PIER NO 3. 23 FEET

PROPOSED STRUCTURE

TYPE: CONTINUOUS STEEL BEAM WITH REINFORCED CONCRETE DECK AND SUBSTRUCTURE
SPANS: 63'-0", 89'-0", 89'-0", 63'-0", C/C BRGS.
ROADWAY: 44'-0" F/F PARAPETS H 520-44 AND THE ALTERNATE MILITARY LOADING
LOADING: MILITARY LOADING
SKREW: 39° 32' 10" LEFT FORWARD W/R TO LOCAL TANGENT OF SPIRAL
WEARING SURFACE: MONOLITHIC CONCRETE
ALIGNMENT: TANGENT
APPROACH SLABS: AS-1-81 (20' LONG)

ADACHE ASSOCIATES INC., ENGINEERS
CLEVELAND 42, OHIO

SITE PLAN

BRIDGE NO. ERI-2-1781
HURON AVERY RD. OVER S.R.2
ERIE COUNTY STA. 18+50.53 TO ERI-2-16.13 STA. 21+60.37
DESIGNED NOYER DRAWN J.T. CHECKED L.A. REVIEWED L.E.D. DATE 9.21.85

ERI-2-1773

STRUCTURE ERI-2-1701L (SFN 2201208)

ITEM	ITEM EXT.	QUANTITY	UNIT	DESCRIPTION	REFERENCE SHEET
202	11301	4.5	CU YD	PORTIONS OF STRUCTURE REMOVED, AS PER PLAN	37
509	10000	822	POUND	EPOXY COATED REINFORCING STEEL	
510	10000	90	EACH	DOWEL HOLES WITH NONSHRINK, NONMETALLIC GROUT	
511	34401	5	CU YD	CLASS S CONCRETE, SUPERSTRUCTURE, AS PER PLAN (PARAPET RECONSTRUCTION)	38
512	10100	518	SQ YD	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)	
512	10400	611	SQ YD	TREATING OF CONCRETE BRIDGE DECK WITH SRS	
516	13600	1	SQ FT	1" PREFORMED EXPANSION JOINT FILLER	
601	28000	18	CU YD	DUMPED ROCK FILL, TYPE D	

STRUCTURE ERI-2-1701R (SFN 2201216)

ITEM	ITEM EXT.	QUANTITY	UNIT	DESCRIPTION	REFERENCE SHEET
202	11301	4.5	CU YD	PORTIONS OF STRUCTURE REMOVED, AS PER PLAN	37
509	10000	822	POUND	EPOXY COATED REINFORCING STEEL	
510	10000	90	EACH	DOWEL HOLES WITH NONSHRINK, NONMETALLIC GROUT	
511	34401	5	CU YD	CLASS S CONCRETE, SUPERSTRUCTURE, AS PER PLAN (PARAPET RECONSTRUCTION)	38
512	10100	518	SQ YD	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)	
512	10400	611	SQ YD	TREATING OF CONCRETE BRIDGE DECK WITH SRS	
516	13600	1	SQ FT	1" PREFORMED EXPANSION JOINT FILLER	
601	28000	4	CU YD	DUMPED ROCK FILL, TYPE D	

STRUCTURE ERI-2-1781 (SFN 2201224)

ITEM	ITEM EXT.	QUANTITY	UNIT	DESCRIPTION	REFERENCE SHEET
202	11301	.6	CU YD	PORTIONS OF STRUCTURE REMOVED, AS PER PLAN	37
202	98200	114	FT	REMOVAL MISC.: ELASTOMERIC STRIP SEAL	37
511	71100	.6	CU YD	CONCRETE MISC.: ABUTMENT REPAIR	38
512	10100	1176	SQ YD	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)	
512	10400	1456	SQ YD	TREATING OF CONCRETE BRIDGE DECK WITH SRS	
512	73500	1	SQ YD	TREATING CONCRETE BRIDGE DECKS WITH GRAVITY FED RESIN	
516	01301	114	FT	ELASTOMERIC STRIP SEAL WITHOUT STEEL EXTRUSIONS, AS PER PLAN	38
526	98100	2	SQ YD	APPROACH SLABS, MISC.: PATCHING	38-39

I:\projects\18296\structure\strquant.dgn
 t/jackson 3/1/2006

DRAWING FILE
 MODIFICATIONS

DESIGN AGENCY
 ODOT
 DISTRICT THREE

DATE
 2/06
 DCW
 STRUCTURE FILE NUMBER


DRAWN
 BTR
 REVISED
 BTR
 CHECKED
 DJV

STRUCTURE SUMMARY


ERI-2-16.13

34
 61

ERI-2-1773



PLAN VIEW



BACKWALL DETAIL

ITEM	QUANTITY	UNIT	DESCRIPTION
202	.6	CU YD	PORTION OF STRUCTURE REMOVED, AS PER PLAN
202	114	FT.	REMOVAL MISC. ELASTOMERIC STRIP SEAL
511	.6	SQ YD	CONCRETE MISC., ABUTMENT REPAIR
512	1456	SQ YD	TREATING OF CONCRETE BRIDGE DECK WITH SRS
512	1	SQ YD	TREATING CONCRETE BRIDGE DECKS WITH GRAVITY FED RESIN
516	114	FT.	ELASTOMERIC STRIP SEAL WITHOUT STEEL EXTRUSIONS, AS PER PLAN
526	2	SQ YD	APPROACH SLAB, MISC. PATCHING

NOTES:
1) THE EXISTING GUARDRAIL IS NOT SHOWN.

QUANTITIES CARRIED TO STRUCTURE SUMMARY SHEET

I:\projects\18296\structure\ERI21781\ERI021781SD.dgn
 t/jackson 3/11/2006

DISTRICT THREE
 OFFICE OF PRODUCTION
 DATE 2/06
 DCN
 STRUCTURE FILE NUMBER 2201224
 DRAWN GTS
 REVISIONS
 DESIGNED GTS
 CHECKED DJV
 PLAN VIEW
 ERI - 2 - 1781
 UNDER COUNTY ROAD 123
 ERI - 2 - 16.13
 1 / 2
 51
 61

ERI-2-1773

DESIGN AGENCY
DISTRICT THREE
OFFICE OF PRODUCTION

DATE
02/06

REVIEWED
DCM

STRUCTURE FILE NUMBER
2201224

DRAWN
GTS

REVISED

DESIGNED
GTS

CHECKED
DJV

SEALING DETAILS


ERI - 2 - 1781

UNDER COUNTY ROAD 123


ERI-2-16.13

2 / 2


52
61




TYPICAL SECTION AT PARAPET
LENGTH = 305'-9"±



PIER CAP ELEVATION VIEW
WIDTH = 3'-0"±



TYPICAL SECTION AT WINGWALL
LENGTH = 16'-3"± AVG.



TYPICAL SECTION AT ABUTMENT
LENGTH = 59'-5"

ITEM	QUANTITY	UNIT	DESCRIPTION
512	1176	SQ YD	SEALING OF CONCRETE STRUCTURES (EPOXY-URETHANE)

NOTES:

1) THE PARAPETS AND ALL EXPOSED AREAS OF THE WINGWALLS AND ENTIRE PIER CAP SHALL BE SEALED WITH ITEM 512.

2) THE SEALING AREA DETAILS ARE NOT TO SCALE.

QUANTITY CARRIED TO STRUCTURE SUMMARY SHEET

I:\projects\18296\struct\ERI21781\ERI021781SD.dgn
DATE 3/1/2006
TJACKSON