

WORK LIMITS

THE WORK LIMITS SHOWN ON THESE PLANS ARE FOR PHYSICAL CONSTRUCTION ONLY. PROVIDE THE INSTALLATION AND OPERATION OF ALL WORK ZONE TRAFFIC CONTROL AND WORK ZONE TRAFFIC CONTROL DEVICES REQUIRED BY THESE PLANS WHETHER INSIDE OR OUTSIDE THESE WORK LIMITS.

FINAL ACCEPTANCE

FINAL ACCEPTANCE OF APPROVED COMPLETED RPMS SHALL BE 90 DAYS AFTER THE LAST INSTALLATION HAS BEEN COMPLETED. RAISED PAVEMENT MARKER MATERIALS WHICH ARE UNACCEPTABLE OR BECOME UNACCEPTABLE PRIOR TO FINAL ACCEPTANCE AS DETERMINED BY THE ENGINEER, FOR ALL CAUSES SUCH AS, BUT NOT LIMITED TO, IMPROPER INSTALLATION, EPOXY NOT HARDENING OR LOSS OF ADHESION TO THE PAVEMENT OR BETWEEN THE CASTING AND THE PRISMATIC RETRO-REFLECTOR, AND LOST OR IMPROPERLY REFLECTING PRISMATIC RETRO-REFLECTOR SHALL BE REPLACED BY THE CONTRACTOR WITH RPM MATERIAL CONFORMING TO THESE SPECIFICATIONS AND REQUIREMENTS AT THE EXPENSE OF THE CONTRACTOR WITHOUT DELAY. THE CONTRACTOR WILL RECEIVE NO PAYMENT FOR UNACCEPTABLE WORK WHICH IS NON-PERFORMED.

Removed "ITEM 621 RPM, MISC.: REPLACEMENT OF RPM CASTING" note & quantity

TRAFFIC CONTROL INSPECTOR

THE CONTRACTOR SHALL DESIGNATE AN INDIVIDUAL OTHER THAN THE SUPERINTENDENT AND SUBJECT TO THE APPROVAL OF THE ENGINEER, TO CONTINUOUSLY INSPECT ALL TRAFFIC CONTROL DEVICES WHENEVER CONSTRUCTION WORK IS BEING PERFORMED WITHIN THE WORK LIMITS OF THE PROJECT. THE DESIGNATED INDIVIDUAL SHALL ALSO INSPECT ALL TRAFFIC DEVICES AT THE BEGINNING AND AT THE END OF EACH WORK DAY. THE DESIGNATED INDIVIDUAL OR A QUALIFIED REPRESENTATIVE SHALL ALSO BE AVAILABLE ON AN AROUND THE CLOCK BASIS TO REPAIR AND/OR REPLACE DAMAGED OR MISSING TRAFFIC CONTROL DEVICES. THESE INDIVIDUALS SHALL BE EQUIPPED WITH CELLULAR PHONES AND THEIR NAMES AND PHONE NUMBERS SHALL BE GIVEN TO THE PROJECT ENGINEER AT THE PRE-CONSTRUCTION MEETING. THE DESIGNATED INDIVIDUAL MAY HAVE OTHER CONSTRUCTION RELATED DUTIES AS LONG AS IMMEDIATE ATTENTION IS GIVEN TO TRAFFIC CONTROL. PAYMENT FOR THE SERVICES OF THE TRAFFIC CONTROL INSPECTOR SHALL BE INCLUDED IN THE LUMP SUM PRICE BID FOR ITEM 614 MAINTAINING TRAFFIC.

LANE CLOSURES

DURATION OF LANE CLOSURES AND RESTRICTIONS SHALL BE AS PER THE PERMITTED LANE CLOSURE CHART. THE PERMITTED LANE CLOSURE CHART USED FOR THIS PROJECT SHALL BE THE MOST CURRENT CHART AVAILABLE ON THE DATE THIS PROJECT SELLS.

THE CHART CAN BE FOUND AT:
<http://plcm.dot.state.oh.us>

SHOULD THE CONTRACTOR FAIL TO MEET ANY OF THE REQUIREMENTS IN THE CHART, THE CONTRACTOR SHALL BE ASSESSED DISINCENTIVES IN THE AMOUNT OF \$100 PER MINUTE OR PORTION THEREOF THAT THE LANE REDUCTION REMAINS BEYOND THE SPECIFIED LIMIT.

STATE SCENIC ASHTABULA RIVER, GRAND RIVER, PYMATUNING CREEK & UPPER CUYAHOGA RIVER

THE CONTRACTOR SHALL NOT DISCHARGE TOXIC OR HAZARDOUS MATERIALS SUCH AS SEALANTS, PAINT, SOLVENTS, CLEANING AGENTS, EARTHEN MATERIALS, WASTE-WATER, FUELS OR DEBRIS OF ANY KIND TO A SCENIC RIVER, ITS TRIBUTARIES, OR DRAINAGE WAYS. IF REFUELING OF IMMOBILE EQUIPMENT IS NECESSARY WITHIN THE FLOODPLAIN OR NEAR ANY TRIBUTARY DRAINAGE WAYS, DITCHES, OR STREAM, THE CONTRACTOR SHALL PROVIDE SECONDARY CONTAINMENT WITH ENOUGH CAPACITY TO COMPLETELY CONTAIN AND COLLECT ALL POTENTIAL LIQUID WASTES IN THE EVENT OF A SPILL.

ANY AND ALL CONSTRUCTION DEBRIS, EARTHEN DEBRIS, EXCESS ASPHALT OR CONCRETE, WOOD DEBRIS FROM CLEARING, EXCESS FILL MATERIAL, AND TRASH SHOULD BE DISPOSED OF AT AN APPROVED UPLAND SITE OR LAND FILL ABOVE FEMA 100-YEAR FLOOD ELEVATIONS. DISPOSAL OF ANY SUCH MATERIALS WITHIN 1000 FEET OF THE STATE SCENIC ASHTABULA RIVER, GRAND RIVER, PYMATUNING CREEK AND UPPER CUYAHOGA RIVER IS PROHIBITED.

IN ACCORDANCE WITH ORC 3750.06, REPORTABLE SPILLS MUST BE REPORTED TO THE LOCAL FIRE DEPARTMENT (911), THE LOCAL EMERGENCY COORDINATOR MIKE FITCHET, ASHTABULA COUNTY EMA DIRECTOR (440-576-3500), ANDY FROST, MAHONING COUNTY EMA DIRECTOR (330-550-6481), RYAN SHACKELFORD, PORTAGE COUNTY EMA DIRECTOR (330-697-2689) TIM WARSTLER, STARK COUNTY EMA DIRECTOR (330-451-3911), TOMMY SMOOT, SUMMIT COUNTY EMA DIRECTOR (330-643-2522) AND JOHN HICKEY, TRUMBULL COUNTY EMA DIRECTOR (330-770-0222), AND THE OHIO SPILL LINE (1-800-282-9378), AND THE OHIO SPILL LINE (1-800-282-9378).

THE CONTRACTOR SHALL KEEP ALL IDLE EQUIPMENT, FUELS, LUBRICANTS, AND ANY STORAGE FOR/OF POTENTIALLY TOXIC OR HAZARDOUS MATERIALS OUT OF THE FEMA DESIGNATED SPECIAL FLOOD HAZARD AREA AND NOT WITHIN 1000 FEET OF THE STATE SCENIC ASHTABULA RIVER, GRAND RIVER, PYMATUNING CREEK AND UPPER CUYAHOGA RIVER.

THE CONTRACTOR SHALL NOTIFY THE PROJECT ENGINEER 40 DAYS PRIOR TO WORK WITHIN 1000 FEET OF THE STATE SCENIC ASHTABULA RIVER, GRAND RIVER, PYMATUNING CREEK AND UPPER CUYAHOGA RIVER. THE PROJECT ENGINEER SHALL NOTIFY THE DISTRICT ENVIRONMENTAL COORDINATOR 35 DAYS PRIOR TO WORK WITHIN 1000 FEET OF THE SCENIC RIVER. THE DISTRICT ENVIRONMENTAL COORDINATOR SHALL COORDINATE WITH ODNR SCENIC RIVERS A MINIMUM OF 15 DAYS PRIOR TO ANY WORK WITHIN 1000 FEET OF STATE SCENIC ASHTABULA RIVER, GRAND RIVER, PYMATUNING CREEK AND UPPER CUYAHOGA RIVER.

DESIGN AGENCY



DESIGNER
AJN

REVIEWER

RMMMM-DD-YY

PROJECT ID

109828

SHEET TOTAL

P.3 10

