


D04 PSIP Phase 2

MODEL: Sheet PAPER: 17x11 (in.) DATE: 3/19/2021 TIME: 1:16:50 PM USER: rhamma
 C:\DOT_OPV\117061A00 - STV-Safety Dgn 2019 PID108685003 PSIP D4 Final Dsn CE Clear\113278\400-Engineering\Traffic\Sheets\113278_TG001.dgn

SHEET NUM.											PART.			ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.							
					19	20	21	26	27	28	01/SAF/OT/ AKRON	02/SAF/OT/ CANT	03/SAF/OT/ YOUN													
											LS	LS	LS	201	11000	LS		ROADWAY								
											159	8	146	159	8	146	202	23000	313	SY	PAVEMENT REMOVED					
											300		987			564	1,167		684	202	30001	1,851	SF	WALK REMOVED, AS PER PLAN	6	
											100		556	21	1,028	616	21	1,068		202	32001	1,705	FT	CURB REMOVED, AS PER PLAN	6	
													88	7	71	88	7	71		202	32501	166	FT	CURB AND GUTTER REMOVED, AS PER PLAN	6	
													18			18				203	20000	18	CY	EMBANKMENT		
													53			53				204	10000	53	SY	SUBGRADE COMPACTION		
													1,396	258	467	1,396	258	467		608	10001	2,121	SF	4" CONCRETE WALK, AS PER PLAN	7	
											560					360		200		608	12001	560	SF	5" CONCRETE WALK, AS PER PLAN	7	
											400			542	6,759		542	7,159		608	52001	7,701	SF	CURB RAMP, AS PER PLAN	6	
											112	104	504	27	42	107	608	74		608	53021	789	SF	DETECTABLE WARNING, AS PER PLAN	6	
											800			4,116		4,916				608	98000	4,916	SF	WALKWAY, MISC.: AKRON CURB RAMP	6	
																319		319		608	98000	319	SF	WALKWAY, MISC.: REMOVE AND REUSE DECORATIVE BRICK WALK	6	
																					EROSION CONTROL					
																1,000		1,000		832	30000	3,000	EACH	EROSION CONTROL		
																					PAVEMENT					
														171	23	308	171	23	308		251	01001	502	SY	PARTIAL DEPTH PAVEMENT REPAIR (441), AS PER PLAN	6
														137	8	130	137	8	130		253	01001	275	SY	PAVEMENT REPAIR, AS PER PLAN	6
														22		22	22				452	12011	22	SY	8" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC 1P, AS PER PLAN	6
														41	6	41	41	6			609	12001	47	FT	COMBINATION CURB AND GUTTER, TYPE 2, AS PER PLAN	7
														120		126	120		126		609	26001	246	FT	CURB, TYPE 6, AS PER PLAN	7
														189	54	152	189	54	152		609	72001	395	SY	CONCRETE MEDIAN, AS PER PLAN	7

TRAFFIC GENERAL SUMMARY

DESIGN AGENCY	
	
DESIGNER	RSH
REVIEWER	LAS 10/23/20
PROJECT ID	113278
SHEET	TOTAL
15	92