

PART	LOG-117 0126	LOG-117 0364					ITEM	ITEM EXTENSION	GRAND TOTAL	UNIT	DESCRIPTION
	1396	1917					202	23501	3313	SQ. YD.	WEARING COURSE REMOVED, AS PER PLAN
	2.3						SPEC	51631400	2.3	CU. YD.	POLYMER MODIFIED ASPHALT EXPANSION JOINT SYSTEM
	-	-								EACH	Wedges
	1.75"	-									Proposed Asphalt Concrete Thickness
	-	4.0"									Wearing Course Removed Thickness

BRIDGE NO.	LENGTH (Bridge Limits) FT.	WIDTH FT.	BRIDGE DECK AREA S.Y.	STRUCTURE FILE NUMBER	COMMENTS (Wearing Course)
LOG-117-0126	79.07	44.00	387	4601858	5" - 7" Existing Asphalt Concrete
LOG-117-0364	175.13	40.00	778	4601866	Existing Concrete Deck and Approach Slabs

Quantities to be carried to the General Summary

CALCULATED BY  
LOGAN COUNTY  
LOG-117-0.00

BRIDGE SUMMARY