

SHEET NUMBER											PART.			ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
				4	5	7	8	9	10		01/S5K	02/STR	03/NFA						
				1,750							500	1,000	250	251	01001	1,750	SY	PAVEMENT	
						436,697					135,969	210,845	89,883	422	11000	436,697	SY	AGGREGATE, SINGLE CHIP SEAL, TYPE A	
						174,677					54,386	84,338	35,953	422	25000	174,677	GAL	EMULSION, CHIP SEAL, 0.40 GAL/SY	
						16,315					16,315			886	11000	16,315	GAL	FOG SEAL, 0.12 GAL/SY	
																		TRAFFIC CONTROL	
									2,129		689	1,019	421	621	00100	2,129	EACH	RPM	
								2,129			689	1,019	421	621	54000	2,129	EACH	RAISED PAVEMENT MARKER REMOVED	
							112.72				31.72	56.48	24.52	642	00104	112.72	MILE	EDGE LINE, 6", TYPE 1	4
							56.36				15.86	28.24	12.26	642	00300	56.36	MILE	CENTER LINE, TYPE 1	
							1,000				1,000			642	00400	1,000	FT	CHANNELIZING LINE, 8", TYPE 1	
							364				162	132	70	642	00500	364	FT	STOP LINE, TYPE 1	
							730				730			642	00620	730	FT	CROSSWALK LINE, 12", TYPE 1	
							8					4	4	642	01000	8	EACH	RAILROAD SYMBOL MARKING, TYPE 1	
							962				962			642	01200	962	FT	PARKING LOT STALL MARKING, TYPE 1	
							4				4			642	01702	4	EACH	HANDICAP SYMBOL MARKING, TYPE 1	
							500				500			642	30000	500	FT	REMOVAL OF PAVEMENT MARKING, CHANNELIZING LINE, 8", TYPE 1	
							365				365			642	30000	365	FT	REMOVAL OF PAVEMENT MARKING, CROSSWALK LINE, 12", TYPE 1	
							481				481			642	30000	481	FT	REMOVAL OF PAVEMENT MARKING, PARKING LOT STALL, TYPE 1	
							182				81	66	35	642	30000	182	FT	REMOVAL OF PAVEMENT MARKING, STOP LINE , TYPE 1	
							2				2			642	30020	2	EACH	REMOVAL OF PAVEMENT MARKING, HANDICAP SYMBOL, TYPE 1	
							4					2	2	642	30020	4	EACH	REMOVAL OF PAVEMENT MARKING, RAILROAD SYMBOL MARKING	
								28.18			7.93	14.12	6.13	642	30030	28.18	MILE	REMOVAL OF PAVEMENT MARKING, CENTERLINE , 6"	
								56.36			15.86	28.24	12.26	642	30030	56.36	MILE	REMOVAL OF PAVEMENT MARKING, EDGE LINE , 6"	
					20						20			614	11110	20	HOUR	MAINTENANCE OF TRAFFIC	
							64.29				23.79	28.24	12.26	614	21100	64.29	MILE	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	
							128.58				47.58	56.48	24.52	614	22110	128.58	MILE	WORK ZONE CENTER LINE, CLASS I, 642 PAINT	
							1,500				1,500			614	23200	1,500	FT	WORK ZONE EDGE LINE, CLASS I, 6", 642 PAINT	
							445				243	132	70	614	26200	445	FT	WORK ZONE CHANNELIZING LINE, CLASS I, 8", 642 PAINT	
																		WORK ZONE STOP LINE, CLASS I, 642 PAINT	
							1,095				1,095			614	27050	1,095	FT	WORK ZONE CROSSWALK LINE, CLASS I, 12", 642 PAINT	
							8					4	4	614	32200	8	EACH	WORK ZONE RAILROAD SYMBOL MARKING, CLASS I, 642 PAINT	
											LS	LS	LS	614	11000	LS		INCIDENTALS	
											LS	LS	LS	624	10000	LS		MAINTAINING TRAFFIC	
																		MOBILIZATION	

GENERAL SUMMARY

DESIGN AGENCY



DESIGNER

CJP

REVIEWER

BJA 7/18/2025

PROJECT ID

114554

SHEET

P.6

TOTAL

11

PAVEMENT MARKING SUBSUMMARY (1/2)	
DESIGN AGENCY	
	
DESIGNER	
CJP	
REVIEWER	
BJA 7/18/2025	
PROJECT ID	
114554	
SHEET	TOTAL
P.8	11