

**632 RELAMP EXISTING SIGNAL SECTION WITH LED LAMP UNIT, BY LENS TYPE, AS PER PLAN**

The contractor shall replace an existing light emitting diode (LED) lamp unit with the appropriate LED lamp unit. The LED signal lamp units shall meet the requirements of CM&S 732.04. All lamp unit replacements shall be completed by 3/31/2023. See below for locations:

Intersections:						SLM:	Red Ball	Yellow Ball	Green Ball	Yellow Arrow	Green Arrow	Red Arrow
CLA	US	40	&	SR	571	2.08	8	8	8			
CLA	SR	334	&	CR	Derr Road (CR 385)	2.31	8	8	8			
CLA	US	68	&	SR	41 SB Ramp	8.89	10	10	10	1	1	
CLA	US	68	&	SR	41 NB Ramp	8.89	7	7	7	1	1	
MIA	IR	75	&	CR	25A SB Ramp (Farrington)	13.14	5	5	5	2	2	2
MIA	IR	75	&	US	36 NB Ramp	16.72	8	8	8	1	1	
MIA	IR	75	&	US	36 SB Ramp	16.73	8	8	8	1	1	
MIA	SR	571	&	CR	Peters Road (CR 149)	11.83	8	8	8			
MIA	SR	202	&	CR	Ross Road (CR 179)	2.02	8	8	8			
MOT	SR	48	&	TR	Waverly-Wampler Avenue (TR 163)	16.22	8	8	8			
MOT	SR	48	&	TR	Northtowne Center-Castlewood Avenue (TR 1177)	16.48	10	10	10	1	1	
MOT	SR	48	&	TR	Nottingham Road (TR 1157)	16.56	10	10	10	4	4	
MOT	SR	48	&	CR	Turner-Shoup Mill Road (CR 74)	17.09	11	11	11	6	6	3
MOT	SR	48	&	CR	Markey Road (CR 61)	17.23	7	7	7			
MOT	SR	48	&	CR	Philadelphia Drive (CR 159)	17.76	10	10	10	3	3	
MOT	SR	48	&	CR	Shiloh Springs Road (CR 26)	17.87	7	7	7	2	2	
MOT	SR	48	&	TR	Woodbury Drive (TR 2103)	18.50	10	10	10	2	2	
MOT	IR	75	&	CR	Northwoods Blvd (NB Ramp)	22.73	8	8	8	1	1	
MOT	SR	741	&	CR	Alex-Bell Road (CR 78)	6.06	12	12	12	6	6	
MOT	SR	741	&	PD	Meijers Drive	5.86	11	11	11	6	6	
MOT	SR	741	&	TR	West Tech Road (TR	0.18	9	9	9	3	3	2

These quantities have been carried to the General Summary and are included in the Total Quantity.

GENERAL NOTES

D07 - TSG MAINT - FY23