


SHEET NUM.										PART.			ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
3	6									01/SAF/21/IMS	02/SAF/21/NHS	03/SAF/21/S>2						
TRAFFIC CONTROL																		
	3.88									3.14	0.52	0.22	645	00117	3.88	MILE	EDGE LINE, 6", TYPE A3, AS PER PLAN	4
	2.5									2.18	0.08	0.24	645	00217	2.5	MILE	LANE LINE, 6", TYPE A3, AS PER PLAN	4
	0.25										0.18	0.07	645	00311	0.25	MILE	CENTER LINE, TYPE A3, AS PER PLAN	4
	1,885									1,735		150	645	00417	1,885	FT	CHANNELIZING LINE, 12", TYPE A3, AS PER PLAN	4
	275									275			645	01565	275	FT	DOTTED LINE, 12", TYPE A3, AS PER PLAN	4
	146.77									123.73	17	6.04	807	13010	146.77	MILE	WET REFLECTIVE SPRAY THERMOPLASTIC PAVEMENT MARKING, EDGE LINE, 6"	
	91.92									83.26	6.68	1.98	807	13110	91.92	MILE	WET REFLECTIVE SPRAY THERMOPLASTIC PAVEMENT MARKING, LANE LINE, 6"	
	2.99										2.72	0.27	807	13200	2.99	MILE	WET REFLECTIVE SPRAY THERMOPLASTIC PAVEMENT MARKING, CENTER LINE	
	68,322									61,390	3,326	3,606	807	13310	68,322	FT	WET REFLECTIVE SPRAY THERMOPLASTIC PAVEMENT MARKING, CHANNELIZING LINE, 12"	
	9,305									6,020	1,985	1,300	807	13410	9,305	FT	WET REFLECTIVE SPRAY THERMOPLASTIC PAVEMENT MARKING, DOTTED LINE, 6"	
	30,100									29,900		200	807	13430	30,100	FT	WET REFLECTIVE SPRAY THERMOPLASTIC PAVEMENT MARKING, DOTTED LINE, 12"	
	241.76									207.07	26.4	8.29	850	10010	241.76	MILE	GROOVING FOR 6" RECESSED PAVEMENT MARKING, (ASPHALT)	
	9,305									6,020	1,985	1,300	850	10110	9,305	FT	GROOVING FOR 6" RECESSED PAVEMENT MARKING, (ASPHALT)	
	98,422									91,290	3,326	3,806	850	10130	98,422	FT	GROOVING FOR 12" RECESSED PAVEMENT MARKING, (ASPHALT)	
	6.63									5.32	0.78	0.53	850	20010	6.63	MILE	GROOVING FOR 6" RECESSED PAVEMENT MARKING, (CONCRETE)	
	2,160									2,010		150	850	20130	2,160	FT	GROOVING FOR 12" RECESSED PAVEMENT MARKING, (CONCRETE)	
MAINTENANCE OF TRAFFIC																		
500										468	16	16	614	11110	500	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	
4										4			614	18601	4	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	3
INCIDENTALS																		
										LS	LS	LS	614	11000	LS		MAINTAINING TRAFFIC	
										LS	LS	LS	624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

DESIGN AGENCY



DESIGNER
WWH

REVIEWER
PMM 11/21/22

PROJECT ID
114853

SHEET TOTAL
P.5 | 6

PID	COUNTY	PLAN SPLIT	ROUTE	BEGIN SLM	END SLM	807		807		807		807		645		645		645		645		645		850		850		850		850		850	
						WET REFLECTIVE SPRAY THERMOPLASTIC PAVEMENT MARKING, LANE LINE, 6 INCH	WET REFLECTIVE SPRAY THERMOPLASTIC PAVEMENT MARKING, CENTER LINE	WET REFLECTIVE SPRAY THERMOPLASTIC PAVEMENT MARKING, EDGE LINE, 6 INCH	WET REFLECTIVE SPRAY THERMOPLASTIC PAVEMENT MARKING, CHANNELIZING LINE, 12 INCH	WET REFLECTIVE SPRAY THERMOPLASTIC PAVEMENT MARKING, DOTTED LINE, 6 INCH	WET REFLECTIVE SPRAY THERMOPLASTIC PAVEMENT MARKING, DOTTED LINE, 12 INCH	LANE LINE, 6 INCH, TYPE A3, AS PER PLAN	CENTER LINE, TYPE A3, AS PER PLAN	EDGE LINE, 6 INCH, TYPE A3, AS PER PLAN	CHANNELIZING LINE, 12 INCH, TYPE A3, AS PER PLAN	DOTTED LINE, 12 INCH, TYPE A3, AS PER PLAN	GROOVING FOR 6 INCH RECESSED PAVEMENT MARKING, ASPHALT	GROOVING FOR 6 INCH RECESSED PAVEMENT MARKING, ASPHALT	GROOVING FOR 12 INCH RECESSED PAVEMENT MARKING, ASPHALT	GROOVING FOR 6 INCH RECESSED PAVEMENT MARKING, CONCRETE	GROOVING FOR 12 INCH RECESSED PAVEMENT MARKING, CONCRETE												
						MILE	MILE	WHITE MILE	YELLOW MILE	FOOT	FOOT	FOOT	MILE	MILE	WHITE MILE	YELLOW MILE	FOOT	FOOT	FOOT	MILE	FOOT	MILE	FOOT	MILE	FOOT	MILE	FOOT	MILE	FOOT				
105215	HAM	03/SAF/21/S>2	125	1.530	1.810	0.380	0.270	0.360					0.090	0.070	0.070										1.010			0.230					
		03/SAF/21/S>2	125 3/2 RAMP A					0.070	0.070																0.140								
		03/SAF/21/S>2	125 3/2 RAMP B					0.280	0.280																0.560								
		03/SAF/21/S>2	125 3/2 RAMP C					0.250	0.250																0.500								
		03/SAF/21/S>2	125 3/2 RAMP D					0.120	0.120																0.240								
105676	GRE	02/SAF/21/NHS	235	9.290	11.350	1.540	2.720	4.040		1326	840			0.180	0.360									840	8.300	1326	0.540						
107957	GRE	02/SAF/21/NHS	35	11.940	14.510	5.140		5.060	5.060	1580	1145		0.080		0.080	0.080								1145	15.260	1580	0.240						
		02/SAF/21/NHS	35 EB RAMP TO US 68					0.220	0.220	250															0.440	250							
		02/SAF/21/NHS	RAMP 68 TO 35 EB					0.340	0.340	170															0.680	170							
		02/SAF/21/NHS	35 WB RAMP TO 68					0.260	0.260																0.520								
		02/SAF/21/NHS	RAMP 68 TO 35 WB					0.160	0.160																0.320								
		02/SAF/21/NHS	35 EB RAMP TO BICKETT					0.180	0.180																0.360								
		02/SAF/21/NHS	RAMP BICKETT TO 35 WB					0.260	0.260																0.520								
105305	CLE	03/SAF/21/S>2	450	0.000	1.060	1.600		2.120	2.120	3606	1300	200	0.151		0.075	0.075	150							1300	5.840	3806	0.301	150					
96654	PRE	01/SAF/21/IMS	70 EB INCLUDING RAMPS	0.000	13.750	17.764		18.616	18.724	8575	3380		0.186		0.640	0.688	585	275						3380	55.104	8575	1.514	860					
		01/SAF/21/IMS	70 WB INCLUDING RAMPS	0.000	16.500	17.665		18.188	18.182	5065	2640		0.187		0.187	0.187								2640	54.122	5065	0.561						
94256	HAM	01/SAF/21/IMS	275, US42 TO LITTLE MIAMI RIVER	1359+00	1682+50	24.621		15.388	15.435	29200		18100	1.581		0.643	0.643	1150								55.440	47300	2.867	1150					
104667	HAM	01/SAF/21/IMS	75, WESTERN HILLS VIADUCT TO MITCHELL	3127+69	305+50	23.210		9.214	9.981	18550		11800	0.227		0.075	0.075									42.405	30350	0.377						
SUBTOTAL						91.920	2.990	75.126	71.642	68322	9305	30100	2.502	0.250	2.130	1.748	1885	275	9305	241.761	98422	6.630	2160										
TOTAL CARRIED TO GENERAL SUMMARY						91.920	2.990	146.768	68322	9305	30100	2.502	0.250	3.878	1885	275	9305	241.761	98422	6.630	2160												

PAVEMENT MARKINGS SUBSUMMARY

DESIGN AGENCY

 DESIGNER
 WWH
 REVIEWER
 PMM 11/18/22
 PROJECT ID
 114853
 SHEET TOTAL
 P.6 6