

I:\Project+Data\0759\Roadway\Sheets\0759\G0002.dgn Sheet 23-NOV-2022 3:36PM dho.fmal

SHEET NUM.										PART.			ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
15	21	28	34	40	42	01/ NHS/OT	02/ S<2/OT	03/ STR/OT										
<b>LIGHTING</b>																		
		4					4		625	00450	4	EACH	CONNECTION, FUSED PULL APART					
		4					4		625	00460	4	EACH	CONNECTION, UNFUSED PULL APART					
		6					6		625	00480	6	EACH	CONNECTION, UNFUSED PERMANENT					
	4	2			1	1	6		625	18510	7	EACH	BRACKET ARM, 30'					
		304					304		625	23200	304	FT	NO. 4 AWG 2400 VOLT DISTRIBUTION CABLE					
		245					245		625	23400	245	FT	NO. 10 AWG POLE AND BRACKET CABLE					
66							66		625	25400	66	FT	CONDUIT, 2", 725.04					
28	46		22	139		20	96	139	625	25500	255	FT	CONDUIT, 3", 725.04					
16							16		625	25550	16	FT	CONDUIT, 3-1/2", 725.04					
				30				30	625	25600	30	FT	CONDUIT, 4", 725.04					
142							142		625	25902	142	FT	CONDUIT, JACKED OR DRILLED, 725.04, 3"					
		2					2		625	26253	2	EACH	LUMINAIRE, CONVENTIONAL, SOLID STATE (LED), AS PER PLAN (150W LED, 120V)	12				
110	23	11	154		10	10	144	154	625	29000	308	FT	TRENCH					
3							3		625	30700	3	EACH	PULL BOX, 725.08, 18"					
1	1	1	1		1	1	3	1	625	30706	5	EACH	PULL BOX, 725.08, 24"					
4	5	5	11		5	5	14	11	625	32000	30	EACH	GROUND ROD					
110	23	11	154		10	10	144	154	625	36010	308	FT	UNDERGROUND WARNING/MARKING TAPE					
1							1		625	76000	1	EACH	ARC FLASH CALCULATIONS AND LABEL, (COL-62-2.86)					
	1						1		625	76000	1	EACH	ARC FLASH CALCULATIONS AND LABEL, (COL-62-13.26)					
		1					1		625	76000	1	EACH	ARC FLASH CALCULATIONS AND LABEL, (COL-CR447-3.39)					
			1					1	625	76000	1	EACH	ARC FLASH CALCULATIONS AND LABEL, (HOL-39-28.25)					
					1	1			625	76000	1	EACH	ARC FLASH CALCULATIONS AND LABEL, (TUS-250-21.73)					
<b>TRAFFIC CONTROL</b>																		
					22			22	630	02100	22	FT	GROUND MOUNTED SUPPORT, NO. 2 POST	Updated Sign Hanger Assembly				
	2					2	2		630	79000	4	EACH	SIGN HANGER ASSEMBLY, SPAN WIRE	Item from Mast Arm to Span Wire				
	36					17.8	36		630	80100	53.8	SF	SIGN, FLAT SHEET					
					5			5	630	85100	5	EACH	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION					
					2			2	630	86002	2	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL					
					1			1	630	86010	1	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND REERECTION					
					62			62	646	10400	62	FT	STOP LINE					
					156			156	646	10520	156	FT	CROSSWALK LINE, 24"					
					1			1	646	20300	1	EACH	LANE ARROW					
					1			1	646	50000	1	EACH	REMOVAL OF PAVEMENT MARKING					
					146			146	646	50100	146	FT	REMOVAL OF PAVEMENT MARKING					

GENERAL SUMMARY

D11-TSG-FY2023