

I:\ProjectData\13231\Design\Roadway\Sheets\13231_TS001.dgn_Sheet 22-JAN-2021 8:52AM jberanek

COUNTY	ROUTE	BEGIN SLM	DESCRIPTION	END SLM	DESCRIPTION	807		807	LANE LINE ESSLM#	807	807	850	850	850	850	REMARKS (FUNDING)
						WET REFLECTIVE EPOXY PAVEMENT MARKING, EDGE LINE, 6"		WET REFLECTIVE EPOXY PAVEMENT MARKING, LANE LINE, 6"		WET REFLECTIVE EPOXY PAVEMENT MARKING, CHANNELIZING LINE, 12"	WET REFLECTIVE EPOXY PAVEMENT MARKING, DOTTED LINE, 6"	GROOVING FOR 6" RECESSED MARKING, (ASPHALT)	GROOVING FOR 6" RECESSED MARKING, (ASPHALT)	GROOVING FOR 12" RECESSED MARKING, (ASPHALT)	GROOVING FOR 6" RECESSED MARKING, (CONCRETE)	
						WHITE MILE	YELLOW MILE	MILE		MILE	FT	FT	MILE	FT	FT	
NHS ROUTES																
COLUMBIANA	US 30	28.03	0.46 MILES WEST OF SR 7 INTERCHANGE	31.32	0.18 MILES EAST OF SR 170 INTERCHANGE	8.72	7.70	6.56	1.640	2,484	3,290	22.98	3,290	2,484		SLM 28.52 - INCLUDE SR 7/SR 267 RAMPS SLM 31.14 - INCLUDE SR 170 WESTERN RAMPS
COLUMBIANA	SR 7	0.00	COLUMBIANA COUNTY LINE	3.56	0.04 MILES EAST OF CR 427 (KOUNTZ AVE)	9.58	9.58	7.61	1.903	5,708	6,642	26.77	6,642	5,708		SLM 0.59 - INCLUDE CLARK AVE RAMPS SLM 1.27 - INCLUDE SR 39 RAMPS SLM 2.76 - INCLUDE SR 45 RAMPS SLM 3.05 - INCLUDE SR 45 RAMPS
COLUMBIANA	SR 11	22.70	0.05 MILES NORTH OF SR 164 OVERPASS	25.20	MAHONING COUNTY LINE	5.76	5.74	4.96	1.240	2,716	1,348	16.46	1,348	2,716		SLM 23.78 - INCLUDE SR 344 RAMPS
HARRISON	US 22	21.47	BEGINNING OF 4-LANE SECTION	25.23	JEFFERSON COUNTY LINE	8.99	8.67	7.66	1.915	1,881	3,545	25.32	3,545	1,881		SLM 21.88 - INCLUDE SR 151 RAMPS SLM 23.62 - INCLUDE SR 151 RAMPS
JEFFERSON	SR 7	31.13	NORTH APPROACH OF BRIDGE JEF-7-3103	34.55	COLUMBIANA COUNTY LINE	6.84	6.84	6.84	1.710	315	344	20.52	344	315		SLM 33.69 - INCLUDE MARKINGS AT SR 213
TUSCARAWAS	US 36	0.00	TUSCARAWAS COUNTY LINE	3.67	IR 77 NORTHBOUND OFF RAMP	7.34	7.34	7.34	1.835	3,673	1,984	21.36	1,984	3,673	0.66	SLM 0.91 - INCLUDE COLLEGE ST. RAMPS SLM 2.98 - INCLUDES 250' OF DOTTED LINE AT EDGES OF CR 15 INTERSECTION IN AND S LEGS SLM 3.53 TO 3.64 - CONCRETE SECTION
EDGE LINE SUB-TOTALS						47.23	45.87									
FUNDING (01/NHS/OT) SUB-TOTALS						93.10	40.97			16,777	17,153	133.41	17,153	16,777	0.66	(01/NHS/OT)
NON-NHS ROUTES																
TUSCARAWAS	US 36	3.67	IR 77 NORTHBOUND OFF RAMP	3.85	END OF 4-LANE SECTION	0.36	0.36	0.36	0.090	100		1.08		100		
EDGE LINE SUB-TOTALS						0.36	0.36									
FUNDING (02/S<2/OT) SUB-TOTALS						0.72	0.36			100	0	1.08	0	100	0.00	(02/S<2/OT)
* - EQUIVALENT SINGLE SOLID LINE LINEAR MILES, SEE GENERAL NOTES																
TOTALS CARRIED TO GENERAL SUMMARY						93.82	41.33			16,877	17,153	134.49	17,153	16,877	0.66	

CALCULATED JPB CHECKED CJV	PAVEMENT MARKING SUBSUMMARY	D11-PM-RWR2021
	4	8