

# PRE-BID MEETING

## DEL-36-11.03

PID: 103626

CONSTRUCTION PROJECT: 230002

CITY OF DELAWARE  
& ODOT DISTRICT 6

DECEMBER 15, 2022 AT 10:00AM



# PREBID MEETING

- The information shared in today's pre-bid meeting is provided as reference and is NOT contractual.
- Recording and transcript of today's meeting will be posted at:  
<ftp://ftp.dot.state.oh.us/pub/Contracts/Attach/DEL-103626/Reference%20Files/>


# PRESENTATION OUTLINE

- Team Introductions
- Project Location
- Project Overview
- Utility Note
- Schedule
- Questions

# DESIGN TEAM

- City of Delaware
- ODOT District 6
- Gannett Fleming
  - EMH&T(Environmental, Survey, ROW Plans, and Landscaping)
  - HDR (Geotechnical, Track, Lighting, Signals, and Traffic Control)

# LOCATION



DEL-36-11.03 (PID 103626) (Project # 230002) Prebid Meeting  
12/15/2022

# LOCATION



# LOCATION



DEL-36-11.03 (PID 103626) (Project # 230002) Prebid Meeting  
12/15/2022

# LOCATION



DEL-36-11.03 (PID 103626) (Project # 230002) Prebid Meeting  
12/15/2022




# LOCATION



DEL-36-11.03 (PID 103626) (Project # 230002) Prebid Meeting  
12/15/2022

# PROJECT OVERVIEW

- Roadway
  - Resurfacing and Full Depth Widening
  - Full Depth Reconstruction
  - Pedestrian Amenities




# PROJECT OVERVIEW

- Roadway (cont.)
  - Building Removals



# PROJECT OVERVIEW

- Roadway (cont.)
  - Advanced Limited Clearing and Grubbing
  - Stumps will remain
  - Completed prior to March 31, 2023



# PROJECT OVERVIEW

- Drainage
- Pavement
- Water
- Sanitary
- Lighting
- Traffic Control
- Traffic Signals
- Landscaping

# PROJECT OVERVIEW

## 🕒 Bridge (looking west)



# PROJECT OVERVIEW

- Bridge
  - Temporary Bridge: Lump Sum (Deck)
    - Includes all pieces and parts and labor needed to construct the closed timber deck and walkways (including railroad submittals)
  - Temporary Bridge: Lump Sum (Tied Wall)
    - Includes all pieces and parts and labor needed to construct tied shoring wall (excluding granular backfill)
  - Drilled Shafts: Concrete Mix Design
    - 7" maximum slump allowed per notes
    - Several shafts need to go through the existing south abutment (identified in the plans)

# PROJECT OVERVIEW

- Track & Railroad Coordination
  - Temporary rail runaround on east side
  - Embankment placed up to bottom of subballast
    - 6" Lifts per NSRR Specifications
  - Subballast is placed by the ODOT contractor
  - Contractor to provide NSRR compliant ballast atop bridge deck waterproofing
  - Force Account to provide & install ballast and track/ties
  - Removed trackwork and ballast remains the property of the contractor
  - Temporary embankment to be removed
- Flagging is to be contracted directly by the contractor with an approved vendor



# OVERVIEW

- Norfolk Southern Permitting
  - Permitting of public utilities is to be completed by the contractor, prior the construction of each utility
  - Permitting through RailPros can be time consuming, note the 70-business day minimum expected lead time in the plan notes (27/644)
    - Anticipated permits required for: Water, Sanitary, Storm, Fiber (interconnects), and electric (underpass lighting).
    - Includes preparation of exhibits
    - Includes permit application fee
    - Includes necessary flagging coordination for the installation of utilities

# PROJECT OVERVIEW

- MOT
  - Three phases
  - Construction sequence notes (29-30/644)
  - Maintaining one lane in each direction




# UTILITY NOTE

- AEP
- Columbia Gas
- Suburban Gas
- Telecommunication companies

*Utility note will be updated via addendum prior to sale date with a contractual utility clear date.*

# UTILITY NOTE

- Shared Fiber Duct bank installed early 2021



# SCHEDULE

- 12.15.22 – Prebid Mtg
- aa.bb.cc – Addendum #1
- 01.26.23 – Sale Date
- 02.06.23 – Award Date
- 03.06.23 - 09.30.25 – Estimated Construction
  - Incentives/Disincentives
    - Phase 3.2 – 45 Day closure
    - Substantial Completion – September 15, 2025

# QUESTIONS ?

Please state your  
**Name & Company**  
Prior to asking your  
question.