

DEL-71-8.91 (Phase A), QUANTITY TABLE														
DESCRIPTION	203	203	203	203	659	659	659	659	659	659	659	659	659	659
	EXCAVATION	EMBANKMENT	BORROW, A.P.P	EMBANKMENT, A.P.P	SOIL ANALYSIS TEST	TOPSOIL	REPAIR SEEDING AND MULCHING	INTERSEEDING	COMMERCIAL FERTILIZER	LIME	WATER	SEEDING AND MULCHING, CLASS 1	SEEDING AND MULCHING, CLASS 3B	MOWING
	CY	CY	CY	CY	EA	CY	SY	SY	TON	ACRES	M. GAL	SY	SY	M. SF
TOTAL EARTHWORK	58456	166843	127000	23718										
TOTAL SEEDING AND MULCHING					2	11697	5269	5269	16	22	600	15401	89976	0.24
TOTALS CARRIED TO GENERAL SUMMARY SHEETS	58456	166843	127000	23718	2	11697	5269	5269	16	22	600	15401	89976	0.24

DEL-71-8.91 (Phase A), Earthworks Summary Sheet

Roadway	203 - EARTH- C.Y.				659 - Seeding - S.Y.		COMMENTS
	COMMON EXCAVATION	EMBANKMENT	BORROW, AS PER PLAN	EMBANKMENT, A.P.P.	SEEDING AND MULCHING, CLASS 1	SEEDING AND MULCHING, CLASS 3B	
Freeway / Ramps							
CD Road	18,464	15,147				26,313	
Ramp A	1,338	31,910				9,640	
Ramp A Acceleration Lane	1,851	3,666				5,169	
Ramp B	3,526	43,197				19,015	
Ramp D	1,732	125				1,732	
Ramp H	0	32,276			0	3,624	
I-71 Median	1	1,048				1,576	
WEIGHT STATION SITE			127,000				
RDWY. TOTALS	26,911	369	127,000	0	0	67,069	BORROW QTY IS DEDUCTED FROM EMBANKMENT QTY
City Roads / County Roads							
Sunbury Parkway	23,773	160,762		23,718	8,657	22,907	
Wilson Road	7,772	5,711			6,744	0	
STREET TOTAL	31,545	166,473		23,718	15,401	22,907	
GRAND TOTAL	58,456	166,843	127,000	23,718	15,401	89,976	

SEEDING AND MULCHING CALCULATIONS

ITEM 659 - TOPSOIL (CY)

TOPSOIL = PERMANENT SEEDED AREA (SY) x 111 CY TOPSOIL/1000 SY PERMANENT SEEDED AREA
105377 x 111 CY / 1000 SY = 11697 CY

ITEM 659 - SOIL ANALYSIS TEST (EA)

ONE TEST PER 10,000 CY OF TOPSOIL
11697 / 10000 CY = 2 EA

ITEM 659 - REPAIR SEEDING AND MULCHING (SY)

REPAIR SEEDING AND MULCHING = 5% OF PERMANENT SEEDED AREA (SY)
105377 x 0.05 = 5269 SY

ITEM 659 - INTERSEEDING (SY)

INTERSEEDING = 5% OF PERMANENT SEEDED AREA (SY)
105377 x 0.05 = 5269 SY

ITEM 659 - COMMERCIAL FERTILIZER (TON)

1 Ton per 7410 Sq. Yd of Permanent seeding area
105377 / 7410 S.Y. 15 Ton

1 Ton per 11112 Sq. Yd of INTER- SEEDED AREA
5269 / 11112 S.Y. 1 TON

TOTAL COMMERCIAL FERTILIZER = 16 TON

ITEM 659 - LIME (ACRE)

LIME = PERMANENT SEEDED AREA (SY) x 9 / (43560 S.F. per Acre)
105377 x 9 /43560 = 22 ACRE

ITEM 659 - WATER (M. GAL)

WATER = PERMANENT SEEDED AREA (SY) x 0.0027 M GAL x 2 APPLICATIONS
105377 x 0.0027 = 570 M. GAL

WATER = INTER-SEEDED AREA (SY) x 0.0027 M GAL x 2 APPLICATIONS
5269 x 0.0027 = 30 M. GAL

TOTAL WATER = 600 M. GAL

ITEM 659 - MOWING (M. SF)

MOWING = 0.25 x PERMANENT SEEDED AREA (SY) x 9/1000000 x 2 times
105377 x ((0.25 x 9)/ 1 M) x 2 0.24 M.S.F.

CD Road

STATION	SEEDING	SEEDING	CUT - END	FILL - END AREA		CUT - UNADJUSTED	FILL - UNADJUSTED	
	WIDTH	AREA	AREA	SF		VOL.	VOL.	
	FT	SY	SF			CY		
	E59 FEEDING AND MULCHING, CLASS 3B	E59 FEEDING AND MULCHING, CLASS 3B	Z03 EXCAVATION (ROADWAY)	Z03 EMBANKMENT (ROADWAY)	Z03 EMBANKMENT AS PER PLAN	Z03 EXCAVATION (ROADWAY)	Z03 EMBANKMENT (ROADWAY)	Z03 EMBANKMENT AS PER PLAN
153+59.52	19.45	0.00	24.13	19.51	-	0.00	0.00	-
154+00.	17.42	82.92	25.01	16.01	-	36.84	26.63	-
154+50.	16.13	93.19	31.87	11.66	-	52.67	25.62	-
155+00.	16.23	89.89	29.33	12.92	-	56.67	22.76	-
155+50.	14.28	84.75	28.39	10.92	-	53.44	22.07	-
156+00.	18.20	90.22	29.78	14.37	-	53.86	23.42	-
156+50.	22.19	112.19	28.54	20.05	-	54.00	31.87	-
157+00.	22.76	124.86	29.11	18.12	-	53.38	35.34	-
157+50.	23.75	129.19	29.48	13.80	-	54.25	29.56	-
158+00.	23.67	131.72	31.06	12.73	-	56.06	24.56	-
158+50.	22.78	129.03	29.70	13.53	-	56.26	24.31	-
159+00.	21.50	123.00	28.58	15.38	-	53.96	26.77	-
159+50.	22.56	122.39	35.08	9.67	-	58.94	23.19	-
160+00.	22.93	126.36	37.70	8.31	-	67.39	16.65	-
160+50.	22.70	126.75	37.42	6.99	-	69.56	14.17	-
161+00.	19.28	116.61	33.22	7.36	-	65.41	13.29	-
161+50.	20.10	109.39	31.20	9.60	-	59.65	15.70	-
162+00.	19.36	109.61	32.50	7.60	-	58.98	15.93	-
162+50.	16.89	100.69	29.69	10.34	-	57.58	16.61	-
163+00.	15.02	88.64	30.57	8.15	-	55.80	17.12	-
163+50.	18.28	92.90	29.89	12.32	-	55.98	18.95	-
164+00.	19.78	105.72	26.84	17.17	-	52.53	27.31	-
164+50.	19.93	110.31	25.81	20.28	-	48.75	34.68	-
165+00.	18.51	106.78	26.68	19.49	-	48.60	36.82	-
165+50.	20.72	108.97	27.53	18.55	-	50.19	35.22	-
166+00.	21.41	117.03	29.54	18.66	-	52.84	34.45	-
166+50.	26.53	133.17	37.22	19.72	-	61.81	35.54	-
167+00.	30.84	159.36	38.27	29.73	-	69.90	45.79	-
167+50.	32.56	176.11	37.10	49.05	-	69.79	72.94	-
168+00.	35.57	189.25	42.30	60.89	-	73.52	101.80	-
168+50.	34.37	194.28	41.16	82.32	-	77.28	132.60	-
169+00.	35.97	195.39	36.81	108.58	-	72.19	176.76	-
169+50.	37.01	202.72	34.65	135.41	-	66.17	225.92	-
170+00.	40.86	216.31	45.53	152.81	-	74.24	266.87	-
170+50.	36.95	216.14	49.17	152.33	-	87.69	282.54	-
171+00.	35.29	200.67	48.67	166.93	-	90.59	295.61	-
171+50.	31.03	184.22	30.94	198.10	-	73.71	337.99	-
172+00.	31.37	173.33	40.65	136.63	-	66.29	309.94	-
172+50.	34.62	183.31	50.95	103.47	-	84.81	222.31	-
173+00.	40.26	208.00	61.71	88.67	-	104.31	177.91	-
173+50.	41.67	227.58	61.98	92.65	-	114.53	167.89	-
174+00.	42.01	232.44	59.31	87.61	-	112.31	166.91	-
174+50.	42.27	234.11	60.77	72.40	-	111.19	148.16	-
175+00.	41.20	231.86	57.41	48.30	-	109.43	111.76	-
175+50.	37.15	217.64	55.17	31.93	-	104.24	74.29	-
176+00.	31.17	189.78	68.57	20.82	-	114.57	48.84	-
176+50.	28.99	167.11	76.26	11.82	-	134.10	30.22	-
177+00.	31.54	168.14	64.77	5.82	-	130.58	16.33	-
177+50.	11.19	118.69	60.31	5.36	-	115.81	10.35	-
178+00.	17.57	79.89	84.47	2.98	-	134.06	7.72	-
178+50.	7.84	70.58	81.17	1.54	-	153.37	4.19	-
179+00.	28.97	102.25	85.61	0.00	-	154.43	1.43	-
179+50.	36.71	182.44	80.02	0.10	-	153.36	0.09	-
180+00.	7.32	122.31	55.89	2.84	-	125.84	2.72	-
180+50.	21.50	80.06	56.02	13.15	-	103.62	14.81	-
181+00.	25.20	129.72	51.00	54.11	-	99.09	62.28	-
181+50.	29.61	152.25	55.04	69.17	-	98.19	114.15	-
182+00.	32.80	173.36	58.45	70.74	-	105.08	129.55	-
182+50.	35.41	189.47	64.26	66.20	-	113.62	126.80	-
183+00.	38.10	204.19	75.63	69.45	-	129.53	125.60	-
183+50.	39.90	216.67	82.37	72.27	-	146.30	131.22	-
184+00.	42.15	227.92	95.76	73.26	-	164.94	134.75	-
184+50.	0.00	117.08	49.44	0.01	-	134.44	67.84	-
185+00.	0.00	0.00	47.69	2.19	-	89.94	2.04	-
185+50.	0.00	0.00	46.53	8.83	-	87.24	10.20	-
186+00.	0.00	0.00	47.79	9.33	-	87.33	16.81	-
186+50.	0.00	0.00	49.13	16.51	-	89.74	23.93	-
187+00.	0.00	0.00	53.22	22.15	-	94.77	35.80	-
187+15.3	0.00	0.00	55.00	19.01	-	30.66	11.66	-
187+50.	7.64	14.73	56.78	15.86	-	71.83	22.41	-
188+00.	11.29	52.58	59.63	14.67	-	107.79	28.27	-
188+50.	14.83	72.56	79.07	9.61	-	128.43	22.48	-
189+00.	20.26	97.47	86.43	3.66	-	153.24	12.29	-

(A4)

189+50.	25.05	125.86	129.72	0.02	-	200.14	3.41	-
190+00.	29.74	152.19	152.18	0.45	-	261.02	0.44	-
190+50.	34.33	177.97	206.76	0.00	-	332.35	0.42	-
191+00.	38.46	202.19	190.05	1.27	-	367.42	1.18	-
191+50.	42.46	224.78	164.10	2.23	-	327.92	3.24	-
192+00.	43.90	239.89	130.39	4.94	-	272.68	6.64	-
192+50.	47.78	254.67	115.56	7.82	-	227.73	11.81	-
193+00.	45.96	260.39	94.18	16.09	-	194.20	22.14	-
193+50.	46.99	258.19	78.90	30.48	-	160.26	43.12	-
194+00.	48.02	263.92	82.63	29.44	-	149.56	55.48	-
194+50.	49.05	269.64	88.90	32.75	-	158.82	57.58	-
195+00.	49.71	274.33	73.11	65.87	-	150.01	91.31	-
195+50.	50.07	277.17	74.65	47.41	-	136.81	104.89	-
196+00.	50.44	279.19	79.91	52.47	-	143.11	92.48	-
196+50.	50.82	281.28	73.02	64.24	-	141.60	108.06	-
197+00.	50.68	281.94	78.50	66.49	-	140.30	121.05	-
197+50.	45.25	266.47	74.16	63.70	-	141.35	120.55	-
198+00.	39.84	236.36	78.43	42.00	-	141.29	97.87	-
198+50.	34.45	206.36	69.90	58.93	-	137.34	93.45	-
199+00.	30.84	181.36	50.83	73.66	-	111.79	122.77	-
199+50.	29.41	167.36	46.25	103.77	-	89.89	164.29	-
199+55.55	7.29	11.32	43.18	49.08	-	9.19	15.71	-
200+00.	0.00	18.00	43.97	24.20	-	71.74	60.32	-
200+50.	0.00	0.00	45.21	28.41	-	82.57	48.71	-
201+00.	0.00	0.00	51.98	17.57	-	89.99	42.57	-
201+50.	40.45	112.36	54.44	273.24	-	98.54	269.27	-
202+00.	39.31	221.56	56.80	167.66	-	103.00	408.24	-
202+50.	41.78	225.25	73.04	95.93	-	120.22	244.07	-
203+00.	43.78	237.67	77.17	92.42	-	139.08	174.40	-
203+50.	46.68	251.28	88.55	92.71	-	153.44	171.42	-
204+00.	45.46	255.94	85.71	141.99	-	161.35	217.31	-
204+50.	41.03	240.25	84.53	99.69	-	157.63	223.78	-
205+00.	38.40	220.64	81.31	108.17	-	153.56	192.46	-
205+50.	39.27	215.75	85.53	98.37	-	154.48	191.24	-
206+00.	39.28	218.19	83.58	93.56	-	156.58	177.71	-
206+50.	38.02	214.72	81.86	74.88	-	153.19	155.96	-
207+00.	38.82	213.44	84.33	80.35	-	153.88	143.73	-
207+50.	40.22	219.56	67.60	83.21	-	140.68	151.44	-
208+00.	40.41	223.97	66.93	81.41	-	124.56	152.43	-
208+50.	37.66	216.86	61.28	81.77	-	118.71	151.09	-
209+00.	34.12	199.39	56.52	84.77	-	109.07	154.20	-
209+50.	33.35	187.42	56.97	81.56	-	105.08	154.01	-
210+00.	33.90	186.81	59.16	71.73	-	107.53	141.94	-
210+50.	34.28	189.39	79.69	62.48	-	128.56	124.27	-
211+00.	34.12	190.00	82.30	56.38	-	149.99	110.06	-
211+50.	33.27	187.19	84.11	53.86	-	154.08	102.07	-
212+00.	32.48	182.64	88.30	48.42	-	159.64	94.70	-
212+50.	33.67	183.75	96.17	44.03	-	170.81	85.60	-
213+00.	32.74	184.47	95.63	44.96	-	177.59	82.40	-
213+50.	32.43	181.03	94.12	45.08	-	175.69	83.37	-
214+00.	33.62	183.47	75.57	47.51	-	157.12	85.73	-
214+50.	34.69	189.75	74.99	49.25	-	139.41	89.59	-
215+00.	34.22	191.42	69.14	53.14	-	133.45	94.81	-
215+50.	37.03	197.92	73.92	56.44	-	132.46	101.46	-
216+00.	38.84	210.75	75.82	64.35	-	138.65	111.84	-
216+50.	36.51	209.31	63.72	70.86	-	129.20	125.19	-
217+00.	34.79	198.06	59.10	80.79	-	113.72	140.42	-
217+50.	36.03	196.72	59.70	83.10	-	110.00	151.75	-
218+00.	40.13	211.56	81.31	82.55	-	130.56	153.38	-
218+50.	42.24	228.81	68.57	83.23	-	138.78	153.50	-
219+00.	43.13	237.14	69.15	78.04	-	127.52	149.32	-
219+50.	42.14	236.86	65.98	83.47	-	125.12	149.55	-
220+00.	40.11	228.47	62.97	68.91	-	119.40	141.09	-
220+50.	35.66	210.47	60.29	57.09	-	114.13	116.67	-
221+00.	35.40	197.39	63.01	71.65	-	114.17	119.20	-
221+50.	34.41	193.92	64.65	75.10	-	118.20	135.88	-
222+00.	32.29	185.28	66.40	62.25	-	121.34	127.18	-
222+50.	30.46	174.31	64.49	68.34	-	121.19	120.92	-
223+00.	34.49	180.42	88.62	67.24	-	141.77	125.54	-
223+50.	37.59	200.22	91.97	68.97	-	167.21	126.12	-
224+00.	39.26	213.47	88.42	81.17	-	167.03	139.02	-
224+50.	38.88	217.06	82.02	92.09	-	157.81	160.43	-
225+00.	38.99	216.31	78.11	111.09	-	148.27	188.13	-
225+50.	38.71	215.83	81.04	90.71	-	147.36	186.85	-
226+00.	39.33	216.78	84.06	79.64	-	152.87	157.73	-
226+50.	38.72	216.81	81.25	78.28	-	153.06	146.22	-
227+00.	40.19	219.19	62.56	88.01	-	133.16	153.97	-
227+50.	37.88	216.86	58.44	89.65	-	112.04	164.50	-
228+00.	36.49	206.58	74.31	83.39	-	122.92	160.22	-
228+50.	37.29	204.94	82.14	58.93	-	144.86	131.78	-
229+00.	36.08	203.81	67.30	42.59	-	138.37	94.00	-
229+50.	35.55	198.97	74.58	29.81	-	131.37	67.04	-
230+00.	34.92	195.75	72.05	24.72	-	135.77	50.49	-
230+30.86	34.71	119.38	72.63	8.65	-	82.68	19.07	-
26312.82						18463.83	15147.48	0.00

(BK)

Ramp A

STATION	SEEDING WIDTH	SEEDING AREA	CUT - END AREA	FILL - END AREA		CUT - UNADJUSTED VOL.	FILL - UNADJUSTED VOL.	
	FT	SY	SF	SF		CY	CY	
	659 SEEDING AND MULCHING, CLASS 3B	659 SEEDING AND MULCHING, CLASS 3B	203 EXCAVATION (ROADWAY)	203 EMBANKMENT (ROADWAY)	203 EMBANKMENT AS PER PLAN	203 EXCAVATION (ROADWAY)	203 EMBANKMENT (ROADWAY)	203 EMBANKMENT AS PER PLAN
891+95.04	40.86	0.00	48.35	131.68	0.00	0.00	0.00	0.00
892+00.	41.01	22.56	47.95	130.85	0.00	8.85	24.11	0.00
892+09.18	40.39	41.52	46.03	126.94	0.00	15.98	43.82	0.00
892+50.	41.03	184.64	49.28	114.83	0.00	72.05	182.76	0.00
893+00.	40.88	227.53	47.91	111.30	0.00	89.99	209.38	0.00
893+50.	47.70	246.05	94.42	114.86	0.00	131.79	209.41	0.00
894+00.	48.27	266.59	116.94	117.75	0.00	195.70	215.38	0.00
894+50.	46.58	263.48	95.91	136.44	0.00	197.08	235.36	0.00
895+00.	44.74	253.67	75.56	190.22	0.00	158.77	302.46	0.00
895+50.	98.10	396.77	62.04	305.97	0.00	127.41	459.44	0.00
896+00.	101.26	553.76	27.50	401.70	0.00	82.91	655.25	0.00
896+50.	87.33	523.86	37.10	533.40	0.00	59.81	865.83	0.00
897+00.	104.54	532.97	9.73	955.72	0.00	43.36	1378.81	0.00
897+50.	150.18	707.53	15.12	1592.39	0.00	23.01	2359.36	0.00
898+00.	128.13	773.07	11.84	1529.76	0.00	24.96	2890.88	0.00
898+50.	135.24	731.58	19.99	1501.92	0.00	29.47	2807.11	0.00
899+00.	135.75	752.74	15.14	1588.13	0.00	32.53	2861.16	0.00
899+50.	188.13	899.65	16.53	2098.11	0.00	29.32	3413.19	0.00
900+00.	190.34	1051.32	0.00	3273.64	0.00	15.31	4973.84	0.00
900+50.	100.78	808.68	0.00	1971.10	0.00	0.00	4856.24	0.00
900+90.84	76.54	402.32	0.00	1950.32	0.00	0.00	2965.76	0.00
		9640.29				1338.30	31909.56	0.00

(AH)

(BK)

Ramp A Acceleration Lane

STATION	SEEDING WIDTH	(W)	CUT - END AREA	FILL - END AREA		CUT - UNADJUSTED VOLUME	FILL - UNADJUSTED VOL.	
	FT	SY	SF	SF		CY	CY	
	659 SEEDING AND MULCHING, CLASS 3B	659 SEEDING AND MULCHING, CLASS 3B	203 EXCAVATION (ROADWAY)	203 EMBANKMENT (ROADWAY)	203 EMBANKMENT AS PER PLAN	203 EXCAVATION (ROADWAY)	203 EMBANKMENT (ROADWAY)	203 EMBANKMENT AS PER PLAN
674+60.38	0.00	0.00	17.43	0.00	0.00	0.00	0.00	0.00
675+00.	5.89	12.97	17.32	0.04	0.00	25.50	0.03	0.00
675+50.	6.43	34.24	17.87	0.08	0.00	32.58	0.11	0.00
676+00.	5.68	33.64	18.81	0.02	0.00	33.96	0.09	0.00
676+50.	9.29	41.58	21.36	0.64	0.00	37.19	0.61	0.00
677+00.	9.39	51.89	22.61	1.54	0.00	40.71	2.02	0.00
677+50.	11.57	58.22	23.04	3.96	0.00	42.27	5.09	0.00
678+00.	10.73	61.94	22.19	4.55	0.00	41.88	7.88	0.00
678+50.	13.18	66.41	24.14	6.46	0.00	42.90	10.19	0.00
679+00.	13.07	72.92	24.23	6.62	0.00	44.79	12.11	0.00
679+50.	13.11	72.73	25.32	6.98	0.00	45.88	12.59	0.00
680+00.	16.51	82.27	25.58	11.02	0.00	47.13	16.67	0.00
680+50.	22.65	108.78	25.53	18.63	0.00	47.32	27.45	0.00
681+00.	24.85	131.95	26.04	25.65	0.00	47.75	41.00	0.00
681+50.	26.10	141.53	24.40	36.53	0.00	46.70	57.57	0.00
682+00.	27.12	147.85	23.45	45.42	0.00	44.31	75.88	0.00
682+50.	31.18	161.96	22.64	58.37	0.00	42.68	96.10	0.00
683+00.	31.24	173.39	22.96	61.92	0.00	42.22	111.38	0.00
683+50.	31.76	175.01	23.55	69.73	0.00	43.06	121.90	0.00
684+00.	31.98	177.06	24.02	75.43	0.00	44.05	134.41	0.00
684+50.	32.43	178.91	23.81	78.54	0.00	44.29	142.56	0.00
685+00.	33.80	183.98	25.75	78.16	0.00	45.89	145.09	0.00
685+50.	36.21	194.49	27.24	81.22	0.00	49.06	147.57	0.00
686+00.	36.65	202.40	31.96	76.99	0.00	54.81	146.49	0.00
686+50.	35.94	201.63	30.78	82.83	0.00	58.09	147.98	0.00
687+00.	35.21	197.64	29.03	86.00	0.00	55.38	156.32	0.00
687+50.	36.85	200.18	30.73	90.84	0.00	55.33	163.74	0.00
688+00.	37.87	207.54	33.37	98.99	0.00	59.35	175.77	0.00
688+50.	38.79	212.93	36.19	104.03	0.00	64.41	187.98	0.00
689+00.	39.55	217.59	38.07	109.55	0.00	68.76	197.76	0.00
689+50.	40.30	221.80	41.22	111.20	0.00	73.42	204.40	0.00
690+00.	41.89	228.32	45.15	126.68	0.00	79.97	220.26	0.00
690+50.	42.57	234.63	51.31	122.07	0.00	89.31	230.32	0.00
691+00.	43.16	238.15	46.23	124.55	0.00	90.31	228.35	0.00
691+50.	42.68	238.44	50.18	123.90	0.00	89.27	230.05	0.00
691+93.9	40.86	203.75	48.34	131.92	0.00	80.09	207.97	0.00
		5168.73				1850.64	3665.72	0.00

(AH)

(BK)

Ramp B

STATION	SEEDING WIDTH	SEEDING AREA	CUT - END AREA	FILL - END AREA		CUT - UNADJUSTED VOLUME	FILL - UNADJUSTED VOL.	
	FT	SY	SF	SF		CY	CY	
	659 SEEDING AND MULCHING; CLASS 3B	659 SEEDING AND MULCHING; CLASS 3B	203 EXCAVATION (ROADWAY)	203 EMBANKMENT (ROADWAY)	203 EMBANKMENT AS PER PLAN	203 EXCAVATION (ROADWAY)	203 EMBANKMENT (ROADWAY)	203 EMBANKMENT AS PER PLAN
484+21.08	42.89	0.00	53.14	74.84	0.00	0.00	0.00	0.00
484+50.	44.09	139.74	60.05	53.39	0.00	60.62	68.67	0.00
484+62.07	44.76	59.57	63.05	87.98	0.00	27.52	31.60	0.00
485+00.	47.29	193.95	77.53	92.36	0.00	98.75	126.67	0.00
485+50.	48.49	266.05	91.89	94.67	0.00	156.88	173.18	0.00
485+97.04	45.46	245.53	91.96	76.02	0.00	160.15	148.69	0.00
486+00.	45.70	14.99	90.06	75.51	0.00	9.98	8.31	0.00
486+50.	42.89	246.10	33.04	80.25	0.00	113.98	144.22	0.00
487+00.	7.57	140.16	0.34	33.13	0.00	30.91	104.98	0.00
487+13.94	6.92	11.22	0.67	29.97	0.00	0.26	16.29	0.00
487+50.	12.65	39.20	3.14	35.03	0.00	2.54	43.41	0.00
488+00.	16.51	81.01	13.70	17.21	0.00	15.59	48.37	0.00
488+50.	60.74	214.59	24.67	23.01	0.00	35.53	37.24	0.00
489+00.	59.73	334.63	22.54	71.93	0.00	43.71	87.91	0.00
489+50.	65.92	349.02	58.12	149.93	0.00	74.69	205.43	0.00
490+00.	73.71	387.87	87.60	207.52	0.00	134.93	330.97	0.00
490+50.	82.16	432.97	100.17	255.97	0.00	173.86	429.16	0.00
491+00.	88.36	473.64	96.97	248.01	0.00	182.54	466.65	0.00
491+50.	81.14	470.81	43.33	325.02	0.00	129.91	530.58	0.00
492+00.	92.98	483.66	38.31	352.64	0.00	75.59	627.46	0.00
492+50.	104.30	548.02	49.03	397.25	0.00	80.87	694.34	0.00
493+00.	116.99	614.71	58.49	571.80	0.00	99.56	897.27	0.00
493+50.	131.38	689.92	36.90	800.32	0.00	88.32	1270.48	0.00
494+00.	149.14	779.22	48.83	786.95	0.00	79.38	1469.69	0.00
494+50.	166.33	876.28	80.81	728.62	0.00	120.04	1403.31	0.00
495+00.	175.96	950.80	113.29	456.33	0.00	179.72	1097.18	0.00
495+50.	185.12	1003.02	117.83	881.11	0.00	214.00	1238.37	0.00
496+00.	192.63	1049.32	141.16	1084.80	0.00	239.81	1820.29	0.00
496+50.	191.05	1065.78	102.22	1223.20	0.00	225.35	2137.04	0.00
497+00.	188.77	1055.05	86.29	1374.70	0.00	174.55	2405.46	0.00
497+50.	195.03	1066.09	72.28	1562.80	0.00	146.82	2719.91	0.00
498+00.	201.27	1100.82	63.00	1748.20	0.00	125.26	3065.74	0.00
498+50.	207.35	1135.05	42.51	2013.20	0.00	97.69	3482.78	0.00
499+00.	214.80	1172.64	46.92	2316.90	0.00	82.81	4009.35	0.00
499+50.	108.73	898.69	0.00	2796.60	0.00	43.44	4734.72	0.00
500+10.13	18.45	424.83	0.00	3599.00	0.00	0.00	7121.62	0.00
		19014.96				3525.54	43197.32	0.00

(AH)

(BK)

Ramp D

STATION	SEEDING WIDTH	SEEDING AREA	CUT - END AREA	FILL - END AREA		CUT - UNADJUSTED VOLUME	FILL - UNADJUSTED VOL.	
	FT	SY	SF	SF		CY	CY	
	659 SEEDING AND MULCHING, CLASS 3B	659 SEEDING AND MULCHING, CLASS 3B	203 EXCAVATION (ROADWAY)	203 EMBANKMENT (ROADWAY)	203 EMBANKMENT AS PER PLAN	203 EXCAVATION (ROADWAY)	203 EMBANKMENT (ROADWAY)	203 EMBANKMENT AS PER PLAN
230+30.86	34.71	0.00	72.63	8.65	0.00	0.00	0.00	0.00
230+50.	32.70	71.68	79.29	6.02	0.00	53.85	5.20	0.00
231+00.	29.03	171.47	84.85	2.42	0.00	151.98	7.81	0.00
231+50.	26.25	153.56	86.01	1.22	0.00	158.20	3.37	0.00
232+00.	33.92	167.14	90.79	1.29	0.00	163.70	2.32	0.00
232+50.	13.57	131.91	33.90	4.58	0.00	115.45	5.44	0.00
233+00.	19.61	92.16	33.92	8.05	0.00	62.80	11.69	0.00
233+50.	20.67	111.89	24.89	11.32	0.00	54.45	17.94	0.00
234+00.	18.11	107.72	25.51	7.57	0.00	46.67	17.49	0.00
234+50.	18.70	102.25	30.24	4.99	0.00	51.62	11.63	0.00
235+00.	27.49	128.29	47.84	1.95	0.00	72.30	6.43	0.00
235+50.	16.87	123.21	86.25	4.39	0.00	124.16	5.87	0.00
236+00.	19.51	101.04	100.13	3.60	0.00	172.57	7.40	0.00
236+50.	12.92	90.06	99.52	1.65	0.00	184.86	4.86	0.00
237+00.	19.93	91.23	98.87	5.83	0.00	183.69	6.93	0.00
237+44.48	15.93	88.61	65.56	7.08	0.00	135.44	10.63	0.00
		1732.22				1731.75	125.01	0.00

(AH)

(BK)

Ramp H

STATION	SEEDING WIDTH	SEEDING WIDTH	SEEDING AREA	SEEDING AREA	CUT - END AREA	FILL - END AREA		CUT - UNADJUSTED VOLUME	FILL - UNADJUSTED VOL.		
	FT	FT	SY	SY	SF	SF		CY	CY		
	659 SEEDING AND MULCHING, CLASS 3B	659 SEEDING AND MULCHING, CLASS 1	659 SEEDING AND MULCHING, CLASS 3B	659 SEEDING AND MULCHING, CLASS 1	203 EXCAVATION (ROADWAY)	203 EMBANKMENT (ROADWAY)	203 EMBANKMENT AS PER PLAN	203 EXCAVATION (ROADWAY)	203 EMBANKMENT (ROADWAY)	203 EMBANKMENT AS PER PLAN	
523+38.13	69.47		0.00	0.00	0.00	1551.70	0.00	0.00	0.00	0.00	(AH)
523+50.	70.10		92.04	0.00	0.00	1574.00	0.00	0.00	687.08	0.00	
524+00.	71.78		394.10	0.00	0.00	1704.70	0.00	0.00	3035.83	0.00	
524+50.	74.17		405.42	0.00	0.00	1894.50	0.00	0.00	3332.59	0.00	
525+00.	78.53		424.16	0.00	0.00	2102.60	0.00	0.00	3701.02	0.00	
525+50.	82.74		447.97	0.00	0.00	2253.10	0.00	0.00	4033.06	0.00	
526+00.	87.86		473.89	0.00	0.00	2408.70	0.00	0.00	4316.48	0.00	
526+50.	92.21		500.19	0.00	0.01	2552.50	0.00	0.01	4593.70	0.00	
527+00.	98.03		528.47	0.00	0.00	2849.00	0.00	0.01	5001.39	0.00	
527+32.52	100.18		358.10	0.00	0.00	3087.10	0.00	0.00	3574.85	0.00	(BK)

I-71 Median Grading

STATION	SEEDING WIDTH	SEEDING AREA	CUT - END AREA	FILL - END AREA		CUT - UNADJUSTED VOLUME	FILL - UNADJUSTED VOL.	
	FT	SY	SF	SF		CY	CY	
	659 SEEDING AND MULCHING, CLASS 3B	659 SEEDING AND MULCHING, CLASS 3B	203 EXCAVATION (ROADWAY)	203 EMBANKMENT (ROADWAY)	203 EMBANKMENT AS PER PLAN	203 EXCAVATION (ROADWAY)	203 EMBANKMENT (ROADWAY)	203 EMBANKMENT AS PER PLAN
698+94.61	0.00	0.00	0.00	0.00	-	0.00	0.00	-
699+00.	31.74	9.50	0.57	2.41	-	0.06	0.24	-
699+17.71	27.57	58.36	0.01	17.61	-	0.19	6.57	-
699+38.71	28.04	64.88	0.00	23.14	-	0.00	15.85	-
699+50.	28.14	35.24	0.00	26.93	-	0.00	10.47	-
699+68.7	28.32	58.66	0.00	33.63	-	0.00	20.97	-
700+00.	49.34	135.04	0.00	146.61	-	0.00	104.47	-
700+08.68	47.39	46.65	0.00	157.68	-	0.00	48.91	-
700+37.88	47.50	153.95	0.00	134.80	-	0.00	158.16	-
700+50.	47.51	63.98	0.00	131.28	-	0.00	59.72	-
701+00.	47.43	263.74	0.00	122.26	-	0.00	234.76	-
701+50.	47.78	264.50	0.00	113.98	-	0.00	218.74	-
701+53.69	47.76	19.59	0.00	113.06	-	0.00	15.51	-
701+93.7	28.71	169.98	0.00	27.13	-	0.00	103.87	-
702+00.	28.67	20.08	0.00	28.15	-	0.00	6.45	-
702+23.7	28.79	75.65	0.00	23.35	-	0.00	22.60	-
702+44.7	32.28	71.24	0.37	17.43	-	0.14	15.86	-
702+50.	32.29	19.01	0.33	10.44	-	0.07	2.74	-
702+62.8	32.31	45.94	0.00	0.00	-	0.08	2.47	-
		1575.98				0.54	1048.36	

(AH)

(BK)

Sunbury Parkway EB

STATION	SEEDING WIDTH	SEEDING WIDTH	SEEDING AREA	SEEDING AREA	CUT - END AREA	FILL - END AREA		CUT - UNADJUSTED VOLUME	FILL - UNADJUSTED VOL.		
	FT	FT	SY	SY	SF	SF		CY	CY		
	659 SEEDING AND MULCHING, CLASS 1	659 SEEDING AND MULCHING, CLASS 3B	659 SEEDING AND MULCHING, CLASS 1	659 SEEDING AND MULCHING, CLASS 3B	203 EXCAVATION (ROADWAY)	203 EMBANKMENT (ROADWAY)	203 EMBANKMENT AS PER PLAN	203 EXCAVATION (ROADWAY)	203 EMBANKMENT (ROADWAY)	203 EMBANKMENT AS PER PLAN	
80+32.2		70.55	0.00	0.00	0.00	0.00		0.00	0.00	0.00	(AH)
81+48.58		132.88	0.00	1315.29	0.00	1928.46		0.00	4156.19	0.00	
81+56.58		134.66	0.00	118.91	0.00	1905.52		0.00	568.00	0.00	(BH)
81+56.58	4.02	66.63	0.00	0.00	0.00	1910.94		0.00	0.00	0.00	(AH)
82+00.	4.02	71.47	19.39	333.13	0.00	2137.60		0.00	3255.33	0.00	
82+50.	4.24	87.31	22.94	441.06	0.00	2616.86		0.00	4402.28	0.00	
83+00.	5.23	28.29	26.31	321.11	0.00	3092.90		0.00	5286.81	0.00	
83+50.	0.00	0.00	14.53	78.58	0.00	2153.86		0.00	4858.11	0.00	
84+00.	14.50	25.35	40.28	70.42	0.00	2462.31		0.00	4274.23	0.00	
84+50.	17.51	62.58	88.92	244.25	0.04	3662.65		0.04	5671.26	0.00	
85+00.	17.51	64.93	97.28	354.19	0.00	3319.42		0.04	6464.88	0.00	
85+50.	17.51	67.14	97.28	366.86	0.00	3579.23		0.00	6387.64	0.00	
86+00.	17.51	70.41	97.28	382.08	0.00	3755.92		0.00	6791.81	0.00	
86+50.	10.22	63.55	77.03	372.11	0.00	792.50	2667.30	0.00	4211.50	2469.72	
86+76.8	6.23	35.86	24.49	148.01	0.00	238.18	2667.30	0.00	511.52	2647.54	
87+00.	7.34	19.16	17.49	70.91	0.00	79.20		0.00	136.36	1145.95	
87+06.8	7.34	16.55	5.55	13.49	0.00	78.99		0.00	19.92	0.00	(BK)
89+41.09	7.34	45.61	0.00	0.00	0.00	192.80		0.00	0.00	0.00	(AH)
89+50.	7.34	70.70	7.27	57.57	0.00	278.86		0.00	77.82	0.00	
89+71.09	6.39	112.41	16.09	214.54	0.00	417.17	2344.11	0.00	271.84	915.51	
90+00.	10.38	111.89	26.93	360.25	0.00	918.69	2344.11	0.00	715.18	2509.93	
90+50.	14.52	105.96	69.17	605.14	0.00	2324.30		0.00	3002.77	2170.47	
91+00.	0.00	0.00	40.33	294.33	0.00	1836.07		0.00	3852.19	0.00	
91+18.34	0.00	0.00	0.00	0.00	0.00	1758.39		0.00	1220.79	0.00	
91+50.	13.50	0.00	23.75	0.00	0.00	1645.23		0.00	1995.53	0.00	
92+00.	28.08	104.49	115.50	290.24	0.00	1402.63		0.00	2822.09	0.00	
92+50.	28.08	88.10	156.00	534.94	122.31	1668.74		113.25	2843.86	0.00	
93+00.	28.01	76.45	155.82	457.07	121.75	1488.39		225.98	2923.27	0.00	
93+50.	28.01	63.74	155.62	389.42	79.10	1365.15		185.97	2642.17	0.00	
94+00.	28.01	57.59	155.62	337.03	66.44	1167.76		134.76	2345.29	0.00	
94+50.	28.01	53.04	155.62	307.30	69.64	915.60		126.00	1929.04	0.00	
95+00.	28.01	45.40	155.62	273.42	58.11	653.49		118.29	1452.86	0.00	
95+50.	28.01	41.72	155.62	241.98	67.75	379.89		116.54	956.83	0.00	
96+00.	28.01	38.57	155.62	223.03	85.48	178.23		141.88	516.78	0.00	
96+50.	28.01	36.49	155.62	208.51	131.86	48.36		201.24	209.81	0.00	
97+00.	28.01	36.74	155.62	203.41	196.67	17.61		304.19	61.08	0.00	
97+50.	28.01	40.05	155.62	213.29	262.85	11.13		425.48	26.61	0.00	
98+00.	28.01	37.01	155.62	214.05	282.47	4.53		504.93	14.50	0.00	
98+50.	28.01	32.74	155.62	193.76	279.69	0.00		520.52	4.19	0.00	
99+00.	28.01	29.55	155.62	173.03	297.32	0.00		534.27	0.00	0.00	
99+50.	28.01	27.94	155.62	159.68	306.56	0.00		559.15	0.00	0.00	

100+00.	28.50	26.60	156.96	151.49	302.34	0.00		563.80	0.00	0.00
100+50.	28.01	26.38	156.96	147.17	375.62	0.00		627.74	0.00	0.00
101+00.	28.01	26.66	155.62	147.34	358.49	0.01		679.73	0.01	0.00
101+50.	28.01	24.81	155.62	142.97	307.67	0.01		616.81	0.02	0.00
102+00.	28.01	22.09	155.62	130.26	253.49	0.00		519.59	0.01	0.00
102+50.	28.01	20.44	155.62	118.13	211.48	1.18		430.53	1.09	0.00
103+00.	28.01	18.53	155.62	108.24	180.92	3.92		363.33	4.72	0.00
103+50.	27.89	16.80	155.27	98.12	162.31	7.17		317.81	10.27	0.00
104+00.	16.01	15.30	121.94	89.14	191.44	0.50		327.55	7.10	0.00
104+50.	14.51	8.59	84.79	66.34	178.12	0.01		342.19	0.47	0.00
105+00.	14.51	8.57	80.62	47.66	182.94	0.00		334.31	0.01	0.00
105+50.	14.51	10.61	80.62	53.29	213.94	0.00		367.48	0.00	0.00
106+00.	14.51	16.67	80.62	75.78	245.50	0.00		425.41	0.00	0.00
106+50.	14.51	24.42	80.62	114.15	307.13	0.00		511.69	0.00	0.00
107+00.	14.51	28.98	80.62	148.34	367.41	0.00		624.57	0.00	0.00
107+50.	14.51	27.72	80.62	157.50	387.05	0.00		698.57	0.00	0.00
107+66.86	14.51	27.38	27.19	51.61	374.88	0.00		237.89	0.00	0.00
108+00.	0.00	31.38	26.72	108.18	385.38	0.00		466.57	0.00	0.00
108+50.	0.00	34.20	0.00	182.17	432.35	0.00		757.16	0.00	0.00
109+00.	0.00	37.68	0.00	199.67	178.88	0.00		565.95	0.00	0.00
109+44.85	0.00	17.35	0.00	137.12	66.87	5.71		204.11	4.74	0.00
			5254.37	13057.06				14195.32	86908.77	11859.13

(BK)

Sunbury Parkway WB

STATION	SEEDING WIDTH	SEEDING WIDTH	SEEDING AREA	SEEDING AREA	CUT - END AREA	FILL - END AREA		CUT - UNADJUSTED VOLUME	FILL - UNADJUSTED VOL.		
	FT	FT	SY	SY	SF	SF		CY	CY		
	659 SEEDING AND MULCHING, CLASS 1	659 SEEDING AND MULCHING, CLASS 3B	659 SEEDING AND MULCHING, CLASS 1	659 SEEDING AND MULCHING, CLASS 3B	203 EXCAVATION (ROADWAY)	203 EMBANKMENT (ROADWAY)	203 EMBANKMENT AS PER PLAN	203 EXCAVATION (ROADWAY)	203 EMBANKMENT (ROADWAY)	203 EMBANKMENT AS PER PLAN	
80+32.2		144.20	0.00	0.00	0.00	0.00		0.00	0.00	0.00	(AH)
81+48.58		167.90	0.00	2017.90	0.00	2690.16		0.00	5797.79	0.00	
81+56.58		169.51	0.00	149.96	0.00	2722.96		0.00	801.94	0.00	(BH)
81+56.58	0.00	0.00	0.00	0.00	0.00	1168.99		0.00	0.00	0.00	(AH)
82+00.	0.00	0.00	0.00	0.00	0.00	1146.29		0.00	1861.66	0.00	
82+50.	0.00	0.00	0.00	0.00	0.00	1143.39		0.00	2120.07	0.00	
83+00.	0.00	0.00	0.00	0.00	0.00	1093.79		0.00	2071.46	0.00	
83+50.	0.00	0.00	0.00	0.00	0.00	1095.30		0.00	2026.94	0.00	
84+00.	0.00	0.00	0.00	0.00	0.00	1151.79		0.00	2080.64	0.00	
84+50.	0.00	0.00	0.00	0.00	0.00	1196.65		0.00	2174.48	0.00	
85+00.	0.00	0.00	0.00	0.00	0.00	1281.84		0.00	2294.90	0.00	
85+50.	0.00	0.00	0.00	0.00	0.00	1387.35		0.00	2471.47	0.00	
86+00.	14.15	84.87	39.31	235.76	0.00	4594.81		0.00	5539.04	0.00	
86+50.	10.27	73.32	67.83	439.43	0.00	1079.91	2667.30	0.00	5254.37	2469.72	
86+76.8	7.34	42.50	26.21	172.44	0.00	335.71	2667.30	0.00	702.57	2647.54	
87+00.	7.34	22.62	18.91	83.93	0.00	85.93		0.00	181.15	1145.95	
87+06.8	7.39	18.36	5.56	15.48	0.00	54.66		0.00	17.70	0.00	(BK)
89+41.09	7.34	1.68	0.00	0.00	0.00	0.00		0.00	0.00	0.00	(AH)
89+50.	7.34	1.60	7.26	1.62	0.00	0.00		0.00	0.00	0.00	
89+71.09	7.34	102.74	17.19	122.25	37.30	442.31	2344.11	14.57	172.75	915.51	
90+00.	10.28	95.16	28.30	317.85	29.54	90.67	2344.11	35.78	285.34	2509.93	
90+50.	14.51	91.84	68.88	519.43	20.06	2025.49		45.93	1959.41	2170.47	
91+00.	14.52	89.58	80.63	503.92	28.82	3227.72		45.26	4864.08	0.00	
91+18.34	14.52	88.78	29.58	181.72	31.97	3108.54		20.65	2151.98	0.00	
91+50.	16.02	86.74	53.70	308.72	40.33	2892.01		42.39	3518.10	0.00	
92+00.	16.01	80.82	88.96	465.45	32.02	2491.75		66.99	4984.96	0.00	
92+50.	16.01	74.14	88.96	430.46	22.15	2084.51		50.16	4237.28	0.00	
93+00.	16.01	69.10	88.96	397.90	21.90	1833.59		40.79	3627.87	0.00	
93+50.	16.01	65.15	88.96	372.91	24.40	1588.78		42.87	3168.86	0.00	
94+00.	16.01	49.49	88.96	318.45	23.15	1335.69		44.03	2707.84	0.00	
94+50.	16.01	44.59	88.96	261.34	22.75	1054.44		42.50	2213.08	0.00	
95+00.	16.01	38.87	88.96	231.82	20.97	765.73		40.48	1685.34	0.00	
95+50.	16.01	34.60	88.96	204.07	24.34	490.53		41.95	1163.20	0.00	
96+00.	16.01	30.59	88.96	181.08	24.26	322.00		45.00	752.34	0.00	
96+50.	16.01	27.01	88.96	160.00	21.72	185.51		42.57	469.92	0.00	
97+00.	16.01	23.95	88.96	141.56	26.47	78.69		44.62	244.63	0.00	
97+50.	16.01	21.28	88.96	125.65	77.13	45.20		95.93	114.71	0.00	
98+00.	16.01	19.44	88.96	113.12	124.13	20.66		186.35	60.98	0.00	
98+50.	16.01	17.85	88.96	103.59	178.56	1.91		280.27	20.90	0.00	
99+00.	16.49	18.42	90.29	100.77	218.77	0.00		367.90	1.77	0.00	
99+50.	16.01	19.01	90.29	103.99	269.10	0.00		451.73	0.00	0.00	

100+00.	16.01	19.19	88.96	106.11	275.57	0.00		504.32	0.00	0.00
100+50.	16.02	18.43	88.96	104.49	264.26	0.00		499.84	0.00	0.00
101+00.	17.01	17.47	91.75	99.73	228.33	0.00		456.10	0.00	0.00
101+50.	18.01	16.36	97.30	93.99	206.69	0.00		402.80	0.00	0.00
102+00.	19.01	15.19	102.86	87.64	148.70	1.27		329.06	1.18	0.00
102+50.	20.01	14.61	108.41	82.76	137.99	2.36		265.45	3.36	0.00
103+00.	21.01	14.09	113.97	79.72	107.43	7.87		227.24	9.47	0.00
103+50.	22.01	13.34	119.51	76.18	110.76	9.96		202.03	16.51	0.00
104+00.	22.01	12.54	122.29	71.89	124.74	4.76		218.06	13.63	0.00
104+50.	14.51	6.63	101.46	53.25	159.49	0.00		263.18	4.41	0.00
105+00.	14.51	10.68	80.62	48.07	174.14	1.12		308.92	1.04	0.00
105+50.	14.51	7.09	80.62	49.35	200.23	0.00		346.64	1.04	0.00
106+00.	14.51	0.00	80.62	19.68	178.66	0.00		350.82	0.00	0.00
106+50.	14.51	0.00	80.62	0.00	183.55	0.00		335.38	0.00	0.00
107+00.	14.51	3.93	80.62	10.93	221.63	0.00		375.17	0.00	0.00
107+50.	14.51	6.79	80.62	29.80	252.34	0.00		438.86	0.00	0.00
107+66.86	0.00	12.43	13.59	18.01	294.16	0.00		170.63	0.00	0.00
108+00.	0.00	0.00	0.00	22.89	341.95	0.00		390.38	0.00	0.00
108+50.	0.00	0.00	0.00	0.00	322.25	0.00		615.00	0.00	0.00
109+00.	0.00	0.00	0.00	0.00	234.35	0.00		515.37	0.00	0.00
109+44.85	0.00	4.99	0.00	12.43	95.20	1.73		273.71	1.44	0.00
			3402.13	9849.50				9577.67	73853.60	11859.13

(BK)

Wilson Road

STATION	SEEDING WIDTH	SEEDING WIDTH	SEEDING AREA	SEEDING AREA	CUT - END AREA	FILL - END AREA		CUT - UNADJUSTED VOLUME	FILL - UNADJUSTED VOL.	
	FT	FT	SY	SY	SF	SF		CY	CY	
	659 SEEDING AND MULCHING, CLASS 1	659 SEEDING AND MULCHING, CLASS 3B	659 SEEDING AND MULCHING, CLASS 1	659 SEEDING AND MULCHING, CLASS 3B	203 EXCAVATION (ROADWAY)	203 EMBANKMENT (ROADWAY)	203 EMBANKMENT AS PER PLAN	203 EXCAVATION (ROADWAY)	203 EMBANKMENT (ROADWAY)	203 EMBANKMENT AS PER PLAN
102+46.18	31.26		0.00	0.00	329.89	0.21	-	0.00	0.00	-
102+50.	32.60		13.55	0.00	313.03	0.90	-	45.48	0.08	-
103+00.	38.94		198.71	0.00	310.93	1.99	-	577.74	2.68	-
103+50.	52.39		253.68	0.00	403.64	0.00	-	661.64	1.84	-
104+00.	64.17		323.77	0.00	485.84	0.00	-	823.59	0.00	-
104+50.	67.56		365.92	0.00	529.74	0.04	-	940.35	0.04	-
105+00.	73.73		392.49	0.00	598.92	0.02	-	1045.06	0.06	-
105+50.	79.10		424.53	0.00	553.04	0.00	-	1066.63	0.02	-
106+00.	75.59		429.68	0.00	484.98	0.00	-	961.13	0.00	-
106+50.	66.31		394.17	0.00	309.93	0.00	-	736.03	0.00	-
107+00.	61.85		356.02	0.00	88.82	49.29	-	369.21	45.64	-
107+50.	68.32		361.59	0.00	81.66	128.76	-	157.85	164.86	-
108+00.	75.74		400.17	0.00	0.00	243.98	-	75.61	345.13	-
108+50.	85.84		448.83	0.00	0.00	445.91	-	0.00	638.79	-
109+00.	94.70		501.48	0.00	0.00	656.20	-	0.00	1020.47	-
109+50.	102.91		548.89	0.00	0.00	779.03	-	0.00	1328.92	-
110+00.	94.12		547.28	0.00	0.00	560.34	-	0.00	1240.16	-
110+50.	59.34		426.26	0.00	96.64	154.53	-	89.48	661.92	-
111+00.	46.71		294.57	0.00	96.54	90.54	-	178.87	226.92	-
111+12.38	44.36		62.64	0.00	94.24	54.73	-	43.74	33.30	-
			6744.23	0.00				7772.41	5710.81	

(AH)

(BK)