

SHEET NUM.													PART.	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
						3	5	6	10	11	13	15	01/STR/ PV						
						LS							LS	201	11000	LS		ROADWAY	
										52			52	202	23000	52	SY	CLEARING AND GRUBBING	
									74	41			115	202	35100	115	FT	PAVEMENT REMOVED	
										45			45	202	75000	45	FT	PIPE REMOVED, 24" AND UNDER	
																		FENCE REMOVED	
											162		162	203	10000	162	CY	EXCAVATION	
											57		57	203	20000	57	CY	EMBANKMENT	
										85			85	607	98000	85	FT	FENCE, MISC.:TEMPORARY ORANGE CONSTRUCTION FENCE (OR EQUIVALENT)	6
									2				2	SPECIAL	69050350	2	EACH	MAILBOX REMOVED AND RESET	3
										5			5	601	11001	5	SY	EROSION CONTROL	
						3.5				22			25.5	601	21050	25.5	SY	RIPRAP, TYPE D, AS PER PLAN (USING 6" REINFORCED CONCRETE SLAB)	11
										4			4	601	32200	4	CY	TIED CONCRETE BLOCK MAT WITH TYPE 1 UNDERLAYMENT	
																		ROCK CHANNEL PROTECTION, TYPE C WITH FILTER	
						708							708	659	10001	708	SY	SEEDING AND MULCHING, AS PER PLAN	3A
						0.1							0.1	659	20000	0.1	TON	COMMERCIAL FERTILIZER	
						0.2							0.2	659	31000	0.2	ACRE	LIME	
						4							4	659	35000	4	MGAL	WATER	
									198				198	670	00701	198	SY	DITCH EROSION PROTECTION, AS PER PLAN	3A
													10,000	832	30001	10,000	EACH	EROSION CONTROL, AS PER PLAN	3A
										1.4			1.4	602	20000	1.4	CY	DRAINAGE	
						40							40	605	13300	40	FT	CONCRETE MASONRY	
						90							90	605	31100	90	FT	6" UNCLASSIFIED PIPE UNDERDRAINS	
																		AGGREGATE DRAINS	
						50							50	611	00900	50	FT	6" CONDUIT, TYPE B	
						50							50	611	01400	50	FT	6" CONDUIT, TYPE E	
						65							65	611	01500	65	FT	6" CONDUIT, TYPE F	
									117				117	611	06400	117	FT	15" CONDUIT, TYPE D, 706.02	
									195				195	611	07600	195	FT	18" CONDUIT, TYPE C, 706.02	
										54			54	611	16400	54	FT	36" CONDUIT, TYPE B, 706.02	
										16			16	611	16600	16	FT	36" CONDUIT, TYPE C, 706.02	
									2				2	611	98470	2	EACH	CATCH BASIN, NO. 2-2B	
										1			1	611	98540	1	EACH	CATCH BASIN, NO. 2-4	
						2							2	611	99710	2	EACH	PRECAST REINFORCED CONCRETE OUTLET	
																		PAVEMENT	
						13							13	301	56000	13	CY	ASPHALT CONCRETE BASE, PG64-22, (449)	
						55							55	304	20000	55	CY	AGGREGATE BASE	
						10							10	407	20000	10	GAL	NON-TRACKING TACK COAT	
						3							3	442	22100	3	CY	ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (449)	
						11							11	442	22120	11	CY	ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (449) (DRIVEWAYS)	
						3							3	442	22300	3	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, 12.5 MM, TYPE A (449)	
						8							8	442	22320	8	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, 12.5 MM, TYPE A (449) (DRIVEWAYS)	
																		WATER WORK ALTERNATES	
												36	36	SPECIAL	63820000	36	FT	4" WATER MAIN DIP CLASS 52 MECHANICAL JOINTS AND FITTINGS	15
																		(DEL-CO WATER SPECIFICATIONS) (ALTERNATE 1)	
												12	12	SPECIAL	63820442	12	FT	10" STEEL PIPE ENCASEMENT, OPEN CUT (DEL-CO WATER SPECIFICATIONS) (ALTERNATE 1)	15
												3,000	3,000	SPECIAL	63898000	3,000	EACH	WATER WORKS, MISC.: EX. WATER MAIN CONNECTION (BY DEL-CO WATER) (ALTERNATE 1)	15
												36	36	SPECIAL	63820416	36	FT	4" WATER MAIN POLYVINYL CHLORIDE PIPE AND FITTINGS	15
																		(CLASS 200 SDR 21, DEL-CO WATER SPECIFICATIONS) (ALTERNATE 2)	
												12	12	SPECIAL	63820442	12	FT	10" STEEL PIPE ENCASEMENT, OPEN CUT (DEL-CO WATER SPECIFICATIONS) (ALTERNATE 2)	15
												3,000	3,000	SPECIAL	63898000	3,000	EACH	WATER WORKS, MISC.: EX. WATER MAIN CONNECTION (BY DEL-CO WATER) (ALTERNATE 2)	15
																		TRAFFIC CONTROL	
										0.02			0.02	644	00104	0.02	MILE	EDGE LINE, 6"	
										0.01			0.01	644	00300	0.01	MILE	CENTER LINE	
																		MAINTENANCE OF TRAFFIC	
							32						32	614	11110	32	hour	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	
								LS					LS	614	12420	LS		DETOUR SIGNING	
								35					35	614	13000	35	CY	ASPHALT CONCRETE FOR MAINTAINING TRAFFIC	
							5						5	614	18601	5	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	4-5
								1					1	617	25000	1	MGAL	WATER	
								0.25					0.25	642	00300	0.25	MILE	CENTER LINE, TYPE 1	
																		INCIDENTALS	
													LS	614	11000	LS		MAINTAINING TRAFFIC	
													LS	623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
													LS	624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

DESIGN AGENCY



6350 PRESIDENTIAL GATEWAY
COLUMBUS, OHIO 43231
(614) 823-4949

DESIGNER

BBB

REVIEWER

SSK 10-17-22

PROJECT ID

108799

SHEET

P.8

TOTAL

21

MODEL: Sheet PAPER SIZE: 34x22 (in.) DATE: 4/22/2025 TIME: 12:57:13 PM USER: BradyB
G:\Design Connect Projects\2022IW-22-013 DEL-315\108799\400-Engineering\Utilities\Sheets\10



REVISED 01 DEC 04	SCALE NTS	PAGE 2 OF 2	D-4
----------------------	--------------	-------------	-----

36	12	3,000
----	----	-------

