SHEET NUM. 8	9	11	12	13	28	29	30	35	36	37	PART. 01/NHS/05	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
																ROADWAY	
							512.5				512.5	202	38000	512.5	FT	GUARDRAIL REMOVED	
							893.75				893.75	202	38200	893.75	FT	GUARDRAIL REMOVED FOR REUSE	
							10				10	202	47000	10	EACH	BRIDGE TERMINAL ASSEMBLY REMOVED	
							29				29	203	20001	29	CY	EMBANKMENT, AS PER PLAN	11
							23.19				23.19	209	15001	23.19	STA	RESHAPING UNDER GUARDRAIL, AS PER PLAN	11
					14.66	14.94					29.6	209	60500	29.6	MILE	LINEAR GRADING	
							512.5				512.5	606	13000	512.5	FT	GUARDRAIL, TYPE 5	
							893.75				893.75	606	16500	893.75	FT	GUARDRAIL REBUILT, TYPE 5	
							862.5				862.5	606	17000	862.5	FT	RAISING TYPE 5 GUARDRAIL	
							2				2	606	35000	2	EACH	BRIDGE TERMINAL ASSEMBLY, TYPE 1	
							4				4	606	35100	4	EACH	BRIDGE TERMINAL ASSEMBLY, TYPE 2	
							4				4	606	35140	4	EACH	BRIDGE TERMINAL ASSEMBLY, TYPE 4	
		1,000									1,000	606	98000	1,000	FT	GUARDRAIL, MISC.: MEDIAN BOX BEAM RAIL REMOVED	11
		1,000									1,000	606	98000	1,000	FT	GUARDRAIL, MISC.: MEDIAN BOX BEAM RAIL	11
	2,000										2,000	SPECIAL	61199820	2,000	LB	MISCELLANEOUS METAL	9
																EROSION CONTROL	
											2,000	832	30000	2,000	EACH	EROSION CONTROL	
																DRAINAGE	
	51										51	611	98630	51	EACH	CATCH BASIN ADJUSTED TO GRADE	
																PAVEMENT	
1,285											1,285	251	01042	1,285	CY	PARTIAL DEPTH PAVEMENT REPAIR (ASPHALT CONCRETE BASE) (LONGITUDINAL)	
70											70	251	01042	70	CY	PARTIAL DEPTH PAVEMENT REPAIR (ASPHALT CONCRETE BASE) (TRANSVERSE)	
130											130	253	02000	130	CY	PAVEMENT REPAIR (LONGITUDINAL)	
5											5	253	02000	5	CY	PAVEMENT REPAIR (TRANSVERSE)	
					18,540	47,465					66,005	254	01000	66,005	SY	PAVEMENT PLANING, ASPHALT CONCRETE (1.50 INCH)	
					174,673	173,065					347,738	254	01000	347,738	SY	PAVEMENT PLANING, ASPHALT CONCRETE (1.75 INCH)	
					4,220	4,552					8,772	254	01000	8,772	SY	PAVEMENT PLANING, ASPHALT CONCRETE (TAPER 1.75 TO 1.50 INCH)	
					973	1,113					2,086	254	01600	2,086	SY	PATCHING PLANED SURFACE	
	4,454										4,454	255	15000	4,454	SY	FULL DEPTH PAVEMENT REMOVAL AND RIGID REPLACEMENT, TYPE 1, CLASS QC MS	
	19,603										19,603	255	20000	19,603	FT	FULL DEPTH PAVEMENT SAWING	
					15,560	17,740					33,300	407	10000	33,300	GAL	TACK COAT	
					6,876	7,009					13,885	408	10001	13,885	GAL	PRIME COAT, AS PER PLAN	9
					5,570	5,504					11,074	442	00100	11,074	CY	ANTI-SEGREGATION EQUIPMENT	
					8,100	9,241					17,341	442	10300	17,341	CY	ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (447) (PG70-22)	
	371										371	442	22400	371	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, 19 MM, TYPE A (449)	
					954	974					1,928	617	10100	1,928	CY	COMPACTED AGGREGATE	
					17,189	17,521					34,710	617	20000	34,710	SY	SHOULDER PREPARATION	
					14.6	14.6					29.2	618	40600	29.2	MILE	RUMBLE STRIPS, SHOULDER (ASPHALT CONCRETE)	
																TRAFFIC CONTROL	
									1,302		1,302	621	00100	1,302	EACH	RPM	
									1,302		1,302	621	54000	1,302	EACH	RAISED PAVEMENT MARKER REMOVED	
							21				21	626	00110	21	EACH	BARRIER REFLECTOR, TYPE 2, 1 WAY	
							5				5	626	00110	5	EACH	BARRIER REFLECTOR, TYPE 2, BIDIRECTIONAL	
								279			279	644	00500	279	FT	STOP LINE	
								115			115	644	00700	115	FT	TRANSVERSE/DIAGONAL LINE	
								537			537	644	00720	537	FT	CHEVRON MARKING	
								10			10	644	40000	10	EACH	SPEED MEASUREMENT MARKING	
								161			161	646	10600	161	FT	TRANSVERSE/DIAGONAL LINE	
								1.5			1.5	807	12010	1.5	MILE	WET REFLECTIVE EPOXY PAVEMENT MARKING, EDGE LINE, 6"	
								0.69			0.69	807	12110	0.69	MILE	WET REFLECTIVE EPOXY PAVEMENT MARKING, LANE LINE, 6"	
								488			488	807	12310	488	FT	WET REFLECTIVE EPOXY PAVEMENT MARKING, CHANNELIZING LINE, 12"	
								35.8			35.8	807	14010	35.8	MILE	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, EDGE LINE, 6"	
								15.44			15.44	807	14110	15.44	MILE	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, LANE LINE, 6"	
								4,210			4,210	807	14310	4,210	FT	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, CHANNELIZING LINE, 12"	

GENERAL SUMMARY

DESIGN AGENCY
DISTRICT 3
ENGINEERING TEAM ONE

DESIGNER
JLL

REVIEWER
KRB 7-2024

PROJECT ID
115168

SHEET P.26 TOTAL 60

ERI-2-0.00

MODEL: Sheet1 PAPERSIZE: 34x22 (in.) DATE: 11/12/2024 TIME: 2:33:58 PM USER: jlowery
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 03\Erie\115168\400-Engineering\Roadway\Sheets\115168_GG001.dgn

SHEET NUM. 8	9	11	12	13	28	29	30	35	36	37	PART. 01/NHS/05	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
								5,343			5,343	807	14410	5,343	FT	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, DOTTED LINE, 6"	
								51.24			51.24	850	10010	51.24	MILE	GROOVING FOR 6" RECESSED PAVEMENT MARKING, (ASPHALT)	
								5,343			5,343	850	10110	5,343	FT	GROOVING FOR 6" RECESSED PAVEMENT MARKING, (ASPHALT)	
								4,210			4,210	850	10130	4,210	FT	GROOVING FOR 12" RECESSED PAVEMENT MARKING, (ASPHALT)	
								2.18			2.18	850	20010	2.18	MILE	GROOVING FOR 6" RECESSED PAVEMENT MARKING, (CONCRETE)	
								488			488	850	20130	488	FT	GROOVING FOR 12" RECESSED PAVEMENT MARKING, (CONCRETE)	
																TRAFFIC SIGNALS	
	4										4	632	26501	4	EACH	DETECTOR LOOP, AS PER PLAN	9
																STRUCTURE REPAIR (ERI-2-0.63)	
										1,681	1,681	512	73500	1,681	SY	TREATING CONCRETE BRIDGE DECKS WITH GRAVITY FED RESIN	
										275	275	517	75600	275	FT	DEEP BEAM BRIDGE RETROFIT RAILING	
										15	15	SPECIAL	51912510	15	SY	PATCHING CONCRETE BRIDGE DECK - TYPE B	37
																STRUCTURE REPAIR (ERI-2-1.425)	
										37.5	37.5	202	38500	37.5	FT	BRIDGE RAILING REMOVED	
										37.5	37.5	517	72300	37.5	FT	RAILING (DEEP BEAM RAIL WITH STEEL TUBULAR BACKUP AND TYPE 2 STEEL POSTS AND ANCHOR BOLTS)	
										75	75	517	75600	75	FT	DEEP BEAM BRIDGE RETROFIT RAILING	
																MAINTENANCE OF TRAFFIC	
				760							760	614	11110	760	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	
			LS								LS	614	12420	LS		DETOUR SIGNING	
			100								100	614	13000	100	CY	ASPHALT CONCRETE FOR MAINTAINING TRAFFIC	
				45							45	614	18601	45	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	13
								30.88			30.88	614	20560	30.88	MILE	WORK ZONE LANE LINE, CLASS III, 6", 642 PAINT	
								71.6			71.6	614	22360	71.6	MILE	WORK ZONE EDGE LINE, CLASS III, 6", 642 PAINT	
								9,396			9,396	614	23690	9,396	FT	WORK ZONE CHANNELIZING LINE, CLASS III, 12", 642 PAINT	
								10,686			10,686	614	24612	10,686	FT	WORK ZONE DOTTED LINE, CLASS III, 6", 642 PAINT	
								558			558	614	26610	558	FT	WORK ZONE STOP LINE, CLASS III, 642 PAINT	
				110							110	808	18700	110	SNMT	DIGITAL SPEED LIMIT (DSL) SIGN ASSEMBLY	
																INCIDENTALS	
											LS	614	11000	LS		MAINTAINING TRAFFIC	
											6	619	16020	6	MNTH	FIELD OFFICE, TYPE C	
											LS	623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
											LS	624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

ERI-2-0.00

MODEL: Sheet2 PAPERSIZE: 34x22 (in.) DATE: 11/12/2024 TIME: 2:33:58 PM USER: jlowery
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 03\Erie\115168\400-Engineering\Roadway\Sheets\115168_GG001.dgn

DESIGN AGENCY
DISTRICT 3
ENGINEERING TEAM ONE

DESIGNER
JLL

REVIEWER
KRB 7-2024

PROJECT ID
115168

SHEET P.27 TOTAL 60