SHEET NUM.									PART.				ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
6	7	10	13	14	14C	15	21	26	01/S<2/BR	02/S<2/PV	03/S<2/PV	04/S>2/PV						
																	ROADWAY	
					388						388		202	23000	388	SY	PAVEMENT REMOVED	
						4,697					4,697		202	30000	4,697	SF	WALK REMOVED	
					149	116					265		202	32000	265	FT	CURB REMOVED	
	3,380										3,380		202	32001	3,380	FT	CURB REMOVED, AS PER PLAN	7
			2.51							2.51			209	60500	2.51	MILE	LINEAR GRADING	
		20								20			209	80000	20	EACH	GRADING MAILBOX APPROACHES	
						3,534					3,534		608	10000	3,534	SF	4" CONCRETE WALK	
						1,163					1,163		608	52000	1,163	SF	CURB RAMP	
						568					568		608	53020	568	SF	DETECTABLE WARNING	
	300										300		609	14001	300	FT	CURB, TYPE 2-A, AS PER PLAN	7
	80										80		609	16001	80	FT	CURB, TYPE 2-B, AS PER PLAN	7
					149						149		609	26000	149	FT	CURB, TYPE 6	
	3,000										3,000		609	26001	3,000	FT	CURB, TYPE 6, AS PER PLAN	7
	40									40			623	39500	40	EACH	MONUMENT BOX ADJUSTED TO GRADE	
																	EROSION CONTROL	
									15	485	185	315	832	30000	1,000	EACH	EROSION CONTROL	
																	DRAINAGE	
	36				3					36	3		611	98630	39	EACH	CATCH BASIN ADJUSTED TO GRADE	
	8										8		611	99155	8	EACH	INLET RECONSTRUCTED TO GRADE, AS PER PLAN	7
	149				4					149	4		611	99654	153	EACH	MANHOLE ADJUSTED TO GRADE	
																	PAVEMENT	
					388						388		204	10000	388	SY	SUBGRADE COMPACTION	
775											775		251	01042	775	CY	PARTIAL DEPTH PAVEMENT REPAIR (ASPHALT CONCRETE BASE)	
65											65		253	02000	65	CY	PAVEMENT REPAIR	
			116,077							116,077			254	01000	116,077	SY	PAVEMENT PLANING, ASPHALT CONCRETE (1.50 INCH)	
			582							582			254	01600	582	SY	PATCHING PLANED SURFACE	
				382								382	255	10160	382	SY	FULL DEPTH PAVEMENT REMOVAL AND RIGID REPLACEMENT, CLASS QC MS	
				418								418	255	10161	418	SY	FULL DEPTH PAVEMENT REMOVAL AND RIGID REPLACEMENT, CLASS QC MS, AS PER PLAN	6
				6,632								6,632	255	20000	6,632	FT	FULL DEPTH PAVEMENT SAWING	
				920								920	256	10000	920	SF	BONDED PATCHING OF PORTLAND CEMENT CONCRETE PAVEMENT, TYPE A	
				27,596								27,596	257	10000	27,596	SY	DIAMOND GRINDING PORTLAND CEMENT CONCRETE PAVEMENT	
					97						97		301	46000	97	CY	ASPHALT CONCRETE BASE, PG64-22	
					65						65		304	20000	65	CY	AGGREGATE BASE	
			9,312		39					9,312	39		407	20000	9,351	GAL	NON-TRACKING TACK COAT	
			1,218							1,218			408	10001	1,218	GAL	PRIME COAT, AS PER PLAN	7
			4,852		32					4,852	32		442	00201	4,884	CY	ASPHALT CONCRETE SURFACE COURSE, 9.5 MM, TYPE A (446), AS PER PLAN (PG64-22)	7
		20	169							189			617	10100	189	CY	COMPACTED AGGREGATE	
																	WATER WORK	
	24				1					24	1		638	10800	25	EACH	VALVE BOX ADJUSTED TO GRADE	
																	TRAFFIC CONTROL	
						2,500				2,500			642	00800	2,500	FT	CURB MARKING, TYPE 1	
						0.05				0.05			646	10000	0.05	MILE	EDGE LINE, 4"	
						0.82				0.82			646	10100	0.82	MILE	LANE LINE, 4"	
						0.51				0.51			646	10200	0.51	MILE	CENTER LINE	
						335				335			646	10300	335	FT	CHANNELIZING LINE, 8"	
						74				74			646	10400	74	FT	STOP LINE	
						371				371			646	10500	371	FT	CROSSWALK LINE	
						14				14			646	20300	14	EACH	LANE ARROW	
						776				776			646	20502	776	FT	DOTTED LINE, 4"	
																	TRAFFIC CONTROL ALTERNATES	
						2.49				2.49			642	00100	2.49	MILE	EDGE LINE, 4", TYPE 1 (ALTERNATE 1)	
						1.17				1.17			642	00200	1.17	MILE	LANE LINE, 4", TYPE 1 (ALTERNATE 1)	
						4.91				4.91			642	00300	4.91	MILE	CENTER LINE, TYPE 1 (ALTERNATE 1)	
						4,257				4,257			642	00400	4,257	FT	CHANNELIZING LINE, 8", TYPE 1 (ALTERNATE 1)	
						957				957			642	00500	957	FT	STOP LINE, TYPE 1 (ALTERNATE 1)	

CALCULATED JLL
CHECKED KRB

GENERAL SUMMARY

ERI-6-6.41
ERI-250-0.00

11
28

I:\ProjectData\92889\Design\Roadway\Sheets\92889_GG001.dgn

SHEET NUM.									PART.				ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
8	9	10	13	14	14C	21	26	28	01\S<2\BR	02\S<2\PV	03\S<2\PV	04\S>2\PV						
						6,451				6,451			642	00600	6,451	FT	CROSSWALK LINE, TYPE 1 (ALTERNATE 1)	
						245				245			642	00700	245	FT	TRANSVERSE/DIAGONAL LINE, TYPE 1 (ALTERNATE 1)	
						2				2			642	01100	2	EACH	SCHOOL SYMBOL MARKING, 72", TYPE 1 (ALTERNATE 1)	
						1				1			642	01110	1	EACH	SCHOOL SYMBOL MARKING, 96", TYPE 1 (ALTERNATE 1)	
						3,452				3,452			642	01200	3,452	FT	PARKING LOT STALL MARKING, TYPE 1 (ALTERNATE 1)	
						106				106			642	01300	106	EACH	LANE ARROW, TYPE 1 (ALTERNATE 1)	
						1				1			642	01312	1	EACH	LANE REDUCTION ARROW, TYPE 1 (ALTERNATE 1)	
						441				441			642	01500	441	FT	DOTTED LINE, 4", TYPE 1 (ALTERNATE 1)	
						2.49				2.49			644	00100	2.49	MILE	EDGE LINE, 4" (ALTERNATE 2)	
						1.17				1.17			644	00200	1.17	MILE	LANE LINE, 4" (ALTERNATE 2)	
						4.91				4.91			644	00300	4.91	MILE	CENTER LINE (ALTERNATE 2)	
						4,257				4,257			644	00400	4,257	FT	CHANNELIZING LINE, 8" (ALTERNATE 2)	
						957				957			644	00500	957	FT	STOP LINE (ALTERNATE 2)	
						6,451				6,451			644	00600	6,451	FT	CROSSWALK LINE (ALTERNATE 2)	
						245				245			644	00700	245	FT	TRANSVERSE/DIAGONAL LINE (ALTERNATE 2)	
						2				2			644	01100	2	EACH	SCHOOL SYMBOL MARKING, 72" (ALTERNATE 2)	
						1				1			644	01110	1	EACH	SCHOOL SYMBOL MARKING, 96" (ALTERNATE 2)	
						3,452				3,452			644	01200	3,452	FT	PARKING LOT STALL MARKING (ALTERNATE 2)	
						106				106			644	01300	106	EACH	LANE ARROW (ALTERNATE 2)	
						1				1			644	01350	1	EACH	LANE REDUCTION ARROW (ALTERNATE 2)	
						441				441			644	01500	441	FT	DOTTED LINE, 4" (ALTERNATE 2)	
																	TRAFFIC SIGNALS	
							43			43			632	26501	43	EACH	DETECTOR LOOP, AS PER PLAN	26
																	STRUCTURE REPAIR (ERI-6-10.09)	
								95	95				202	98200	95	FT	REMOVAL MISC.: JOINT SEALER	27
								76	76				512	10100	76	SY	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)	
								119	119				512	73501	119	SY	TREATING CONCRETE BRIDGE DECKS WITH GRAVITY FED RESIN, AS PER PLAN	27
								76	76				512	74000	76	SY	REMOVAL OF EXISTING COATINGS FROM CONCRETE SURFACES	
								95	95				516	31000	95	FT	JOINT SEALER	
																	MAINTENANCE OF TRAFFIC	
	300										300		614	11110	300	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	
10										10			614	12460	10	EACH	WORK ZONE MARKING SIGN	
25										25			614	13000	25	CY	ASPHALT CONCRETE FOR MAINTAINING TRAFFIC	
8										8			614	18601	8	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	8
						0.4				0.4			614	20200	0.4	MILE	WORK ZONE LANE LINE, CLASS I, 4", 740.06, TYPE I	
						2.38				2.38			614	20550	2.38	MILE	WORK ZONE LANE LINE, CLASS III, 4", 642 PAINT	
					0.12	0.25				0.25	0.12		614	21200	0.37	MILE	WORK ZONE CENTER LINE, CLASS I, 740.06, TYPE I	
						9.86				9.86			614	21550	9.86	MILE	WORK ZONE CENTER LINE, CLASS III, 642 PAINT	
					0.36						0.36		614	22210	0.36	MILE	WORK ZONE EDGE LINE, CLASS I, 6", 740.06, TYPE I	
						150				150			614	23400	150	FT	WORK ZONE CHANNELIZING LINE, CLASS I, 8", 740.06, TYPE I	
						8,514				8,514			614	23680	8,514	FT	WORK ZONE CHANNELIZING LINE, CLASS III, 8", 642 PAINT	
					462						462		614	24400	462	FT	WORK ZONE DOTTED LINE, CLASS I, 4", 740.06, TYPE I	
						74				74			614	26400	74	FT	WORK ZONE STOP LINE, CLASS I, 740.06, TYPE I	
						1,654				1,654			614	26610	1,654	FT	WORK ZONE STOP LINE, CLASS III, 642 PAINT	
					LS						LS		615	10000	LS		ROADS FOR MAINTAINING TRAFFIC	
					21						21		615	25000	21	SY	PAVEMENT FOR MAINTAINING TRAFFIC, CLASS B	
																	INCIDENTALS	
									LS	LS	LS	LS	614	11000	LS		MAINTAINING TRAFFIC	
										3			619	16010	3	MNTH	FIELD OFFICE, TYPE B	
									LS	LS	LS	LS	623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
									LS	LS	LS	LS	624	10000	LS		MOBILIZATION	

Item 642 - Curb Marking, Type 1 (Alternate 1) has been deleted

Item 644 - Curb Marking (Alternate 2) has been deleted.

CALCULATED JLL
CHECKED KRB

GENERAL SUMMARY

ERI-6-6.41
ERI-250-0.00

H:\ProjectData\92889\Design\Roadway\Sheets\92889_GG001.dgn