SHEET NUMBER													PART.	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
P.112	P.115	P.125	P.127	OFFICE CALCS									01/SAF/21						
																		LIGHTING	
			20										20	625	00450	20	EACH	CONNECTION, FUSED PULL APART	
			21										21	625	00480	21	EACH	CONNECTION, UNFUSED PERMANENT	
			10										10	625	10490	10	EACH	LIGHT POLE, CONVENTIONAL, AT15B40	
			10										10	625	14100	10	EACH	LIGHT POLE FOUNDATION, 24" X 8' DEEP	
			1,845										1,845	625	23200	1,845	FT	NO. 4 AWG 2400 VOLT DISTRIBUTION CABLE	
			1,650										1,650	625	23400	1,650	FT	NO. 10 AWG POLE AND BRACKET CABLE	
			1,066										1,066	625	25500	1,066	FT	CONDUIT, 3", 725.04	
			221										221	625	25902	221	FT	CONDUIT, JACKED OR DRILLED, 725.04 (3")	
			10										10	625	26253	10	EACH	LUMINAIRE, CONVENTIONAL, SOLID STATE (LED), AS PER PLAN, IES-II-M, LED, 9317-11000 LUMENS	P.125
			1,039										1,039	625	29000	1,039	FT	TRENCH	
			5										5	625	30700	5	EACH	PULL BOX, 725.08, 18"	
			1										1	625	30706	1	EACH	PULL BOX, 725.08, 24"	
			2										2	625	31510	2	EACH	PULL BOX REMOVED	
			10										10	625	32000	10	EACH	GROUND ROD	
			1										1	625	34001	1	EACH	POWER SERVICE, AS PER PLAN	P.125
			1,260										1,260	625	36010	1,260	FT	UNDERGROUND WARNING/MARKING TAPE	
		LS											LS	625	39000	LS		TEMPORARY LIGHTING	P.125
		LS											LS	SPECIAL	62540000	LS		MAINTAIN EXISTING LIGHTING	P.125
			2										2	625	75403	2	EACH	LIGHT POLE REMOVED FOR STORAGE, AS PER PLAN	P.125
		1											1	625	75801	1	EACH	DISCONNECT CIRCUIT, AS PER PLAN	P.125
			1										1	625	76000	1	EACH	ARC FLASH CALCULATIONS AND LABEL, FAY-22-6.21	
			1										1	632	70400	1	EACH	CONDUIT RISER, 2" DIAMETER	
			1										1	633	67200	1	EACH	CONTROLLER WORK PAD	
																		TRAFFIC CONTROL	
69													69	621	00100	69	EACH	RPM	
	248												248	630	02100	248	FT	GROUND MOUNTED SUPPORT, NO. 2 POST	
	178												178	630	03100	178	FT	GROUND MOUNTED SUPPORT, NO. 3 POST	
	59												59	630	04100	59	FT	GROUND MOUNTED SUPPORT, NO. 4 POST (SQUARE POST)	
	26												26	630	06400	26	FT	GROUND MOUNTED STRUCTURAL BEAM SUPPORT, S4X7.7	
	15												15	630	08600	15	EACH	SIGN POST REFLECTOR	
	2												2	630	09000	2	EACH	BREAKAWAY STRUCTURAL BEAM CONNECTION	
	220												220	630	80100	220	SF	SIGN, FLAT SHEET	
	27												27	630	80200	27	SF	SIGN, GROUND MOUNTED EXTRUSHEET	
	2												2	630	84500	2	EACH	GROUND MOUNTED STRUCTURAL BEAM SUPPORT FOUNDATION	
	30												30	630	84900	30	EACH	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL	
	26												26	630	86002	26	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	
	3												3	630	86102	3	EACH	REMOVAL OF GROUND MOUNTED STRUCTURAL BEAM SUPPORT AND DISPOSAL	
0.74													0.74	644	00104	0.74	MILE	EDGE LINE, 6"	
0.14													0.14	644	00300	0.14	MILE	CENTER LINE	
45													45	644	00700	45	FT	TRANSVERSE/DIAGONAL LINE	
1													1	644	01000	1	EACH	RAILROAD SYMBOL MARKING	
203													203	644	01520	203	FT	DOTTED LINE, 12"	
73													73	644	20800	73	FT	YIELD LINE	

GENERAL SUMMARY

DESIGN AGENCY
B&N
burgessniple.com

DESIGNER
RNK

REVIEWER
MRT 09/15/25

PROJECT ID
119587

SHEET P.69 TOTAL P.137

FAY-22-6.21

MODEL: Sheet_SurvFt PAPERSIZE: 34x22 (in.) DATE: 11/21/2025 TIME: 10:29:04 AM USER: kuhlman
pw:\\bn-pw.bentley.com:bn-pw-03\Documents\Ohio\OHDOT\PR61662\119587\400-Engineering\Roadway\Sheets\119587_GG001

SIGNING ESTIMATED QUANTITIES

SHEET NO.	REFERENCE NO.	LOCATION	STATION	SIDE	CODE	SIZE (INCHES)	630 SIGN, FLAT SHEET SQ FT	630 SIGN, GROUND MOUNTED EXTRUSHEET SQ FT	630 GROUND MOUNTED SUPPORT, NO. 2 POST FT	630 GROUND MOUNTED SUPPORT, NO. 3 POST FT	630 GROUND MOUNTED SUPPORT, NO. 4 SQUARE POST FT	630 GROUND MOUNTED STRUCTURAL BEAM SUPPORT, S4X7.7 FT	630 REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL EACH	630 REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL EACH	630 REMOVAL OF GROUND MOUNTED STRUCTURAL BEAM SUPPORT AND DISPOSAL EACH	630 SIGN POST REFLECTOR EACH	630 BREAKAWAY STRUCTURAL BEAM CONNECTION EACH	630 GROUND MOUNTED STRUCTURAL BEAM SUPPORT FOUNDATION EACH		
P.123	S-34	JAMISON RD	203+00	RT	W3-2-36	36 X 36	9.0			14.1					1					
					M6-4-21	21 X 15	2.2													
P.124	S-35	JAMISON RD	207+80	LT	M1-4-24-2	24 X 24	4.0			13.5										
					M6-4-21	21 X 15	2.2													
P.124	S-36	JAMISON RD	209+80	LT	W3-2-36	36 X 36	9.0			14.1						1				
P.124	S-37	JAMISON RD	211+30	LT	W2-6-36	36 X 36	9.0			14.1						1				
P.117	S-38	US 22	117+30	LT	R3-H8ba-30	30 X 30	6.3			12.8										
P.119	S-39	US 22	124+00	RT	M2-H4-108	108 X 36		27.0				13.0 - 13.0					2	2		
TOTALS FROM THIS SHEET							42	27	0	69	0	26	0	0	1	2	2	2		
TOTALS FROM SHEET P. 114							33	0	0	41	15	0	30	26	2	2	0	0		
TOTALS FROM SHEET P. 115							146	0	248	68	44	0	0	0	0	11	0	0		
TOTALS CARRIED TO GENERAL SUMMARY							220	27	248	178	59	26	30	26	3	15	2	2		

FAY-22-6.21

MODEL: Sheet_SurvFt PAPERSIZE: 34x22 (in.) DATE: 11/21/2025 TIME: 8:22:20 AM USER: srifflle
pw:\\bn-pw.bentley.com:bn-pw-03\Documents\Ohio\OHDOTPR61662\119587\402-Engineering-Compass\Traffic\Sheets\119587_TS004.dgn

DESIGN AGENCY
COMPASS INFRASTRUCTURE GROUP

DESIGNER
KMK

REVIEWER
SSR 03-17-25

PROJECT ID
119587

SHEET P.115 TOTAL P.137