

STRUCTURE ESTIMATED QUANTITIES

Sheeting Wall 4W21 along I-71 NB / Ramp A5

**FRA-70/71-12.68/14.86
PID No. 105523**

Franklin County, Ohio

Prepared For:

**The Ohio Department of Transportation
District 6**



**1801 Watermark Drive, Suite 150
Columbus, Ohio 43215
(614) 210-0751
www.gpdgroup.com**

May 31, 2019

Project: FRANKLIN COUNTY -4W21 Design: TJW
Subject: Estimated Quantities - Paper Tracings Check: RFV
Date: 5/31/2019

ITEM 504 - SHEET PILING LEFT IN PLACE, AS PER PLAN

Wall 4W21A area : 4101 sf cadd area
Wall 4W21B area : 4517 sf "
Wall 4W21C area : 2114 sf "

Total = **10732 sf**

ITEM 518 - POROUS BACKFILL WITH GEOTEXTILE FABRIC

Wall 4W21A area : 566 sf exist ground to 1' below grade
Wall 4W21B area : 620 sf "
Wall 4W21C area : 161 sf "
thickness : 2 ft

Total = **100 cy**

ITEM 518 - 6" PERFORATED CORRUGATED PLASTIC PIPE

length = 384.58 ft, wall length used

Total = **385 ft**