



## Post Construction - Project Summary

## Project Data

Project EDA	5.84	Units acres
Is the Project Routine Maintenance per L&D Vol. 2, Sec. 1112.2	No	
BMPs Required?	BMPs Required	NA
Ain (New Impervious Area in New Permanent R/W	0	acres
Does Entire Site Drain to Large River (>100 sq. miles)?	No	
Water Quality Treatment Required	Yes	
Water Quantity Treatment Required	No	

## Treatment Percent and Treatment Requirement

Aix (Project EDA that is inside the existing right-of-way)	5.84	acres
Ain (New Impervious Area in New Permanent R/W)	0	acres
T% (Treatment Percent)	20.00	%
Treatment Requirement	1.17	acres

## BMPs Provided

BMP Name	BMP Type	Contributing Drainage Area (acres)	Contributing Drainage Area in ODOT R/W (acres)
VBFB1	Vegetated Biofilter	0.96	0.66
VBFB2	Vegetated Biofilter	0.83	0.62

## Treatment Provided

Total Area with ODOT R/W Treated (acres)	1.28
Treatment Requirements (acres)	1.17
Treatment Check	Good

## BMP Submittal Requirements (Per L&amp;D, Vol. 2, Sec. 1116.2)

1. Estimated Project Earth Disturbed Area	Yes	Good
2. Treatment Percent Calculation	Yes	Good
3. BMP Selected for use	Yes	Good
4. Drainage area mapping for post-construction BMPs that show the total contributing drainage area and the amount of contributing area within ODOT right-of-way	Yes	Good
5. Plan sheets showing locations of post-construction BMP	Yes	Good
6. Calculations for each BMP	Yes	Good
7. Explanation for any area that is not treated	Yes	Good