SHEET NUM.													PART.	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
P. 10		P. 11		P. 15		P. 20							01/SAF/21						
																		ROADWAY	
														201	11000	LS		CLEARING AND GRUBBING	P. 5
178													178	202	23000	178	SY	PAVEMENT REMOVED	
2,357													2,357	202	30000	2,357	SF	WALK REMOVED	
74													74	202	35100	74	FT	PIPE REMOVED, 24" AND UNDER	
25													25	202	38000	25	FT	GUARDRAIL REMOVED	
				212									212	203	10000	212	CY	EXCAVATION	
				34									34	203	20000	34	CY	EMBANKMENT	
													488	204	10000	488	SY	SUBGRADE COMPACTION	
25													25	606	15050	25	FT	GUARDRAIL, TYPE MGS	
171													171	608	52000	171	SF	CURB RAMP	
31													31	609	28001	31	FT	CURB, TYPE 7, AS PER PLAN	P. 16
																		EROSION CONTROL	
				382									382	659	10000	382	SY	SEEDING AND MULCHING	
													0.03	659	20000	0.03	TON	COMMERCIAL FERTILIZER	
													1	659	35000	1	MGAL	WATER	
													0.1	659	40000	0.1	MSF	MOWING	
													5,000	832	30000	5,000	EACH	EROSION CONTROL	
													121	836	10000	121	SY	SEEDING AND EROSION CONTROL WITH TURF REINFORCING MAT, TYPE 1	
																		DRAINAGE	
													301	605	06000	301	FT	4" BASE PIPE UNDERDRAINS	
35													35	611	05900	35	FT	15" CONDUIT, TYPE B	
1													1	611	98470	1	EACH	CATCH BASIN, NO. 2-2B	
																		PAVEMENT	
													374	252	01500	374	FT	FULL DEPTH PAVEMENT SAWING	
													166	254	01000	166	SY	PAVEMENT PLANING, ASPHALT CONCRETE, 3"	
													69	301	56000	69	CY	ASPHALT CONCRETE BASE, PG64-22, (449)	
39													39	304	20000	39	CY	AGGREGATE BASE	
													93	304	20001	93	CY	AGGREGATE BASE, AS PER PLAN	P. 5
													791	407	20000	791	GAL	NON-TRACKING TACK COAT	
20													67	441	70000	67	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (449), PG64-22	
																		TRAFFIC CONTROL	
		8											8	621	00100	8	EACH	RPM	
		8											8	621	54000	8	EACH	RAISED PAVEMENT MARKER REMOVED	
		55											55	630	03100	55	FT	GROUND MOUNTED SUPPORT, NO. 3 POST	
		~~1~~											~~1~~	~~630~~	~~72530~~	~~1~~	~~EACH~~	~~OVERHEAD SIGN SUPPORT, TYPE TC-16.22, DESIGN 9~~	
		1											1	630	84510	1	EACH	RIGID OVERHEAD SIGN SUPPORT FOUNDATION	
		94											94	630	80100	94	SF	SIGN, FLAT SHEET	
		1											1	630	84900	1	EACH	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL	
		1											1	630	86002	1	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	
		223											223	644	00400	223	FT	CHANNELIZING LINE, 8"	
		12											12	644	00500	12	FT	STOP LINE	
		19											19	644	00620	19	FT	CROSSWALK LINE, 12"	
		5											5	644	01300	5	EACH	LANE ARROW	
		103											103	644	01510	103	FT	DOTTED LINE, 6"	
		2											2	644	30020	2	EACH	REMOVAL OF PAVEMENT MARKING	

GENERAL SUMMARY

DESIGN AGENCY
STRAND ASSOCIATES®

DESIGNER
TMK

REVIEWER
JDH 01-02-24

PROJECT ID
119049

SHEET P.8 TOTAL 20

FRA-161-8.66

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 4/9/2024 TIME: 4:53:31 PM USER: JordanG
S:\CIN3500--3599\3589\027\Drawings\CAD\119\049\400-Engineering\Roadway\Sheets\119049_GG001.dgn

TRAFFIC CONTROL SUBSUMMARY

REF NO.	SHEET NO.	STATION TO STATION	621 RPM EACH	621 RAISED PAVEMENT MARKER REMOVED EACH		630 SIGN, FLAT SHEET SF	630 GROUND MOUNTED SUPPORT, NO. 3 POST FT	630 OVERHEAD SIGN SUPPORT, TYPE TC-16.22, DESIGN 9 EACH	630 RIGID OVERHEAD SIGN SUPPORT FOUNDATION EACH	630 REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL EACH	630 REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL EACH			644 DOTTED LINE, 6" FT	644 LANE ARROW EACH	644 STOP LINE FT	644 CROSSWALK LINE, 12" FT	644 ITEM CODE DOES NOT EXIST IN ITEM MASTER	644 REMOVAL OF PAVEMENT MARKING EACH				
		TO																					
		S.R. 161 (W DUBLIN GRANVILLE ROAD)																					
CR-1	P. 18	15+37 16.5' RT 15+37 25.1' RT																8.7					
CR-2	P. 18	15+47 18.6' RT 15+47 28.7' RT																10					
CH-1	P. 18	13+04 11.5' RT 15+27 11.5' RT														223							
LA-1	P. 18	13+32													1								
LA-2	P. 18	14+23													1								
LA-3	P. 18	15+16													1								
S-1	P. 18	10+85 RT				10.6	14.2																
S-2	P. 18	12+54 RT				13.1	15.2																
S-3	P. 18	13+92 RT				10	13																
SL-1	P. 18	15+27 11.5' RT 15+27 23.6' RT															11.7						
RM-1	P. 18	13+04 11' RT 15+24 11' RT	8	8																			
		OLENTANGY RIVER ROAD																					
DL-1	P. 19	21+49 60.4' RT 22+04 12.6' LT												102.4									
LA-4	P. 19	22+46													1				1				
LA-5	P. 19	23+44													1				1				
R-1	P. 19	23+83 LT								1	1												
S-4	P. 19	21+01 RT				6.3	12.0																
S--5	P. 19	23+78 LT				26.8																	
S--6	P. 19	23+78 LT				26.8																	
SP-1	P. 19	27+78 32.4' LT						1	1														
TOTALS CARRIED TO GENERAL SUMMARY			8	8		94.0	55.0	1	1	1	1			103	5	223	12		2				

FRA-161-8.66

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 4/9/2024 TIME: 4:45:09 PM USER: JordanG
S:\CIN\3500--3599\3589\027\Drawings\CAD\119049\400-Engineering\Traffic\Sheets\119049_TS001.dgn

DESIGN AGENCY
STRAND ASSOCIATES®

DESIGNER
TMK

REVIEWER
JDH 01-02-24

PROJECT ID
119049