


DETERIORATION MAP FRA-270-50.90 OVER INTERSTATE ROUTE 270 FRANKLIN COUNTY STATE OF OHIO




DETERIORATION MAP
FRA-270-50.90
OVER INTERSTATE ROUTE 270
FRANKLIN COUNTY
STATE OF OHIO

RESOURCE INTERNATIONAL, INC.
6500 SADDLE CREEK CAVATWAY
COLUMBUS, OHIO 43231
(614) 623-4949



DRAWN BY: GTF	DATE: 6-2-2014	DRAWING NO.: 00-0	SHEET: 1 OF 1
CHECKED BY: CAY			
JOB NO.: W-13-144			



DETERIORATION - REAR APPROACH SLAB

Color	Percent	Area (S.F.)
	9.35	65.46
	5.82	40.75
	9.99	69.94
	15.79	110.54
	59.04	413.31

DETERIORATION - BRIDGE DECK

Color	Percent	Area (S.F.)
	8.21	636.94
	8.05	624.54
	13.08	1014.43
	27.69	2147.46
	42.97	3332.62

DETERIORATION - FORWARD APPROACH SLAB

Color	Percent	Area (S.F.)
	14.05	98.33
	14.79	103.52
	20.49	143.42
	30.66	214.63
	20.01	140.10




FIGURE 1



6350 Presidential Gateway
 Columbus, Ohio 43231
 Telephone: (614) 823-4949
 Fax Number: (614) 823-4990

Pavement Core Data Summary

PROJECT	ODOT D 6 Task 6-U May 2014
LOCATION	Lockbourne Road FRA 270 50.90
JOB No.	W-13-144
BORING/CORE No.	C-3
DATE CORE OBTAINED	5/8/2014

Core Composition						Comments/Remarks		
Core Number	Lift Thickness (in.)	Asphalt		Overlay Concrete	Concrete	Other		
C-3	2.50			✓			- A few minor voids in the overlay lift of the core and also in the concrete lift of the core	
	3.50				✓			

Total Pavement Thickness = 6.00 in. Total Overlay Thickness = 2.50 in. Total Concrete Thickness = 3.50 in. Total Base Thickness = 0.00 in.





6350 Presidential Gateway
 Columbus, Ohio 43231
 Telephone: (614) 823-4949
 Fax Number: (614) 823-4990

Pavement Core Data Summary

PROJECT	ODOT D 6 Task 6-U May 2014
LOCATION	Lockbourne Road FRA 270 50.90
JOB No.	W-13-144
BORING/CORE No.	C-4
DATE CORE OBTAINED	5/8/2014

Core Composition						Comments/Remarks	
Core Number	Lift Thickness (in.)	Asphalt		Overlay Concrete	Concrete	Other	
C-4	3.25			✓			
	3.25				✓		

- Trace air voids evident in both sections of the core
 - 3/4 inch rebar evident 4 inches from top of core

Total Pavement Thickness = 6.50 in. Total Overlay Thickness = 3.25 in. Total Concrete Thickness = 3.25 in. Total Base Thickness = 0.00 in.

