

PAVEMENT CALC SHEET 1

ITEM_CODE 202E23000 202E23010 304E20000 452E16060 204E45000 206E10500 206E11000 206E15010
 ADDITIONAL_DESCRIPTION
 TYPICAL SECTION LEGEND NUMBER 5 8
 RATE / THICKNESS / ETC 0.17

STATION RANGE	TYPICAL SECTION	SIDE	DISTANCE (D)	AVERAGE WIDTH (W)	SURFACE AREA (A) A=DXW/9	CADD GENERATED AREA	202	202	304	452	204	206	206	206									
							PAVEMENT REMOVED	PAVEMENT REMOVED, ASPHALT		AGGREGATE BASE	13.5" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC1 WITH QC/QA	PROOF ROLLING	CEMENT	CURING COAT	CEMENT STABILIZED SUBGRADE, 12 INCHES DEEP								
			FT	FT	SY	SY	SY	SY	CY	SY	SY	TON	SY	SY									
	TO																						
74+50.00		81+56.96	CONC	706.96		1857.22	1857.22																
74+50.00		81+56.96	INSIDE	706.96		261.89		261.89															
74+50.00		81+56.96	OUTSIDE	706.96		828.56		828.56															
74+50.00		81+34.43	EOS	684.43		4574.44			4574.44														
74+50.00		81+34.43	6" OFFSET	684.43		4650.33			775.06														
74+50.00		81+34.43	6" OFFSET	684.43		4726.11						140.37	4726.11	4726.11									
81+34.43		81+64.48	6" OFFSET	30.05	0.00	227.89			37.98														
81+34.43		81+64.48	6" OFFSET	30.05	0.00	231.22						6.87	231.22	231.22									
84+77.01		85+07.06	6" OFFSET	30.05	0.00	227.89			37.98														
84+77.01		85+07.06	6" OFFSET	30.05	0.00	231.22						6.87	231.22	231.22									
84+84.09		94+00.00	CONC	915.91	0.00	2437.89	2437.89																
84+84.09		94+00.00	INSIDE	915.91	0.00	283.44		283.44															
84+84.09		94+00.00	OUTSIDE	915.91	0.00	1080.89		1080.89															
85+07.06		94+00.00	EOS	892.94	0.00	6031.11			6031.11														
85+07.06		94+00.00	6" OFFSET	892.94	0.00	6096.11			1016.02														
85+07.06		94+00.00	6" OFFSET	892.94	0.00	6193.89						183.96	6193.89	6193.89									
SUBTOTALS							4295.11	2454.78		1867.04	10605.56		338.06	11382.44	11382.44								
TOTALS CARRIED TO GENERAL SUMMARY							4296	2455		1868	10606		339	11383	11383								

Northbound Full Depth Concrete Pavement