

I:\ProjectData\GAL\104975_GAL-141-8.85\Design\Roadway\Sheets\104975_cc001.dgn Sheet 4/3/2020 2:20:29 PM jwiseman

SHEET NUM.								PART.		ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.	CALCULATED JDW	CHECKED ARM
3	4	5	7	8			01/STR/OT										
								LUMP	201	11000	LS		ROADWAY	3			
				334				334	202	75001	334	FT	CLEARING AND GRUBBING	3			
			5,874					5,874	203	10000	5,874	CY	FENCE REMOVED, AS PER PLAN	3			
													EXCAVATION				
								LUMP	208	10000	LS		PRE-BLAST CONDITION SURVEY				
								LUMP	208	12000	LS		BLASTING CONSULTANT				
								LUMP	208	13000	LS		AIR BLAST AND NOISE CONTROL				
								LUMP	208	14000	LS		VIBRATION CONTROL AND MONITORING				
													EROSION CONTROL				
			3,355					3,355	659	00541	3,355	SY	SEEDING AND MULCHING, CLASS 3C, AS PER PLAN	3			
0.5								0.5	659	20000	0.5	TON	COMMERCIAL FERTILIZER				
0.7								0.7	659	31000	0.7	ACRE	LIME				
18.2								18.2	659	35000	18.2	MGAL	WATER				
								5,000	832	30000	5,000	EACH	EROSION CONTROL				
													PAVEMENT				
			155					155	407	20000	155	GAL	NON-TRACKING TACK COAT				
			152					152	408	10000	152	GAL	PRIME COAT				
			81					81	441	50000	81	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22				
			32					32	617	10100	32	CY	COMPACTED AGGREGATE				
													TRAFFIC CONTROL				
			22					22	621	00100	22	EACH	RPM				
			22					22	621	54000	22	EACH	RAISED PAVEMENT MARKER REMOVED				
			0.32					0.32	642	00104	0.32	MILE	EDGE LINE, 6", TYPE 1				
			0.16					0.16	642	00300	0.16	MILE	CENTER LINE, TYPE 1				
													MAINTENANCE OF TRAFFIC				
								1	SPECIAL	61411300	1	EACH	WORK ZONE TRAFFIC SIGNAL	4			
		2						2	614	12338	2	EACH	WORK ZONE IMPACT ATTENUATOR (BIDIRECTIONAL)				
	1							1	614	12740	1	EACH	WORK ZONE LIGHTING SYSTEM				
		13						13	614	13310	13	EACH	BARRIER REFLECTOR, TYPE 1 (BIDIRECTIONAL)				
		13						13	614	13360	13	EACH	OBJECT MARKER, TWO WAY				
		6						6	614	18601	6	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	4			
		0.16						0.16	614	22010	0.16	MILE	WORK ZONE EDGE LINE, CLASS I, 6"				
		22						22	614	26000	22	FT	WORK ZONE STOP LINE, CLASS I				
			620					620	622	41000	620	FT	PORTABLE BARRIER, 32"				
													INCIDENTALS				
								LUMP	103	05000	LS		PREMIUM FOR CONTRACT PERFORMANCE BOND AND FOR PAYMENT BOND				
								LUMP	614	11000	LS		MAINTAINING TRAFFIC				
								LUMP	623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING				
								LUMP	624	10000	LS		MOBILIZATION				

GENERAL SUMMARY

GAL - 141 - 8.85