

**Utility Note**  
**GAL-7-19,94**  
**PID #115533**

Bidders are advised that the following utility facilities will remain in place or be relocated within the construction limits of the project as set out below. All station locations listed below are approximate unless otherwise stated.

**American Electric Power**

The power company has an existing aerial line that parallels the entire project work limits on the west side of the roadway

- This line will remain in place and energized during construction

**AT&T**

The phone company has an existing buried fiber and copper lines that parallel the entire project work limits on the west side of the roadway.

- The location and depth of these lines will be verified and if they present a conflict, they will be relocated outside work limits and closer to the right of way line

**Suddenlink**

The cable company has existing buried lines that parallel the entire project work limits on the west side of the roadway, at 32-35ft from centerline of roadway.

- The location and depth of these lines will be verified and if they present a conflict, they will be relocated outside work limits and closer to the right of way line.

**City of Gallipolis – water**

The city has an existing 6” asbestos cement water line that parallels the entire project work limits on the west side of the roadway, at approximately 3ft from edge line of roadway and at a depth of 3-5ft from existing ground.

- The water line will conflict with the culvert replacement and will be relocated outside project work limits and closer to the right of way line. Due to the line being asbestos, the City of Gallipolis will be required to cut and remove any abandoned sections that are located within project work limits.

**GENERAL COMMENTS**

Sections 105.07 and 107.16 of the Department of Transportation Construction and Materials Specifications require, among other things, that the contractor cooperate with all utilities located within the limits of this construction project and take responsibility for the protection of the utility property and services.

This note is to advise bidders of all relocated and / or remaining power line locations within the project work limits. The contractor shall comply with all OSHA power line safety regulations and ensure proper equipment and / or OSHA recommended procedures are used to comply with power line clearance distances.