SHEET NUM.												PART.		ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
3	5		7	9	10	13	14		32			01/NFP/PV							
																		MAINTENANCE OF TRAFFIC	
					80							80		614	11110	80	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	
				10								10		614	12460	10	EACH	WORK ZONE MARKING SIGN	
				10								10		614	13000	10	CY	ASPHALT CONCRETE FOR MAINTAINING TRAFFIC	
					4							4		614	18601	4	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	
				11.7								11.7		614	21100	11.7	MILE	WORK ZONE CENTER LINE, CLASS I, 642 PAINT	
				5.85								5.85		614	21550	5.85	MILE	WORK ZONE CENTER LINE, CLASS III, 642 PAINT	
				11.7								11.7		614	22110	11.7	MILE	WORK ZONE EDGE LINE, CLASS I, 6", 642 PAINT	
				11.7								11.7		614	22360	11.7	MILE	WORK ZONE EDGE LINE, CLASS III, 6", 642 PAINT	
				113								113		614	26200	113	FT	WORK ZONE STOP LINE, CLASS I, 642 PAINT	
				113								113		614	26610	113	FT	WORK ZONE STOP LINE, CLASS III, 642 PAINT	
				530								530		614	27200	530	FT	WORK ZONE CROSSWALK LINE, CLASS I, 642 PAINT	
				530								530		614	27620	530	FT	WORK ZONE CROSSWALK LINE, CLASS III, 642 PAINT	
				2								2		614	31200	2	EACH	WORK ZONE WORD ON PAVEMENT, 72", CLASS I, 642 PAINT "XING"	
				2								2		614	31620	2	EACH	WORK ZONE WORD ON PAVEMENT, 72", CLASS III, 642 PAINT "XING"	
				300								300		630	97800	300	SF	SIGNING, MISC.: ADDITIONAL SIGNS, GROUND MOUNTED, AS DIRECTED BY THE ENGINEER	
																		INCIDENTALS	
												LS		614	11000	LS		MAINTAINING TRAFFIC	
6												6		619	16011	6	MNTH	FIELD OFFICE, TYPE B, AS PER PLAN	3
												LS		623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
												LS		624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

DESIGN AGENCY

DESIGNER JAG

REVIEWER EMK 08/30/21

PROJECT ID 100751

SHEET P.12 | TOTAL P.31

GEA-322-14.47

ADDENDUM_R1

MODEL: Sheet PAPERSIZE: 17x11 (in.) DATE: 11/23/2021 TIME: 8:59:20 AM USER: jgmovse
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 12\Geauga\100751\1400-Engineering\Roadway\Sheets\100751_GG002.dgn